## TM 3-34.47(FM 5-426/3 Oct 95)/MCRP 3-17.7C

### **CARPENTRY**

## September 2013

Publication of TM 3-34.47, 20 September 2013, supersedes FM 5-426, *Carpentry*, 3 October 1995. This special conversion to the TM publishing medium/nomenclature has been accomplished to comply with TRADOC doctrine restructuring requirements. The title and content of TM 3-34.47 is identical to that of the superseded FM 5-426.

This special conversion does not integrate any changes in Army doctrine since December 2009 and does not alter the publication's original references; therefore, some sources cited in this TM may no longer be current. For the status of official Department of the Army (DA) publications, consult DA Pam 25-30, Consolidated Index of Army Publications and Blank Forms, at <a href="http://armypubs.army.mil/2530.html">http://armypubs.army.mil/2530.html</a>. DA Pam 25-30 is updated as new and revised publications, as well as changes to publications are published. For the content/availability of specific subject matter, contact the appropriate proponent.

DISTRIBUTION RESTRICTION: Approved for public release; distribution is unlimited.

# HEADQUARTERS, DEPARTMENT OF THE ARMY

This publication is available at Army Knowledge Online (https://armypubs.us.army.mil/doctrine/index.html).

To receive publishing updates, please subscribe at http://www.apd.army.mil/AdminPubs/new\_subscribe.asp.

Technical Manual No. 3-34.47/Marine Corps Reference Publication 3-17.7C

Headquarters Department of the Army Washington, DC, 20 September 2013

# **CARPENTRY**

## **Contents**

		Page
	PREFACE	ix
Chapter 1	CONSTRUCTION DRAWINGS	1-1
-	Architectural Symbols, Line Conventions, and Material Conventions	1-1
	Working Drawings	1-5
	Site Plans	1-6
	Elevations	1-6
	Floor Plans	1-8
	Detail Drawings	1-11
	Sections	
	Details	
	Wood Framing Drawings	1-15
Chapter 2	CONSTRUCTION PLANNING AND MATERIALS	2-1
	Planning	2-1
	Materials	2-3
Chapter 3	BILLS OF MATERIALS	3-1
•	Materials Takeoff List	3-1
	Materials Estimate List	3-3
	Bill Of Materials Format	3-3
Chapter 4	BUILDING LAYOUT AND FOUNDATION	4-1
	Layout	
	Foundations	
Chapter 5	FORMS FOR CONCRETE	5-1
Onapier o	Form Design	_
	Form Construction	
Chanter C		
Chapter 6	ROUGH FRAMING	_
	Types Of Framing Connections	
	COHIECTIONS	0-4

DISTRIBUTION RESTRICTION: Approved for public release; distribution is unlimited.

	Sills	6-10
	Girders	6-11
	Flooring	
	Walls And Partitions	
	Ceilings	
	Wall Openings	
	Stairways	
Chapter 7	ROOF SYSTEMS AND COVERINGS	
	Roof Framing	
	Trusses	
	Roof Openings Roof Decking	
	Roof Coverings	
	Reroofing	
Chapter 8	DOORS AND WINDOWS	
Chapter 6	Doors	
	Windows	
	Accessories	
Chapter 9	FINISH CARPENTRY	9-1
	Interior Wall And Partition Coverings	
	Base Molding	9-9
	Ceiling Coverings	9-12
	Ceiling Moldings	9-14
Chapter 10	NONSTANDARD FIXED BRIDGE	10-1
	Bridge Classification	10-1
	Substructure	
	Superstructure	10-11
Chapter 11	TIMBER-PILE WHARVES	11-1
	Types Of Wharves	
	Types Of Piles	
	Installation Of Piles	
	Wharf Superstructure	
	Docking Hardware	
Appendix A	CONVERSION TABLES	
Appendix B	CARPENTRY ABBREVIATIONS AND SYMBOLS	B-1
Appendix C	MANPOWER ESTIMATES	C-1
Appendix D	GENERAL INFORMATION	D-1
	GLOSSARY	Glossary-1
	REFERENCES	References-1
	INDEX	Index-1

# **Figures**

Figure 1-1. Window symbols	1-1
Figure 1-2. Door symbols	1-2
Figure 1-3. Line conventions	1-3
Figure 1-4. Typical wall symbols	1-5
Figure 1-5. Typical site plan	1-7
Figure 1-6. Elevation views	1-8
Figure 1-7. Floor-plan development	1-9
Figure 1-8. Typical floor plan	1-10
Figure 1-9. Typical wall section	1-13
Figure 1-10. Typical eave, door, and window details	1-14
Figure 1-11. Stairway and steps	1-15
Figure 1-12. Typical foundation wall, post, footing, and girder details	1-17
Figure 1-13. Light framing details (20-foot-wide building)	1-18
Figure 1-14. Floor framing details (20-foot-wide building)	1-19
Figure 1-15. Typical wall-panel framing details	1-20
Figure 1-16. Trussed-rafter details	1-21
Figure 1-17. W-truss	1-22
Figure 1-18. Roof trusses	1-23
Figure 2-1. Template for framing walls	2-2
Figure 2-2. Marking a pattern	2-3
Figure 2-3. Examples of board-feet computations	2-7
Figure 2-4. Types of nails	2-8
Figure 2-5. Sizes of cut nails	2-9
Figure 2-6. Specialized nails	2-10
Figure 2-7. Wood screws	2-13
Figure 2-8. Sinking a wood screw properly	2-14
Figure 2-9. Lag screws	2-14
Figure 2-10. Sheet-metal screws	2-15
Figure 2-11. Carriage bolts	2-16
Figure 2-12. Machine bolts	2-17
Figure 2-13. Stove bolts	2-18
Figure 2-14. Expansion bolt and shield	2-18
Figure 2-15. Driftpins	2-19
Figure 2-16. Corrugated fasteners	2-19
Figure 2-17. Proper use of corrugated fasteners	2-20
Figure 2-18. Split-ring installation	2-21
Figure 2-19. Toothed-ring installation	2-21
Figure 3-1. 20- x 40-foot TO building substructure	
Figure 3-2. Sample DA Form 2702	3-4

Figure 4-1. Laying out a rectangle	4-2
Figure 4-2. Laying out irregular projects	4-3
Figure 4-3. Locating batter boards	4-4
Figure 4-4. Laying out building lines from batter boards	4-6
Figure 4-5. Foundation walls	4-7
Figure 4-6. Columns and posts	4-8
Figure 4-7. Posts with braces	4-9
Figure 5-1. Typical large footing form	5-3
Figure 5-2. Typical small footing form	5-3
Figure 5-3. Footing and pier form	5-4
Figure 5-4. Wall-footing forms	5-4
Figure 5-5. Concrete wall form	5-5
Figure 5-6. Constructing wall panels	5-6
Figure 5-7. Removing wood spreaders	5-7
Figure 5-8. Wire ties for form walls	5-8
Figure 5-9. Tie rod and spreader combination	5-9
Figure 5-10. Wall form for curtain walls	5-9
Figure 5-11. Column and footing form	5-10
Figure 5-12. Beam and girder forms	5-10
Figure 5-13. Beam, column and floor plan	5-11
Figure 5-14. Floor slab form	5-12
Figure 5-15. Stairway slab form	5-13
Figure 6-1. Framing for light structures	6-2
Figure 6-2. Light-framing details	6-3
Figure 6-3. Heavy-framing details	6-4
Figure 6-4. Butt joints	6-5
Figure 6-5. Lap joints	6-7
Figure 6-6. Splices	6-8
Figure 6-7. Splice stresses	6-9
Figure 6-8. Types of sills	6-10
Figure 6-9. Corner joint of a built-up sill	6-11
Figure 6-10. Built-up girder details	6-12
Figure 6-11. Joist-to-girder attachment	6-13
Figure 6-12. Girder load area	6-17
Figure 6-13. Built-up girder lumber arrangement	6-17
Figure 6-14. Butt and half-lap joints	
Figure 6-15. Use of metal cap and masonry footing	6-19
Figure 6-16. Column spacing	
Figure 6-17. Girder and beam form	6-20
Figure 6-18. Floor joists	
Figure 6-19. Reinforced joists	

Figure 6-20. Sill and joist connections	. 6-23
Figure 6-21. Top plates and ledgers	. 6-24
Figure 6-22. Type of bridging	. 6-25
Figure 6-23. Floor openings	. 6-27
Figure 6-24. Double headers and trimmers	6-28
Figure 6-25. Floor-opening construction	. 6-28
Figure 6-26. Subfloor	6-30
Figure 6-27. Square-edged and tongue-and-groove finish flooring	. 6-31
Figure 6-28. Typical wall-frame details	. 6-32
Figure 6-29. Typical wall construction	. 6-33
Figure 6-30. Corner-post construction using ordinary 2 x 4 studs	. 6-34
Figure 6-31. Alternate corner-post construction using ordinary 2 x 4 studs	. 6-34
Figure 6-32. Corner-post construction using both 2-inch and 4-inch lumber	. 6-35
Figure 6-33. T-Post construction	. 6-36
Figure 6-34. Partition posts	. 6-37
Figure 6-35. Door and window framing	. 6-38
Figure 6-36. Top-plate and sole-plate construction	. 6-39
Figure 6-37. Types of wall bridging	. 6-40
Figure 6-38. Plumbing a post	. 6-41
Figure 6-39. Straightening a wall	. 6-42
Figure 6-40. Three methods of bracing	. 6-43
Figure 6-41. Horizontal and diagonal sheathing	. 6-44
Figure 6-42. Gypsum and plywood sheathing	. 6-45
Figure 6-43. Vertical and horizontal wood siding	. 6-46
Figure 6-44. Vinyl and aluminum sidings	. 6-48
Figure 6-45. Built-up plate supporting joist and roof rafters	. 6-50
Figure 6-46. One method of bracing attic plate	. 6-50
Figure 6-47. Framing for stovepipe	6-51
Figure 6-48. Installing stovepipe	. 6-52
Figure 6-49. Types of ventilators	. 6-53
Figure 6-50. Typical stairway	6-54
Figure 6-51. Step construction	. 6-54
Figure 6-52. Complete stairway detail	. 6-55
Figure 7-1. Types of roofs	7-1
Figure 7-2. Framing a roof	7-2
Figure 7-3. Common roof-framing terms	7-2
Figure 7-4. Roofing terms	7-4
Figure 7-5. Use of framing square	7-5
Figure 7-6. Determining roof pitch	7-5
Figure 7-7. Collar tie or beam	7-6
Figure 7-8. Scale or measurement method	7-7

Figure 7-9. Step-off method	7-8
Figure 7-10. Rafter table, type 1	7-10
Figure 7-11. Rafter table, type 2	7-10
Figure 7-12. Types of trusses	7-12
Figure 7-13. Truss terms	7-13
Figure 7-14. Knee braces	7-13
Figure 7-15. Truss layout	7-14
Figure 7-16. Truss assembly	7-15
Figure 7-17. Assembling a typical truss	7-15
Figure 7-18. Truss- or rafter-support detail	7-17
Figure 7-19. Laying out and assembling with a template	7-18
Figure 7-20. Erecting rafter trusses	7-19
Figure 7-21. Temporary bracing	7-20
Figure 7-22. Roof-opening construction	7-20
Figure 7-23. Square-butt asphalt strip shingle	7-21
Figure 7-24. Laying an asphalt-shingle roof	7-22
Figure 7-25. Laying out a pattern	7-22
Figure 7-26. Hip or ridge flashing	7-23
Figure 7-27. Open-valley flashing	7-23
Figure 7-28. Open-valley flashing details using roll roofing	7-24
Figure 7-29. Vertical wall flashing	7-24
Figure 7-30. Roof replacement	7-27
Figure 7-31. Open-valley flashing	7-28
Figure 7-32. Closed-valley flashing using woven strip shingles	7-29
Figure 7-33. Smooth-surfaced roll roofing	7-31
Figure 8-1. Types of doors	8-1
Figure 8-2. Mill-built doors	8-3
Figure 8-3. Principal parts of a door frame	8-4
Figure 8-4. Types of door frames	8-5
Figure 8-5. Single outside door	8-6
Figure 8-6. Single inside door	8-7
Figure 8-7. Door jambs	8-8
Figure 8-8. Jam allowances	8-9
Figure 8-9. Hanging a door	8-11
Figure 8-10. Door butt (hinge)	8-12
Figure 8-11. Installing door butts (hinges)	8-13
Figure 8-12. Door trim and stop	8-14
Figure 8-13. Installing lock and strike plate	8-15
Figure 8-14. Types of windows	8-16
Figure 8-15. Window frame and sash details	8-17
Figure 8-16 Door screen construction	8-18

Figure 8-17. Door screen sizes	8-19
Figure 8-18. Hood or canopy details	8-20
Figure 9-1. Hanging sheetrock and wood panels	9-2
Figure 9-2. Fitting wall panels to uneven walls	9-3
Figure 9-3. Sheetrock applied vertically	9-5
Figure 9-4. The double-nailing system for installing sheetrock	9-5
Figure 9-5. Cutting sheetrock	9-7
Figure 9-6. Types of base molding	9-10
Figure 9-7. Installing base molding	9-10
Figure 9-8. Trim lap-miter joint	9-11
Figure 9-9. Base-shoe trimming	9-12
Figure 9-10. Brace for holding ceiling panels	9-13
Figure 9-11. Furring strips on ceiling joists	9-14
Figure 9-12. Ceiling molding	9-14
Figure 10-1. Nonstandard fixed highway bridge	10-1
Figure 10-2. Timber sill abutment	10-2
Figure 10-3. Pile abutment and retaining wall	10-2
Figure 10-4. Pile bent and trestle bent	10-3
Figure 10-5. Pile-bent pier	10-4
Figure 10-6. Trestle-bent pier	10-5
Figure 10-7. Crib pier	10-6
Figure 10-8. Bracing	10-7
Figure 10-9. Laying out a centerline	10-8
Figure 10-10. Abutment and retaining wall	10-9
Figure 10-11. Retaining-wall details	10-10
Figure 10-12. Determining trestle-bent height	10-11
Figure 10-13. Stringer placement	10-12
Figure 10-14. Fastening stringers	10-13
Figure 10-15. Open laminated deck, sectional view	10-14
Figure 10-16. Open laminated deck	10-15
Figure 10-17. Solid-plank deck	10-16
Figure 10-18. Extended deck for handrail support	10-16
Figure 10-19. Tread placement	10-17
Figure 10-20. Standard curb and handrail	10-18
Figure 11-1. Common wharves	11-2
Figure 11-2. Logger's tools	11-3
Figure 11-3. Realigning with a block and tackle	11-3
Figure 11-4. Realigning with a jet	11-4
Figure 11-5. Realigning with a frame	11-4
Figure 11-6. Floating template	11-5
Figure 11-7. Cutting piles	11-6

F: 44.0.0 : 11.11	44 7
Figure 11-8. Capping and bracing piles	
Figure 11-9. Transverse bracing for different size piles	
Figure 11-10. Stringers and decking in place	
Figure 11-11. Wharf-edge cross-section of a timber-pile wharf	
Figure 11-12. Typical pile dolphin	
Figure 11-13. Typical dolphin plan views	
Figure 11-14. Mooring hardware	
Figure 11-15. Timber grillwork	
Figure 11-16. Mooring hardware over bearing pile	11-16
Tables	
Table 2-1. Nominal and dressed sizes of lumber	
Table 2-2. Sizes, types, and uses of nails	
Table 2-3. Screw sizes and dimensions	
Table 2-4. Drill and auger bit sizes	
Table 2-5. Lag-screw sizes	2-14
Table 2-6. Carriage-bolt sizes	2-16
Table 2-7. Machine-bolt sizes	2-17
Table 3-1. Materials takeoff list for a 20- x 40-foot building	3-2
Table 3-2. Materials estimate list	3-3
Table 6-1. Sizes of built-up wood girders	6-14
Table 6-2. Allowable spans for floor joists using nonstress-graded lumber	6-24
Table 6 3. Group classification—nonstress-graded lumber	6-25
Table C-1. Rough framing	C-1
Table C-2. Sheathing and siding	C-2
Table C-3. Insulation	C-2
Table C-4. Finish carpentry	C-3
Table C-5. Door installation	C-4
Table C-6 Flooring	C-5
Table C-7. Window installation	C-5
Table C-8. Built-up roofing, insulation, and flashing	C-6
Table C-9. Roll roofing	C-6
Table C-10. Shingle roofing	C-7
Table C-11. Metal, asbestos-cement, and tile roofing (pitch at least 3 inches per foot.)	C-7
Table C-12. Pile bracing and capping	
Table C-13. Pier framing	
Table C 14 Dock bardware	O-0

### **Preface**

This manual is intended for use as a training guide and reference text for engineer personnel responsible for planning and executing theater of operations (TO) construction. It provides techniques and procedures for frame construction, preparation and use of bill of materials (BOMs), building layout, formatting for concrete slabs and foundations, framing and finish carpentry, roof framing and coverings, bridge and wharf construction, and the materials used for these operations.

The proponent for this publication is the United States Army Engineer School (USAES). Submit changes for improvement on Department of the Army (DA) Form 2028 (Recommended Changes to Publications and Blank Forms) to Commandant, United States (US) Army Engineer School, ATTN: ATSE-TD-D, Fort Leonard Wood, Missouri 65473-6650.

Unless this publication states otherwise, masculine nouns and pronouns do not refer exclusively to men.

This page intentionally	y left blank.	

#### Chapter 1

## **Construction Drawings**

Before the carpenter can begin his work, he must have a complete set of construction drawings or prints. He must be familiar with how the drawings are prepared. He should also know how to read the drawings so that he will understand what he must do to comply with their requirements. This chapter will help the carpenter to reach that understanding

# ARCHITECTURAL SYMBOLS, LINE CONVENTIONS, AND MATERIAL CONVENTIONS

- 1-1. The plan for a building must give all the details necessary to construct the building. Therefore, it usually consists of a collection of sheets, called a *set of plans*. Each sheet shows the details of a different phase or part of the construction. Several of the sheets will be devoted to floor plans. Other sheets in the set will show construction details (such as wiring, plumbing, and air-conditioning details and types and quantities of materials). Refer to appendix A for conversion tables.
- 1-2. Architectural symbols on construction drawings show the type and location of windows (figure 1-1), doors (figure 1-2), and other features. They show the general shape of an actual architectural feature and show any motion that is supposed to occur.





Figure 1-1. Window symbols






Figure 1-2. Door symbols

1-3. *Line conventions* are different types and weights of lines used to represent the features of an object. The meaning of a line with certain characteristics has been standardized and will be the same on any drawing. These line conventions must be understood in order to read drawings. The line conventions most often encountered in construction prints are shown and described in figure 1-3.

NAME	CON- VENT- ION	DESCRIPTION AND APPLICATION	EXAMPLE
VISIBLE LINES		HEAVY, UNBROKEN LINES, USED TO INDICATE VISIBLE EDGES OF AN OBJECT.	0[
HIDDEN LINES		MEDIUM LINES WITH SHORT, EVENLY SPACED DASHES. USED TO INDICATE CONCEALED EDGES.	
CENTER LINES		THIN LINES MADE UP OF LONG AND SHORT DASHES ALTERNATELY SPACED AND CONSISTENT IN LENGTH. USED TO INDICATE SYMMETRY ABOUT AN AXIS AND LOCATION OF CENTERS.	<b>\$</b>
DIMENSION LINES		THIN LINES TERMINATED WITH ARROWHEADS AT EACH END. USED TO INDICATE DISTANCE MEASURED.	
EXTENSION LINES		THIN, UNBROKEN LINE. USED TO INDICATE EXTENT OF DIMENSIONS.	
LEADER		THIN LINE TERMINATED WITH ARROWHEAD OR DOT AT ONE END. USED TO INDICATE A PART, DIMENSION, OR OTHER REFERENCE.	2 tx50 nvc

Figure 1-3. Line conventions

NAME	CON- VENT ION	DESCRIPTION AND APPLICATION	EXAMPLE
PHANTOM OR DATUM LINE		MEDIUM SERIES OF ONE LONG DASH AND TWO SHORT DASHES EVENLY SPACED ENDING WITH LONG DASH. USED TO INDICATE: ALTERNATE POSITION OF PARTS, REPEATED DETAIL, OR A DATUM PLANE.	5
STITCH LINE		MEDIUM LINE OF SHORT DASHES. EVENLY SPACED AND LABELED. USED TO INDICATE STITCHING OR SEWING.	- since
BREAK (LONG)	^	THIN, SOLID RULED LINE WITH FREE-HAND ZIGZAGS. USED TO REDUCE SIZE OF DRAWING REQUIRED TO DELINEATE OBJECT AND REDUCE DETAIL.	<del></del>
BREAK (SHORT)	~~~	THICK, SOLID FREE-HAND LINES. USED TO INDICATE A SHORT BREAK.	
CUTTING OR VIEWING PLANE— VIEWING PLANE OPTIONAL	T T LJ	THICK, SHORT DASHES. USED TO SHOW OFFSET WITH ARROWHEADS TO SHOW DIRECTION IN WHICH SECTION OR PLANE IS VIEWED OR TAKEN.	<b>€</b>
CUTTING PLANE FOR COMPLEX OR OFFSET VIEWS	?	THICK, SHORT DASHES. USED TO SHOW OFFSET WITH ARROWHEADS TO SHOW DIRECTION VIEWED.	

Figure 1-3. Line conventions (continued)

- 1-4. *Material conventions* are symbols that show the type of material used in the structure. The symbol selected normally represents the material in some way; for example, the symbol for wood shows the grain in the wood. (However, it is not always possible to use a common characteristic of the material for the symbol.) (Appendix B gives the symbols for the most common types of materials.)
- 1-5. Figure 1-4 shows typical exterior and interior wall symbols. (Note how the material conventions are used in the makeup of the symbols for masonry, brick, and concrete walls.)
- 1-6. The carpenter should know all of the symbols for materials to help him read a construction drawing. A symbol on a drawing should always be checked if there is any doubt about its meaning. Refer to appendix B for common abbreviations and symbols.




Figure 1-4. Typical wall symbols

#### **WORKING DRAWINGS**

1-7. Working drawings and specifications are the main sources of information for supervisors and technicians responsible for the actual construction. The construction working drawing gives a complete graphic description of the structure to be erected and the construction method to be followed.

1-8. A set of working drawings includes both general and detail drawings. General drawings consist of plans and elevations; detail drawings consist of sections and detail views.

#### SITE PLANS

- 1-9. A site plan (also called a *plot plan*) shows—
  - Property lines and locations.
  - Contours and profiles.
  - Building lines.
  - Locations of structures to be built.
  - Existing structures.
  - Approaches.
  - Finished grades.
  - Existing and new utilities (such as sewer, water, and gas).
- 1-10. Figure 1-5 shows a typical site plan. Appropriate outlines show the location of each building. The new facility can be located by referring to the schedule of facilities on the plan. The site plan has a north-pointing arrow to indicate site north—not magnetic north. Each facility has a number (or code letter) to identify it in the schedule of facilities. The contour lines show the elevation of the earth surfaces. (All points on a contour have the same elevation.)
- 1-11. Distances are given between principal details and reference lines. (The coordinate reference lines on the figure are centerlines of the roads surrounding the area.) All distances in a plan view simply give the horizontal measurement between two points; they do not show terrain irregularities. (The sizes of proposed facilities are given in the schedule of facilities.)
- 1-12. Examine the site plan shown in figure 1-5 to see what information can be obtained from it. For example, the contour lines show that the ground surface of the site area slopes. The location and identification of each facility are given. Most of the facilities are spaced at least 60 feet apart, but the library (facility No. 3) and the recreation building (facility No. 4) are only 15 feet apart. The library is the smallest of the four buildings and is closest to the road- the east wall of the library is 20 feet from the centerline of the road, while the other buildings are 30 or 60 feet from the centerline.

#### **ELEVATIONS**

- 1-13. Elevations are drawings that show the front, rear, or side view of a building or structure. Sample elevation views are given in figure 1-6, page 1-8. Construction materials may be shown on the elevation. The ground level (called the grade) surrounding the structure may also be shown. When more than one view is shown on a drawing sheet, each view is given a title. If any view has a scale different from that shown in the title block, the scale is given beneath the title of that view.
- 1-14. The centerline symbol of alternate long and short dashes shows finished floor lines The hidden line symbol of short, evenly spaced dashes shows foundations below the grade line. Note that figure 1-6 shows the footings are below grade.
- 1-15. Elevations show the locations and types of doors and windows. Each different type of window shown in the elevations is marked; the three types of windows shown here are marked W-1, W-2, and W-3. These identifying marks refer to a particular size of window whose dimensions are given in a table known as the window schedule. In some cases, rough opening dimensions of windows are given on the drawing. Note that the building shown here has two double doors on each side and a double door at each end. The elevation also shows that at the end of the building with the loading platform, the door is at the level of the stage floor; all the other doors are at grade level.




Figure 1-5. Typical site plan




Figure 1-6. Elevation views

#### FLOOR PLANS

- 1-16. A floor plan is a cross-sectional view of a building. The horizontal cut crosses all openings regardless of their height from the floor. The development of a floor plan is shown in figure 1-7.
- 1-17. A floor plan may show, among other things, the outside shape of the building; the arrangement, size, and shape of the rooms; the type of material and the length, thickness, and character of the building walls at a particular floor; the type, width, and location of the doors and windows; the types and locations of utility installations; and the location of stairways. A typical floor plan is shown in figure 1-8, pages 1-10.
- 1-18. As you read the floor plan in figure 1-8, note the features of the recreation building. The lines with small circles show wiring for electrical outlets; appropriate symbols show the plumbing fixtures. These features are important to the carpenter from the standpoint of coordination. He may have to make special provisions, at various stages of construction, for the placement of electrical or plumbing fixtures. Installation of these fixtures should be coordinated at the appropriate time with the electrician, plumber, and foreman.
- 1-19. As you examine the floor plan, note that the interior of the building will consist of an auditorium, a lobby with a post exchange (PX) counter, a men's toilet, a women's toilet, a projection room on a second level above the lobby, two dressing rooms, and a stage. The stage may not be apparent but, by noting the steps adjacent to each dressing room, it can be seen that there is a change in elevation. (The elevation view, shown in Figure 1-6 shows the stage and its elevation.)
- 1-20. Note that on the floor plan (figure 1-8) all building entrance and exit doors are the same type (1D) and all windows are the double-hung type. All interior single doors are the same (2D), and two double doors (3D) open into the lobby from the auditorium. The projection room will be reached via a 15-riser stairway located in a 12- x 18-foot room. Entrance to this room will be from the auditorium through a

single door opening into the room. At the top of the stairway, a single door opens into the projection room. The wall of the projection room that faces the stage (inside wall) has three openings. Note that no windows are shown for the side of the building at the second level where the projection room is located, but windows are shown at the main level.




Figure 1-7. Floor-plan development




Figure 1-8. Typical floor plan




Figure 1-8. Typical floor plan (continued)

#### **DETAIL DRAWINGS**

1-21. Detail drawings are more specific than other types of construction plans. They are generally drawn on a larger scale and show features that do not appear on other plans.

#### **SECTIONS**

- 1-22. Sections are drawn to a large scale showing details of a particular construction feature that cannot be given in a general drawing. They show—
  - Height.

- Materials.
- Fastening and support systems.
- Any concealed features.
- 1-23. A typical wall section, with parts identified by name and/or size, is illustrated in figure 1-9. This figure shows how a structure looks when cut vertically by a cutting plane.
- 1-24. Wall sections are very important to construction supervisors and to the craftsmen who do the actual building. They show the construction of the wall, as well as the way in which structural members and other features are joined to it. Wall sections extend vertically from the foundation bed to the roof. Sections are classified as typical and specific.

#### TYPICAL SECTIONS

1-25. Typical sections are used to show construction features that are repeated many times throughout a structure.

#### SPECIFIC SECTIONS

1-26. When a particular construction feature occurs only once and is not shown clearly in the general drawing, a cutting plane is passed through that portion.

#### **DETAILS**

- 1-27. Details are large-scale drawings which show features that do not appear (or appear on too small a scale) on the plans, elevations, and sections. Sections show the builder how various parts are connected and placed. Details do not have a cutting-plane indication, but are simply noted by a code. The construction of doors, windows, and eaves is usually shown in detail drawings. Figure 1-10, page 1-14, shows some typical door framing details, window wood-framing details, and an eave detail for a simple type of cornice. Other details which are customarily shown are sills, girder and joint connections, and stairways.
- 1-28. Figure 1-11, page 1-15, shows how a stairway is drawn in a plan and how riser-tread information is given. For example, on the plan, DOVVN 17 RISERS followed by an arrow means that there are 17 risers in the run of stairs going to the first floor from the floor above, in the direction indicated by the arrow. The riser-tread diagram provides height and width information. The standard for the riser, or height from the bottom of the tread to the bottom of the next tread, ranges from 6 1/2 to 7 1/2 inches. The tread width is usually such that the sum of riser and tread is about 18 inches (a 7-inch riser and 11-inch tread is standard). On the plan, the distance between the riser lines is the width of the tread.




Figure 1-9. Typical wall section




Figure 1-10. Typical eave, door, and window details




Figure 1-11. Stairway and steps

#### WOOD FRAMING DRAWINGS

1-29. Framing plans show the size, number, and location of the structural members constituting the building framework. Separate framing plans may be drawn for the floors, walls, and roof. The floor framing plan must specify the sizes and spacing of joists, girders, and columns used to support the floor. Detail drawings are added, if necessary, to show the methods of anchoring joists and girders to the columns and foundation walls or footings. Wall framing plans show the location and method of framing openings and ceiling heights so that studs and posts can be cut. Roof framing plans show the construction of the rafters used to span the building and support the roof. Size, spacing, roof slope, and all necessary details are shown. Working prints for TO buildings usually show details of all framing.

#### LIGHT WOOD FRAMING

- 1-30. Light framing is used in barracks, bathhouses, administration buildings, light shops, hospitals, and similar structures.
- 1-31. Detailed drawings of foundation walls, footings, posts, and girder details normally used in standard TO construction are shown in figure 1-12, page 1-17.
- 1-32. The various details for overall framing of a 20-foot-wide building (including ground level, window openings, braces, splices, and nomenclature of framing) are shown in figure 1-13, page 1-18.
- 1-33. Figure 1-14, page 1-19, shows floor framing details showing footings, posts, girders, joists, reinforced sections of floor for heavy loads, section views covering makeup of certain sections, scabs for joint girders to posts, and post-bracing details as placed for cross sections and longitudinal sections. On a construction drawing, the type of footings and the size of the various members are shown. In some cases the lengths are given, while in others the BOM that accompanies the print specifies the required lengths of the various members.

- 1-34. Wall framing for end panels is shown in view A in figure 1-15, page 1-20. Wall framing plans are detail drawings showing the locations of studs, plates, sills, and bracing. They show one wall at a time. The height for panels is usually shown. From this height, the length of wall studs is determined by deducting the thickness of the top or rafter plate and the bottom plate. Studs placed next to window openings may be placed either on edge or flat, depending upon the type of windows used. Details for side panels (view B of figure 1-15) cover the same type of information as listed for end panels.
- 1-35. Chapter 6 covers the details of wall framing. The space between studs is given in the wall framing detail drawing, as well as the height of the girt from the bottom plate, and the types of door and window openings, if any. For window openings, the details specify whether the window is hinged to swing in or out, or whether it is to be a sliding panel.
- 1-36. Examples of drawings showing the makeup of various trussed rafters are given in figure 1-16, page 1-21. A 40-foot trussed rafter showing a partition bearing in the center is shown in view A. The drawing shows the splices required, bracing details, the stud and top plate at one end of the rafter, and the size of the members.
- 1-37. A typical detail drawing of a 20-foot trussed rafter is shown in view B of figure 1-16. Filler blocks are used to keep the brace members in a vertical plane, since the rafter and bottom chord are nailed together rather than spliced. The drawing shows placement of the rafter tie on the opposite side from the vertical brace. Usually the splice plate for the bottom chord (if one is needed) is placed on the side where the rafters are to be nailed so that it can serve also as a filler block.
- 1-38. A modified trussed rafter, shown in view C of figure 1-16, is used only when specified in plans for certain construction. It will not be used in areas subject to high wind velocities or moderate to heavy snowfall. In this type of trussed rafter, the bottom chord is placed on the rafters above the top plate.
- 1-39. The construction plans will specify the best type of trussed rafter for the purpose. The drawings must show, in detail, the construction features of the rafter selected.
- 1-40. Another type of truss is the W-truss, shown in figure 1-17, page 1-22. It may be used in either TO or residential construction, time permitting.




Figure 1-12. Typical foundation wall, post, footing, and girder details




Figure 1-13. Light framing details (20-foot-wide building)




Figure 1-14. Floor framing details (20-foot-wide building)




Figure 1-15. Typical wall-panel framing details




Figure 1-16. Trussed-rafter details




Figure 1-17. W-truss

#### **HEAVY WOOD FRAMING**

- 1-41. Heavy wood framing consists of framing members (timber construction) at least 6 inches in dimension (for example, 2 x 6 inches or 4 x 12 inches). Examples of this type of framing can be found in heavy roof trusses, timber-trestle bridges, and wharves.
- 1-42. The major differences between light and heavy framing are the size of timber used and the types of fasteners used. Fasteners for both light and heavy framing will be covered in chapter 2.
- 1-43. Note the similarities, as well as the differences, between the drawings for light and heavy wood framing. Figure 1-18 is a typical example of a drawing showing framing details for light and heavy roof trusses. Drawings for other types of heavy wood framing will similarly illustrate the kinds of material to be used and the way in which it is joined.




Figure 1-18. Roof trusses

This page intentionally	y left blank.	

## Chapter 2

# **Construction Planning and Materials**

Successful construction in the military TO demands a thorough familiarity with the materials used and the planning required to assemble these materials into a building—a building that is most suitable for the requirements, while most effectively fitting within the constraints imposed by the locality. This chapter acquaints the carpenter with those materials and with planning techniques.

## **PLANNING**

- 2-1. The importance of properly planning construction cannot be overemphasized. Construction planning allows an orderly series of operations and prevents duplication of effort and waste of materials. The major considerations in planning are—
  - The construction-plant layout.
  - The distribution of materials.
  - The number of skilled and semiskilled men available.
  - The number and type of units to be constructed.
- 2-2. From a list of the operations required, an estimate is made of the total number of man-hours needed. This estimate forms the basis for determining the number and type of men needed and for organizing the erection crew(s). (Refer to appendix C.) Arrangements for assembling the necessary materials at the job site and for the preliminary cutting and assembly are made in advance.
- 2-3. The method of erecting buildings directly influences the amount of time, labor, and materials needed. The methods may be divided into two types: the built-in-place method and the panel, *or preassembly (prefabricated)*, method. Working parties for both methods should be set up as follows:
  - The layout party.
  - The cutting party.
  - The assembling party (built-in-place method only).
  - The carrying party.
  - The erecting party for sidewalls.
  - The erecting party for rafters.
  - The sheathing party (built-in-place method only).
  - The roofing party.
  - The door-and-window party.
  - The finishing party.

## **BUILT-IN-PLACE METHOD**

- 2-4. In this method, each piece is separately erected in *its* proper place. When *using* the built-in-place method, the noncommissioned officer in charge (NCOIC) of construction divides the men into working parties, whose duties may be as follows:
  - Laying out the foundation.
  - Grading and excavating.
  - Laying out and cutting various sizes of material.

- Carrying material to the cutting and erecting parties.
- 2-5. If a party finishes its task before the building is completed, it is assigned a new task. For example, if the party laying out the foundation completes its work before erection of the building has begun, it is assigned a new duty (such as cutting rafters).
- 2-6. Parts of the building are built in the following order: footings, posts, sills, joists, floor, soles, studs, plates, girts, rafters, bracing, siding, sheathing, roofing, doors, windows, steps, and inside finish (if used).

#### PANEL METHOD

- 2-7. In this method (also called preassembly (prefabricated)), a complete section is built as a unit and then set in the building in its proper place. It is used extensively because it makes for greater speed, better control over working parties, and better use of manpower. For example, it allows the use of a standard list of sizes for each similar section. Standard plans shown in Technical Manuals (TMs) 5-02-1 and 5-302-2 further simplify construction. The panel method requires careful planning before the actual construction. Before measuring and cutting lumber, the number and size of sections that are alike should be determined from the construction drawing. This ensures availability of the correct numbers of each piece.
- 2-8. The carpenter assigns a crew to cut and assemble one section. (Several cutting and assembling parties may be used at one time on different types of sections.)
- 2-9. In most cases, a template (figure 2-1) is built as a guide for assembling the section. The template should be built square and should be correct in size.




Figure 2-1. Template for framing walls

2-10. The number and size of each piece in a section are given to the man in charge of the cutting party. The cutting party cuts the timber to the correct length with a handsaw or power saw. The length is measured with a square and a tape. After one piece has been cut, it may be used as a pattern for marking the remaining pieces (figure 2-2). The pattern is set up by nailing two blocks to the piece of correct size, one near each end, as shown in the figure. These blocks act as stops to hold the pattern in place on the timber to be marked.




Figure 2-2. Marking a pattern

- 2-11. The plate and sole are placed in the template with the studs and girts between them; then the door and window posts, if any, are placed as shown in figure 2-1. The girts, sole, and plate are nailed to the studs with 16d or 20d nails. If insulation board is used, it and the wall sheathing are put on the section before it is taken out of the template. Applying the wall finish before raising the section makes the use of scaffolds or ladders unnecessary.
- 2-12. The erecting party sets the sections into place, braces them temporarily, and nails them together. The end section should be first; it may be erected on graded earth. The sidewall sections are next; they should be erected so as to keep the two walls even. The rafter party can then place the rafters on the walls.
- 2-13. The panel method of erection may be used for all types of small buildings and large warehouses. When this method is used for large buildings, cranes are used to place sections too heavy to be handled by hand.

#### WARNING

When machinery is used, use caution in fastening the lifting cable or rope to avoid damaging the section.

## **MATERIALS**

2-14. The primary components used in frame construction are lumber and hardware. This section includes information on the types and sizes of lumber as well as a description of various metal fasteners.

## LUMBER

2-15. Lumber varies greatly in structural characteristics. A carpenter must learn about lumber so that he can choose the most suitable material for each job. This section covers the types, standard sizes, and uses of lumber for construction carpentry. It also covers the methods of measuring lumber quantities in terms of board feet, which is the unit by which it is ordered.

#### Grades

2-16. Lumber, as it comes from the sawmill, is divided into three main classes: yard lumber, structural material, and factory and shop lumber. However, only yard lumber will be considered here. It is classified on the basis of quality. The carpenter must choose a quality that is suitable for the intended purpose. At the same time, he must exercise economy by not choosing a better (and therefore more expensive) grade than is required. Lumber is subdivided into classifications of select lumber and common lumber.

#### Select Lumber

- 2-17. Select lumber is of good appearance and finishing. It is identified by the following grade names for comparison of quality:
  - Grade A is suitable for natural finishes and is practically clear.
  - *Grade B* is suitable for natural finishes, is of high quality, and is generally clear.
  - *Grade C* is suitable for high-quality paint finishes.
  - *Grade D* is suitable for paint finishes between high-finishing grades and common grades and has somewhat the nature of both.

#### Common Lumber

- 2-18. Common lumber is suitable for general construction and utility purposes. It is identified by the following grade names for comparison of quality:
  - No. 1 common is suitable for use without waste, it is sound and tight knotted, and it may be considered watertight lumber.
  - *No. 2 common* is less restricted in quality than No. 1, but of the same general quality. It is used for framing, sheathing, and other structural forms where the stress or strain is not too great.
  - *No. 3 common* permits some waste, and it is lower in quality than No. 2. It is used for such rough work as footing, guardrails, and rough flooring.
  - No. 4 common permits waste, is of low quality, and may have coarse features such as decay and holes. It is used for sheathing, subfloors, and roof boards in the cheaper types of construction, but its most important industrial outlet is for boxes and crates.
  - No. 5 common is not produced in some kinds of lumber. It is used for boxes, crates, and dunnage, for which the quality requirement is very low.

## Uses

2-19. In frame construction, lumber is used primarily for the frame and walls.

#### Frames

- 2-20. Building frames are the wood forms constructed to support the finished members of a structure. These include posts, girders (beams), scabs, joists, subfloors, sole plates, girts, knee braces, top plates, and rafters. Softwoods are usually used for wood framing and all other construction carpentry covered in this manual.
- 2-21. *No. 2 common* lumber is used for framing. Heavy frame components, such as beams and girders, are made by combining several pieces of framing material.

#### Walls

- 2-22. The exterior wall of a frame structure usually has three layers: sheathing, building paper, and siding.
- 2-23. Sheathing and siding lumber are normally grade No. 2 common softwood, which is with solid knots, no voids.

2-24. Siding is either vertically or horizontally applied. Theater construction may limit available material to lap siding for both horizontal and vertical surfaces. For local procurement, there are several types of drop and bevel siding, which is applied horizontally. (See page 6-42, siding.)

#### **Sizes**

2-25. Lumber is usually sawed into standard dimensions (length, width, and thickness). This allows uniformity in planning structures and in ordering materials. Table 2-1 lists the common widths and thicknesses of wood in rough and in dressed dimensions in the US. Standards have been established for dimension differences between the quoted size of lumber and its standard sizes when dressed. Quoted size refers to dimensions prior to surfacing. These dimension differences must be taken into consideration. A good example of the dimension difference is the common 2 x 4. As shown in table 2-1, the familiar quoted size 2 x 4 is the rough or nominal dimension, but the actual dressed size is 1 1/2 x 3 1/2 inches. Lumber is sawn in standard sizes used for light framing

• Thickness: 1, 2, and 4 inches.

• Width: 2, 4, 6, 8, 10, and 12 inches.

• Length: 8, 10, 12, 14, 16, 18, and 20 feet.

2-26. The actual dimensions of dressed lumber are less than the sawn dimensions because of drying and planing (or finishing). For the relative difference between swan (standard or nominal) dimensions and actual sizes of construction lumber, see table 2-1.

Table 2-1. Nominal and dressed sizes of lumber

Nominal Size (In Inches)	Dressed Size (In Inches)
1 x 3	3/4 x 2 1/2
1 x 4	3/4 x 3 1/2
1 x 6	3/4 x 5 1/2
1 x 8	3/4 x 7 1/4
1 x 10	3/4 x 9 1/4
1 x 12	3/4 x 11 1/4
2 x 4	1 1/2 x 3 1/2
2 x 6	1 1/2 x 5 1/2
2 x 8	1 1/2 x 7 1/4
2 x 10	1 1/2 x 9 1/4
2 x 12	1 1/2 x 11 1/4
3 x 8	2 1/2 x 7 1/4
3 x 12	2 1/2 x 11 1/4
4 x 12	3 1/2 x 11 1/4
4 x 16	3 1/2 x 15 1/4
6 x 12	5 1/2 x 11 1/2
6 x 16	5 1/2 x 15 1/2
6 x 18	5 1/2 x 17 1/2
8 x 16	7 1/2 x 15 1/2
8 x 20	7 1/2 x 19 1/2
8 x 24	7 1/2 x 23 1/2

2-27. Plywood is usually 4 x 8 feet and varies from 1/8 to 1 inch in thickness.

2-28. The amount of lumber required is measured in board feet. A board foot is a unit measure representing an area of 1 foot by 1 foot, 1 inch thick. Thus, a board that is 1 inch thick, 1 foot wide, and 1 foot long measures 1 board foot. A board that is 1 inch thick, 1 foot wide, and 12 feet long measures 12 board feet.

2-29. To determine the number of board feet in one or more pieces of lumber, use the following formula:

$$Board\ feet = \frac{N\ x\ T(in)x\ W(in)x\ L(ft)}{12}\ or\ \frac{N\ x\ T(in)x\ W(in)x\ L(in)}{144}$$

where-

N = number of lumber pieces

T = thickness

W = width

L=length

2-30. Examples of board feet computations are shown in figure 2-3.




Figure 2-3. Examples of board-feet computations

#### HARDWARE

2-31. A wide variety of fasteners are used for frame construction in the TO. These fasteners are all made of metal. They are classified as nails, screws, bolts, driftpins, corrugated fasteners, and timber connectors.

#### **Nails**

- 2-32. Nails, the most common type of metal fasteners, are available in a wide range of types and sizes.
- 2-33. Some basic nail types are shown in figure 2-4, page 2-8. The common nail is designed for rough framing. The box nail is used for toenailing and light work in frame construction. The casing nail is used in finished carpentry work to fasten doors and window casings and other wood trim. The finishing nail and brad are used for light, wood-trim material and are easy to drive below the surface of lumber with a nail set.



Figure 2-4. Types of nails

2-34. The size of a nail is measured in a unit known as a penny. Penny is abbreviated with the lowercase letter *d*. It indicates the length of the nail. A 6d nail is 2 inches long; a 10d nail is 3 inches long (figure 2-5). These measurements apply to *common*, *box*, *casing*, and *finish* nails only. *Brads* and small *box* nails are identified by their actual length and gauge number.




Figure 2-5. Sizes of cut nails

- 2-35. A nail, whatever the type, should be at least three times as long as the thickness of the wood it is intended to hold. Two thirds of the length of the nail is driven into the other piece of wood for proper anchorage. The other one-third of the length provides the necessary anchorage of the piece being fastened. Protruding nails should be bent over to prevent damage to materials and injury to personnel.
- 2-36. There are a few general rules to be followed in the use of nails in building. Nails should be driven at an angle slightly toward each other to improve their holding power. You should be careful in placing nails to provide the greatest holding power. Nails driven with the grain do not hold as well as nails driven across the grain. A few nails of proper type and size, properly placed an properly driven, will hold better than a great many driven close together. Nails are generally considered the cheapest and easiest fasteners to be applied.
- 2-37. Figure 2-6, page 2-10, shows a few of the many specialized nails. Some nails are specially coated with zinc, cement, or resin materials. Some have threading for increased holding power. Nails are made from many materials, such as iron, steel, copper, bronze, aluminum, and stainless steel.




Figure 2-6. Specialized nails

2-38. Annular and spiral nails are threaded for greater holding power. They are good for fastening paneling or plywood flooring. The drywall nail is used for hanging drywall and has a special coating to prevent rust. Roofing nails are not specified by the penny system; they are referred to by length. They are available in lengths from 3/4 to 2 inches and have large heads. The double-headed nail, or duplex-head nail, is used for temporary construction, such as form work or scaffolding. The double head on this nail makes it easy to pull out when forms or scaffolding are torn down. Nails for power nailing come in rolls or clips for easy loading into a nailer. They are coated for easier driving and greater holding power. Table 2-2 gives the general sizes and types of nails preferred for specific applications.

Table 2-2. Sizes, types, and uses of nails

SIZE	LGTH (IN)	DIAM (IN)	REMARKS	WHERE USED
2d	1	.072	Small head	Finish work, shop work
2d	1	.072	Large flathead	Small timber, wood shingles, lathes
3d	1 1/4	.08	Small head	Finish work, shop work
3d	1 1/4	.08	Large flathead	Small timber, wood' shingles, lathes
4d	1 ½	.098	Small head	Finish work, shop work
4d	1 ½	.098	Large flathead	Small timber, lathes, shop work
5d	1 3/4	.098	Small head	Finish work, shop work
5d	1 3/4	.098	Large flathead	Small timber, lathes, shop work
6d	2	.113	Small head	Finish work, casing, stops, and so forth, shop work
6d	2	.113	Large flathead	Small timber, siding, sheathing, and so forth, shop work
7d	2 1/4	.113	Small head	Casing, base, ceiling, stops, and so forth
7d	2 1/4	.113	Large flathead	Sheathing, siding, subflooring, light framing

SIZE LGTH (IN) DIAM (IN) REMARKS WHERE USED 8d 2 ½ .131 Small head Casing, base, ceiling, wainscot and so forth, shop work 8d 2 1/2 .131 Large Flathead Sheathing, siding, subflooring, light framing, shop work 8d 1 1/4 .131 Extra-large flathead Roll roofing, composition shingles 2 3/4 9d .131 Small head Casing, base, ceiling, and so forth 2 3/4 9d .131 Large flathead Sheathing, siding, subflooring, framing, shop work 10d 3 .148 Small head Casing, base, ceiling, and so forth, shop work 10d 3 .148 Large flathead Sheathing, siding, subflooring, framing, shop work 12d 3 1/4 .148 Large flathead Sheathing, subflooring, framing 16d 3 ½ .162 Large flathead Framing, bridges, and so forth 4 .192 Large flathead 20d Framing, bridges, and so forth 30d 4 1/2 .207 Large flathead Heavy framing, bridges, and so forth 40d 5 .225 Large flathead Heavy framing, bridges, and so forth 50d 5 ½ .244 Large flathead Extra-heavy framing, bridges, and so forth 6 60d .262 Large flathead Extra heavy framing, bridges, and so forth This chart applies to wire nails, although it may be used to determine the length of cut nails.

Table 2-2. Sizes, types, and uses of nails

#### Screws

2-39. Screws are more expensive than nails in both time and money, but are sometimes required for superior results. They provide more holding power than nails and can be easily tightened to draw material securely together. Screws are neater in appearance and may be withdrawn without damaging the material. The common wood screw is usually made of unhardened steel, stainless steel, aluminum, or brass. The steel may be bright-finished or blue, or it may be zinc, cadmium, or chromeplated. Wood screws are threaded for approximately 2/3 of the length of the screw from a gimlet point and have a slotted head.

2-40. Screws vary in length and size of shaft. Each length is made in a number of shaft sizes identified by a number that shows relative differences in the diameter of the screws. Proper screw size number indicates the wire gauge of the body, the drill or bit size for the body hold, and the drill or bit size for the starter hole. Table 2-3, page 2-12, shows screw sizes and dimensions. Table 2-4, page 2-13, shows applicable drill and auger bit sizes for screws.

Table 2-3. Screw sizes and dimensions

											S	SIZE											
LENGTH (IN)	0	1	7	3	4	5 6	7	8	6	10	11	12	13 1	14	15 1	16 1	17 1	18	20 22	2 24	26	28	30
7,		×	×	×																			
3/8	×	×	×	×	×	×	×	×	×														
7,2		×	×	×	×	×	×	×	×	×	×	×											
5/8		×	×	×	×	×	×	×	×	×	×	×	× ×										
3/4			×	×	×	×	×	×	×	×	×	×	× ×	×	×								
7,8			×	×	×	×	×	×	×	×	×	×	×	×	×								
:			- 1	×	×	×	×	×	×	×	×	×	×	<u>×</u>	×	<u>×</u>	<u>×</u>		×				
1 1/4					×	×	×	×	×	×	×	×	× ×	×	×	<u>×</u>	<u>×</u>		×	×			
11/2					×	×	×	×	×	×	×	×	× ×	×	×	<u>×</u>	<u>×</u>		×	×			
1 34					- 1	×	×	×	×	×	×	×	× ×	<u>×</u>	×	<u>×</u>	×		×	×			
2					- 1	×	×	×	×	×	×	×	× ×	<u>×</u>	×	<u>×</u>	<u>×</u>		×	×			
2 1/4					- 1	×	×	×	×	×	×	×	× ×	<u>×</u>	×	<u>×</u>	<u>×</u>		×	×			
2 1/2					- 1	×	×	×	×	×	×	×	× ×	×	×	<u>×</u>	<u>×</u>		× ×	×			
2 3/4						×	×	×	×	×	×	×	× ×	×	×	<u>×</u>	<u>×</u>		×	×			
3						×	×	×	×	×	×	×	× ×	×	×	<u>×</u>	<u>×</u>		×	×	×		
3 1/2								×	×	×	×	×	× ×	<u>×</u>	×	<u>×</u>	<u>×</u>		×	×	×		
4								×	×	×	×	×	<u>×</u>		×	<u>×</u>	×		×	×	×	×	
4 ½												×	<u>×</u>		×		<u>×</u>		×	×	×	×	×
2												×	<u>×</u>		×		<u>×</u>		× ×	×	×	×	×
9													×		×		×		×	×	×	×	×
										3UAG	E AN	D DIAN	<b>GUAGE AND DIAMETER</b>										
STEEL WIRE GAUGE	3Al	JGE			_	17	15		14		13	12	1		10	6	8		7	6 1/2	9		5
DIAMETER (INCHES)	Ş	ES)			<u>ب</u>	.054	0.72	72	.080		.091	.105	.120		.135	.148	.162		.177	.184		.192	.207
STEEL WIRE GAUGE	BAI	JGE			4	4 1/2	4		3		2 1/2	2	~	1/2	. ^!	0	00		00 1/2	000		0000	
DIAMETER (INCHES)	う	ES)			, ,	.216	.225	5	.243		.253	.262	.283	3	1	.306	.331		ı	.362		.393	

20 September 2013

SCRE	W SIZE	1	2	3	4	5	6	7	8	9	10	12	14	16	18
NOMINAL S		0.73	.086	.099	.112	.125	.138	.151	.164	.177	.190	.216	.242	.268	.294
BODY DIAM	IETER	5/64	3/32	7/64	7/64	1/8	9/64	5/32	11/64	3/16	3/16	7/32	1/4	17/64	19/64
PILOT	DRILL SIZE	_	_	_	_	_	_	_	_	_	_	4	4	5	5
HOLE	BIT SIZE	_													
STARTER	DRILL SIZE	_	1/16	1/16	5/64	5/64	3/32	7/64	7/64	1/8	1/8	9/64	5/32	3/16	13/64
HOLE	BIT SIZE	_	_	_	_	_	_	_		_	_	_	_	_	4

Table 2-4. Drill and auger bit sizes

- 2-41. Both slotted and Phillips (cross-slotted) flathead and oval-head screws are countersunk enough to allow a covering material to be used. Slotted roundhead and Phillips roundhead screws are not countersunk, but are driven firmly flush with the surface.
- 2-42. The most common types of screws, along with their uses, are discussed in the following paragraphs.

#### **Wood Screws**

2-43. Wood screws are designated according to head style. The most common types are flathead, oval head, and roundhead (figure 2-7) with either slotted or Phillips heads. Their sizes vary from 1/4 to 6 inches. Screw sizes up to 1 inch increase by eighths, screws from 1 to 3 inches increase by quarters, and screws from 3 to 6 inches increase by half inches.




Figure 2-7. Wood screws

2-44. To prepare wood for receiving the screws (figure 2-8, page 2-14), a pilot hole the diameter of the screw is bored into the piece of wood to be fastened. A smaller starter hole is then bored into the piece of wood that is to act as anchor or to hold the threads of the screws. The starter hole has a diameter less than that of the screw threads and is drilled to a depth of 1/2 or 2/3 the length of the threads to be anchored. This method assures accuracy in placing the screws, reduces the possibility of splitting the wood, and reduces the time required.

20 September 2013 TM 3-34.47/MCRP 3-17.7C 2-13




Figure 2-8. Sinking a wood screw properly

## Lag Screws

2-45. The Army name for lag screws (figure 2-9) is lag bolt, wood-screw type. They are longer and heavier than the common wood screw and have coarser threads, which extend from a cone or gimlet point slightly more than half the length of the screw. Square-head and hexagon-head lag screws are usually placed with a wrench. They are used when ordinary wood screws would be too short or too light and spikes would not be strong enough. Lag screw sizes are given in table 2-5. Combined with expansion anchors, lag screws are used to frame timbers to existing masonry.

**DIAMETER (INCHES)** LENGTHS (INCHES) 1/4 3/8, 7/16, 1/2 5/8, 3/4 7/8, 1 Χ Χ 1 1/2 Х Χ Χ 2, 2 1/2, 3, 3 1/2, so forth, 7 1/2, 8 to 10 Х Х Х Χ 11 to 12 Х Χ Х 13 to 16 Х Χ

Table 2-5. Lag-screw sizes




Figure 2-9. Lag screws

#### Sheet-Metal Screws

2-46. Sheet-metal screws are used for the assembly of metal parts. These screws are steel or brass with four types of heads: flat, round, oval, and McAllister, as shown in figure 2-10.




Figure 2-10. Sheet-metal screws

#### **Bolts**

2-47. Bolts are used when great strength is required or when the work must be disassembled frequently. Nuts are usually used for fastening bolts. The use of washers between the nut and wood surfaces, or between both the nut and the head and their opposing surfaces, will avoid marring the surfaces and will permit additional torque in tightening. Bolts are selected by length, diameter, threads, style of head, and type.

## Carriage Bolts

- 2-48. Carriage bolts come in three types: square neck, finned neck, and ribbed neck, as shown in figure 2-11, page 2-16.
- 2-49. In each type of carriage bolt, the part of the shank immediately below the head grips the materials into which the bolt is inserted. This keeps the bolt from turning when a nut is tightened down on it or removed. The finned carriage bolt has two or more fins extending from the head to the shank. The ribbed type has longitudinal ribs, splines, or serrations on all or part of a shoulder, located immediately beneath the head.




Figure 2-11. Carriage bolts

- 2-50. Holes bored to receive carriage bolts are bored to a tight fit for the body of the bolt and counterbored to permit the head of the bolt to fit flush with or below the surface of the material being fastened. The bolt is then driven into the hole with a hammer.
- 2-51. Carriage bolts are chiefly for wood-to-wood use, but may also be used for wood-to-metal. If used for wood-to-metal application, the bolt head should be fitted to the wood item. Metal surfaces are sometimes predrilled and countersunk to allow the use of carriage bolts for metal-to-metal fastening. Carriage bolts can be obtained from 1/4 to 1 inch in diameter and from 3/4 to 20 inches long. (Table 2-6 lists carriage-bolt sizes.) A common flat washer should be used between the nut and the wood surface with carriage bolts.

LENGTHS (INCHES)	DIA	METER (INCHES)		
	3/16, 1/4, 5/16, 3/8	7/16, 1/2	9/16, 5/8	3, 3/4
3/4	Х			
1	х	х		
1 1/4	х	х	х	
1 1/2, 2, 2 1/2, so forth, 9 1/2, 10 to 20	X	x	x	х

Table 2-6. Carriage-bolt sizes

#### Machine Bolts

2-52. Machine bolts (or cap screws) (figure 2-12) are made with cut national fine or national coarse threads. These threads extend from twice the diameter of the bolt plus 1/4 inch (for bolts less than 6 inches in length) to twice the diameter of the bolt plus 1/2 inch (for bolts over 6 inches in length). Machine bolts are precision made and generally applied metal to metal where close tolerance is needed. The head may be

square, hexagon, double hexagon, rounded, or flat countersunk. The nut usually corresponds in shape to the head of the bolt with which it is used. (Machine bolts are externally driven only.)




Figure 2-12. Machine bolts

2-53. A machine bolt is selected on the basis of head style, length, diameter, and type of thread. The hole through which the bolt is to pass is bored to the same diameter as the bolt. Machine bolts are made in diameters from 1/4 to 3 inches and may be obtained in any length desired. (Table 2-7 lists machine-bolt sizes.)

**DIAMETER (INCHES)** LENGTHS (INCHES) 1/4, 3/8 7/16 1/2, 9/16, 5/8 3/4, 7/8, 1 1 1/8, 1 1/4 3/4 Х 1, 1 1/4 Х Х Х 1 ½, 2, 2 1/2 Х Χ Χ Х 3, 3 ½, 4, 4 ½, so forth, 9 ½, 10 to 20 Х Х Х Х Х 21 to 25 Χ Х Х 26 to 39 Х Χ

Table 2-7. Machine-bolt sizes

#### Stove Bolts

2-54. Stove bolts (figure 2-13, page 2-18) are less precisely made than machine bolts. They have either flat or round slotted heads and have threads extending almost the full length of the body. Stove bolts are generally used with square nuts and may be applied metal to metal, wood to wood, or wood to metal. If flatheaded, they are countersunk; if roundheaded, they are used flush with the surface.




Figure 2-13. Stove bolts

#### **Expansion Bolts**

2-55. An expansion bolt is a bolt used together with an expansion shield (figure 2-14), which is usually made of lead or plastic, to provide anchorage in substances in which a threaded fastener is useless. The shield (or *expansion anchor*) is inserted in a predrilled hole and expands when the bolt is driven into it. Wedged firmly in the hole, the shield provides a secure base for the grip of the fastener.




Figure 2-14. Expansion bolt and shield

2-56. The expansion shield can be used with a nail, screw, or bolt. The shield may be obtained separately or may include the nail, screw, or bolt.

#### **Driftpins**

2-57. Driftpins (called *driftbolts* for supply purposes) (figure 2-15) are long, heavy, threadless bolts used to hold heavy pieces of timber together. Driftpins have heads, and they vary in diameter from 1/2 to 1 inch, and in length from 18 to 26 inches.




Figure 2-15. Driftpins

2-58. To use the driftpin, make a hole in the timber slightly smaller than the diameter of the pin. Drive the pin into the hole. It is held in place by the compression action of the wood.

## **Corrugated Fasteners**

- 2-59. Corrugated fasteners are used to fasten joints and splices in small boards, particularly in miter joints and butt joints. Corrugated fasteners are made of 18- to 22-gauge sheet metal with alternate ridges and grooves; the ridges vary from 3/16 to 5/16 inch, center to center. One end is cut square; the other end is sharpened, with beveled edges.
- 2-60. There are two types of corrugated fasteners: one with ridges running parallel, the other with ridges running at a slight angle to one another (figure 2-16). The latter type tends to compress the material, since the ridges and grooves are closer at the top than at the bottom. Corrugated fasteners vary from 5/8 to 1 1/8 inches wide and from 1/4 to 3/4 inch long. Ridges on the fasteners range from three to six ridges per fastener.




Figure 2-16. Corrugated fasteners

2-61. Corrugated fasteners are a great advantage when used to fasten parallel boards together (as in fastening tabletops), to make any type of joint, and to substitute for nails where nails may split the lumber.

The fasteners have a greater holding power in small lumber than nails do. The proper method of using the fasteners is shown in figure 2-17.




Figure 2-17. Proper use of corrugated fasteners

## **Timber Connectors**

2-62. Timber connectors are metal devices for increasing the joint strength in timber structures. Efficient connections for either timber-to-timber joints or timber-to-steel joints are provided by the several types of timber connectors. The right type is determined by the kind of joint to be made and the load to be carried. The connectors—

- Eliminate much of the complicated framing of joints.
- Simplify the design of heavy construction.
- Provide greater efficiency in the use of material.
- Reduce the amount of timber and hardware used.
- Save time and labor.

2-63. *Split rings* (figure 2-18) are made of low-carbon steel and have 21/2- and Winch diameters. Split rings are used between two timber faces for heavy construction. They fit into grooves that are cut half the depth of the ring into each of the timber faces. The grooves are made with a special bit used in an electric, air, or hand drill. The tongue-and-groove split in the ring permits the ring to bear equally against the cone wall and the outer wall of the groove into which it is placed. The inside bevel and mill edge make installation into, and removal from, the groove easier.




Figure 2-18. Split-ring installation

2-64. *Toothed rings* (figure 2-19) are corrugated and toothed and are made from 16-gauge plate, low-carbon steel. They are used between two timber frames for comparatively light construction and are embedded into the contact faces of the joint members by pressure.




Figure 2-19. Toothed-ring installation

20 September 2013 TM 3-34.47/MCRP 3-17.7C 2-21

This page intentionally	y left blank.	

## **Chapter 3**

## **Bills of Materials**

A BOM is a list of all materials needed to complete a structure. It is based on takeoffs and estimates of the materials needed. It includes item number (parts and materials), name, description, unit of measure, quantity and, where called for, the stock size and number, and sometimes the weight. The carpenter uses it when ordering materials.

A BOM is usually made up by the draftsman when the original drawings are prepared. However, when no BOM accompanies field prints, it must be developed up by the construction crew. For this reason, a carpenter should be able to develop a BOM, as well as work with one. Accuracy can best be obtained by having a separate bill prepared by at least two estimators. The bills may then be compared and one copy corrected or both used to make up a final BOM.

Before a BOM can be prepared, a materials takeoff list and a materials estimate list are prepared.

## MATERIALS TAKEOFF LIST

- 3-1. The first step leading to preparation of a BOM is a materials takeoff list. This is a list of all parts of the building, taken from the plans, usually by tallying and checking off the items indicated on the drawings and specifications. Both architectural and engineering plans provide the names and sizes of the items that are to be listed.
- 3-2. For example, figure 3-1, page 3-2, shows a plan for the substructure of a 20- x 40-foot TO building. Table 3-1, page 3-2, is the materials takeoff list for this building. This list identifies all parts of the building, starting with its base and working upward. The following paragraphs are an example of computing the materials needed for the footers.
- 3-3. Look at the first and second columns of the materials takeoff list. The first column gives the *item* (footers); the next column gives the *number of pieces* (46) needed to make up the item.
- 3-4. The 20- x 40-foot building shown on the plan requires 15 foundation posts. Since three pieces are needed for each footer, a total of 45 pieces is needed.
- 3-5. The *length in place* (1 foot 5 inches) is the actual length of the member after it has been cut and is ready to be nailed in place. The *size* (2 x 6) refers to the nominal size of the lumber. The *length* refers to the standard lengths available from the lumberyard or depot, such as 8-, 10-, and 12-foot pieces of stock.




Figure 3-1. 20- x 40-foot TO building substructure

Table 3-1. Materials takeoff list for a 20- x 40-foot building

ITEM NAME OR USE OF PIECE	NO. OF PIECES	UNIT	LENGTH IN PLACE	SIZE	LENGTH	NO. PER LENGTH	QUANTITY
1. Footers	45	PC	1' – 5'	2x6	10'	7	7
2. Spreaders	30	PC	1' – '	2x6	8'	6	5
3. Foundation Post	15	PC	3' – 0'	6x6	12'	4	4
4. Scabs	20	PC	1' - 0'	1x6	8'	8	3
5. Girders	36	PC	10' – 0'	2x6	10'	1	36
6. Joists	46	PC	10' – 0'	2x6	10'	1	46
7. Joist Splices	21	PC	2' - 0'	1x6	8'	4	6
8. Block Bridging	40	PC	1' – 10 3/8'	2x6	8'	4	10
9. Closers	12	PC	10' – 0'	1x8	10'	1	12
10. Flooring	800	BF	RL	1x6	RL	_	_

3-6. Select the most economical length for the 15 footers. Convert the required length to available lengths for economical use. Seven 1-foot 5-inch-long pieces are cut from each 10-foot piece of stock; 45 1-foot 5-inch pieces require seven 2 x 6 x 10 pieces. Leftover material can be used for bridging.

ITEM SIZE & UNIT **TAKEOFF** WASTE **ADDITIONAL TOTAL** BD FT **LENGTH QUANTITY** ALLOWANCE REQUIREMENTS **QUANTITY** MEASURE 1. 6 x 6 x12 PC 4 1 None 5 180 2. 2 x 6 x 10 89 8 98 980 PC None 2 15 20 160 3. 2 x 6 x 8 PC 3 For Temporary Bracing 4. 2 1 x 8 x 10 PC 12 None 14 91 2 5. 1 x 6 x 8 PC 9 2 For Batter Boards 13 52 6. 1 x 6 x RL BF 800 160 None 960 960 7. 16d 36 Nails, Framing 36 LB 8. 8d LB 23 Nails, Flooring 23

Table 3-2. Materials estimate list

## MATERIALS ESTIMATE LIST

- 3-7. The materials estimate list puts materials takeoff list information into a shorter form, adds an allowance for waste and breakage, and makes an estimate of required quantities of material. These materials include nails, cement, concrete form lumber, tie wire, and temporary bracing or scaffold lumber. (table 3-2 is a sample materials estimate list.)
- 3-8. The first step in preparing this list is to group (from the takeoff list) all pieces of the same size and length. For example, start with the largest size lumber that can be found on the materials takeoff list. Group all the pieces of that same size and length that appear on the list. This groups the total number of each size and length that will be needed. Continue in this way with each size of lumber, working down to the smallest size and length of material.
- 3-9. The sizes and pounds of nails needed should also be added to the list. Two formulas used for estimating the number of pounds of nails needed are shown below:

# Estimating quantity of nails required

• For flooring, sheathing, and other 1-inch material, use the following formula:

Number of pounds (2 penny through 8 penny) =

$$\frac{penny}{4}x\frac{board\ measure}{100}$$

• For framing materials that are 2 inches or more, use the following formula:

Number of pounds (10 penny through 60 penny) =

$$\frac{penny}{6}x\frac{board\ measure}{100}$$

- 3-10. For each material size, a waste factor must be added. For flooring, sheathing, and other 1-inch material, add a waste allowance of 2 percent; for all other materials 2 inches and larger, add 10 percent to the total number.
- 3-11. Next, estimate the amount of additional requirements for materials (such as bracing) that are not shown on the plans. Add the total quantity for each size and length of material. If it is used for siding, sheathing, or flooring, convert it to board feet using the method given in chapter 2 (page 2-5).

## BILL OF MATERIALS FORMAT

3-12. The information for the BOM (DA Form 2702) is taken from the materials estimate list. The BOM is used to requisition these materials. The materials estimate list contains information on materials needed for a project, but it also contains much information on materials needed for a project, but it also contains much

information of little interest to depot personnel. Therefore, use the simplified BOM (DA Form 2702 (Bill of Materials), figure 3-2) to requisition materials.

3-13. The rest of the building would be analyzed in the same way.

XXXXX	BILL OF MATERIAL For use of this form, see DA Pan 420-6; the pr		OE.	DATE XX/	/xx/xx
CINDIV	(requesting unit)		KY XX	JOB ORDER NO X X X WORK REGUE	K X ST NO.
STOCK OR PART NO.	DESCRIPTION OF ARTICLE	UNIT	QUANTITY	UNIT PRICE	TOTAL COST
0000-00-000-000	Lumber, 6x6x12; 180 bdft Lumber, 2x6x10; 980 bdft Lumber, 2x6x8; 160 bdft Lumber, 1x8x10; 94 bdft Lumber, 1x6x8; 52 bdft Lumber, 1x6x8; 960 bdft Nails, 16d Nails, 8d	PC P	98 20 14 13 86 36 23		
A 150RM 2702				:>O : 1983 (	0 - 426-310

Figure 3-2. Sample DA Form 2702 (to view the most current version of this form please visit http://www.apd.army.mil/pub/eforms/pureedge/a2702.xfdl)

## Chapter 4

# **Building Layout and Foundation**

The details of layout and planning are essential to proper construction of a building. Layout prepares the site for the foundation which must be planned and completed for each building being constructed. This chapter introduces the carpenter to the tools, materials, and techniques used in the effective accomplishment of these vital layout and planning functions.

## LAYOUT

- 4-1. Layout techniques are described in the following paragraphs. The following are the most commonly used layout tools and materials:
  - A string line is used to distinguish the dimensions of the building layout.
  - A sledgehammer is used to sink corner stakes or batter boards and posts.
  - A posthole auger is used to dig the holes required to set posts properly in some soils.
  - A handsaw is used to cut batter boards and posts.
  - An ax or a hatchet is used to sharpen batter-board posts and stakes.
  - A hammer is used for building batter boards.
  - A chalk line is used to deposit chalk on the surface in order to make a straight guideline.
  - A 100-foot/30-meter tape is used for measuring diagonally (usually in a 100 foot length) and for laying out excavation or foundation lines.
  - *Tracing tape is* used for laying out excavation or foundation lines. The tape is made of cotton cloth approximately 1 inch wide. It usually comes in a 200 foot length.
  - A carpenter's level is used to level a surface and to sight level lines. It may be used directly on the surface or with a straightedge.
  - A line level has a spirit bubble to show levelness. The level is hung from a taut line. It gives the greatest accuracy when it is placed halfway between the points to be leveled.
  - An automatic level measures approximate differences in elevation and can establish grades over limited distances. The landscape, level bubble, and index line are seen in the tube.
  - 8d nails are used to secure string line to batter boards.
  - A plumbing bob is used to locate the corners of the building dimensions.
  - A framing square is used to check the squareness of lines.

## LAYING OUT A RECTANGULAR BUILDING SITE

- 4-2. Working from an established line, such as a road or a property line (line AB in figure 4-1, page 4-2) that is parallel to construction, establish the maximum outer perimeter (AB, CD, AC, BD) of the building area.
- 4-3. Measure away from the front line (AB) along the side lines (AC and BD) the distances (AO and BO) desired to the dimension of the project that is to run parallel to the front line.




Figure 4-1. Laying out a rectangle

- 4-4. Stretch a line tightly from point O to O. This line will mark the project's frontage.
- 4-5. Measure in from lines AC and BD along line OO one-half the difference between the length of line OO and the desired length of the project. The points (X and X) will constitute the front corners of the project.
- 4-6. The two distances OX and XO establish the distances E and F. Extend lines from the two front corners, X and X, parallel to AC and BD at the distances established as E and F for the required depth of the project. This provides the side lines of the project (XG and XH).
- 4-7. Joining the extreme ends of side 111 XH will provide the rear line (GH) of the project.
- 4-8. After the four corners (X, X, G, and H) have been located, drive stakes at each corner. Batter boards may be erected at these points either after the stakes have been set or while they are being set. Dimensions are determined accurately during each step.

#### LAYING OUT AN IRREGULAR BUILDING SITE

4-9. Where the outline of the building is other than a rectangle, the procedure in establishing each point is the same as described for laying out a simple rectangle. However, more points have to be located, and the final proving of the work is more likely to reveal a small error. When the building is an irregular shape, it is advisable to first lay out a large rectangle which will comprise the entire building or the greater part of it. This is shown in figure 4-2 as HOPQ When this is established, the remaining portion of the layout will consist of small rectangles, each of which can be laid out and proved separately. These rectangles are shown as LMNP ABCQ, DEFG, and IJKO in figure 4-2.




Figure 4-2. Laying out irregular projects

## **SETTING BATTER BOARDS**

4-10. Batter boards are a temporary framework used to assist in locating corners when laying out a foundation. Batter-board posts are made from  $2 \times 4$  or  $4 \times 4$  material; corner stakes are made from  $2 \times 2$ s. Batter boards are made from  $1 \times 4$  or  $1 \times 6$  pieces.

## **Staking Procedures**

4-11. Corner stakes are driven to mark the exact corners of the project. Excavating for a foundation will disturb the stakes, so batter boards are set up outside the boundary established by the stakes to preserve definite and accurate building lines. Heavy cord or fine wire is stretched from one batter board to another to mark these lines.

#### **Location of Batter Boards**

4-12. Figure 4-3, page 4-4, shows how to locate batter boards. Right-angle batter boards are erected 3 or 4 feet outside of each corner stake. Straight batter boards are erected 3 or 4 feet outside of the line stakes.




Figure 4-3. Locating batter boards

## **Construction of Batter Boards**

4-13. Right-angle batter boards should be fastened to the posts after the posts are sunk. Since the boards should be at the exact height of the top of the foundation, it may be desirable to adjust the height by nailing the boards to the stakes after the stakes have been sunk. Right-angle batter boards may be nailed close to

perpendicular by using a framing square and should be leveled by means of a carpenter's level before they are secured. Then, angle saw cuts may be made or nails driven into the tops of the boards to hold the lines in place. Separate cuts or nails may be used for the building line, the foundation line, the footing line, and excavation lines. These grooves permit the removal and replacement of the lines in the correct position.

## **EXTENDING LINES**

- 4-14. The following procedure applies to a simple layout as shown in figure 4-4, page 4-6, and must be amended to apply to different or more complex layout problems:
  - **Step 1.** After locating and sinking stakes A and B. erect batter boards 1, 2, 3, and 4. Extend a chalk line (X) from batter board 1 to batter board 3, over stakes A and B.
  - **Step 2.** After locating and sinking stake C, erect batter boards 5 and 6. Extend chalk line Y from batter board 2 over stakes A and C to batter board 6.
  - **Step 3.** After locating and sinking stake D, erect batter boards 7 and 8. Extend chalk line Z from batter board 5 to batter board 7, over stakes C and D.
  - **Step 4.** Extend line O from batter board 8 to batter board 4, over stakes D and B.
- 4-15. Where foundation walls are wide at the bottom and extend beyond the outside dimensions of the building, the excavation must be larger than the laid-out size. To lay out dimensions of this excavation, measure out as far as required from the building line on each batter board and stretch lines between these points, outside the first layout.
- 4-16. The lines may be at a right angle where they cross the corner layout stakes, found by holding a plumb bob over the corner layout stakes and adjusting the lines until they touch the plumb-bob line. All lines should be checked with a line level or a carpenter's level.

20 September 2013 TM 3-34.47/MCRP 3-17.7C 4-5




Figure 4-4. Laying out building lines from batter boards

## **SQUARING LINES**

4-17. The two methods commonly used for squaring extended lines are the 6-8-10 method and the diagonal method.

#### The 6-8-10 Method

4-18. After extended lines are in place, measure line EF for a distance of 6 feet (figure 4-4). Measure line EG for a distance of 8 feet. Adjust the lines (Y and X) until FG equals 10 feet. Multiples of 6-8-10 may be used for large layouts; for example, 12-16-20 for a layout 50 feet by 100 feet. For accuracy, never start with a measurement of less than 6 feet.

#### The Diagonal Method

4-19. If the layout is rectangular, lines H and I, cutting the rectangle from opposing corners, will form two triangles as shown in figure 4-4. If the rectangle is perfect, these lines will be equal in length and the corners perfectly square. If lines H and I are not equal in length, adjust the corners by moving the lines right or left until H and I are equal.

#### **FOUNDATIONS**

4-20. Foundations vary according to their use, the soil-bearing capacity, and the type of material available. The material may be cut stone, rock, brick, concrete, tile, or wood, depending on the weight the foundation is to support. Foundations may be classified as wall or column (pier) foundations.

## WALL FOUNDATIONS

- 4-21. Wall foundations (figure 4-5) are solid their total length and are usually used when heavy loads are to be carried or where the earth has low supporting strength. These walls may be made of concrete, rock, brick, or cut stone, with a footing at the bottom. Because of the time, labor, and material required to build it, this type of wall will be used in the TO only when other types cannot be used. Steel-rod reinforcements should be used in all concrete walls.
- 4-22. *Rubble stone masonry is* used for walls both above and below ground and for bridge abutments. In military construction, it is used when form lumber for masonry units is not available. Rubble masonry may be laid up with or without mortar; if strength and stability are desired, mortar must be used.
- 4-23. Coursed rubble is assembled of roughly squared stones in such a manner as to produce approximately continuous horizontal bed joints.
- 4-24. *Random rubble is* the crudest of all types of stonework. Little attention is paid to laying the stone in courses. Each layer must contain bonding stones that extend through the wall. This produces a wall that is well tied together.




Figure 4-5. Foundation walls

## **COLUMN OR POST FOUNDATIONS**

4-25. The use of column or post foundations constructed from masonry or wood saves time and labor. The posts or columns are spaced according to the weight to be carried. In most cases, the spacing is 6 to 10 feet apart. The sketches in figure 4-6 show the different types of posts with appropriate types of footing. Wood posts are generally used, since they are installed with the least time and labor. When wood posts extend 3 feet or more above the ground, braces are necessary (figure 4-7).




Figure 4-6. Columns and posts




Figure 4-7. Posts with braces

This page intentionally	y left blank.	

### **Chapter 5**

## **Forms for Concrete**

Forms play a major role in concrete construction. They give the plastic concrete its shape and hold it until it hardens. Forms protect the concrete, assist in curing it, and support any reinforcing rods or conduits embedded in the concrete. This chapter familiarizes the carpenter with the design and construction of various types of forms.

### FORM DESIGN

5-1. Forms for concrete must be tight, rigid, and strong. If forms are not tight, loss of concrete may cause a honeycomb effect, or loss of water may cause sand-streaking. The forms must be braced enough to stay in alignment. Special care is needed when bracing and tying down forms used in applications such as retainer walls, where the mass of concrete is large at the bottom and tapers toward the top. In this type of construction and in the first pour for walls and columns, the concrete tends to lift the form above its proper elevation. (Field Manual 5-742 gives formulas and tables for designing forms of proper strength.)

### FORM CONSTRUCTION

- 5-2. Although forms are generally constructed from wood, fiber, earth, or metal, the TO carpenter usually constructs wood or fiber forms.
- 5-3. Wood forms are the most common in building construction. They are economical, easy to handle, and easy to produce, and they adapt to many shapes. Form lumber can be reused for roofing, bracing, or similar purposes.
- 5-4. Lumber should be straight, strong, and only partially seasoned. Kiln-dried lumber tends to swell when soaked with water. Swelling may cause bulging and distortion. If green lumber is used, allow for shrinkage, or keep it wet until the concrete is in place. Softwoods (pine, fir, and spruce) are the most economical; they are light, easy to work with, and generally available.
- 5-5. Wood coming in contact with concrete should be surfaced (smooth) on the side towards the concrete and on both edges. The edges may be square, shiplap, or tongue-and-groove. Tongue-and-groove lumber makes a more watertight joint, which reduces warping.
- 5-6. Plywood is economical to use for wall and floor forms; however, plywood used for this purpose should be made with waterproof glue and marked for use in concrete forms. Plywood is warp-resistant and can be used more often than other lumber.
- 5-7. An advantage of using plywood for forms is the great number of sizes available. It is made in thicknesses of 1/4, 3/8, 1/2, 5/8, and 3/4 inch, and in widths up to 48 inches. The 8-foot lengths are most commonly used. The 6/8- and 3/4-inch thicknesses are most economical. Thinner plywood requires solid backing to prevent deflection. The 1/4-inch thickness is useful for curved surfaces.

### **CAUTION**

- Watch for protruding nails. They are the principal cause of accidents on form work.
- Inspect tools frequently.
- Place mud sills under shoring that rests on the ground.
- Protect all men on scaffolds and on the ground.
- Do not raise large form panels in heavy gusts of wind.
- Brace all shoring securely to prevent collapse of form work.
- 5-8. Waterproof cardboard and other fiber materials are used for round concrete columns and other preformed shapes. Forms are made by gluing layers of fiber together and molding them to the right shape. The advantage is that fabrication at the job site is not necessary.

### FOUNDATION AND FOOTING FORMS

- 5-9. When possible, earth is excavated to form a mold for concrete-wall footings. If wood forms are needed, the four sides are built in panels.
- 5-10. Panels for two opposite sides are made at exact footing width; the other pair has two end cleats on the inside spaced the length of the footing plus twice the sheathing thickness. One-inch-thick sheathing is nailed to vertical cleats spaced on 2-foot centers. Two-inch dressed lumber should be used for the cleats.

*Note.* Panels are held in place with form nails until the tie wire is installed. Nails should be driven only part way from the outside so that they can be easily removed.

- 5-11. Tie wires are wrapped around the center cleats. Wire holes on each side of the cleat should be less than 1 inch in diameter to prevent mortar leaks. Reinforcing bars must be placed before the wire is installed.
- 5-12. For forms 4 feet square or larger, stakes are driven as shown in figure 5-1. These stakes, and 1 x 6 boards nailed across the top of the form, prevent spreading. Panels may be higher than the required depth of footing, since they can be marked on the inside to show the top of the footing. If the footings are less than 1 foot deep and 2 feet square, forms can be constructed of 1-inch sheathing without cleats (figure 5-2).
- 5-13. When placing a footing and a small pier at the same time, the form is built as shown in figure 5-3, page 5-4. To ensure that support for the upper form does not interfere with the placement of concrete in the lower form, 2 x 4 or 4 x 4 pieces are nailed to the top of the lower form (as shown). The top form is then nailed to these pieces.
- 5-14. Construction and bracing of forms for wall footings are shown in figure 5-4, page 5-4. The sides are 2-inch lumber held in place by stakes and held apart by spreaders. The short brace shown at each stake holds the form in line.

5-2




Figure 5-1. Typical large footing form




Figure 5-2. Typical small footing form

20 September 2013 TM 3-34.47/MCRP 3-17.7C 5-3




Figure 5-3. Footing and pier form




Figure 5-4. Wall-footing forms

### WALL FORMS

5-15. Wall forms are made of wall "panels" and other parts shown in figure 5-5. These parts are described as follows:

### **Wall Panels**

5-16. Wall panels are made by nailing the *sheathing* to the *studs* and can be built in place or prefabricated elsewhere. Prefabricated wall panels should be no more than 10 feet long so that they can be easily handled. Figure 5-6, page 5-6, shows how wall panels are connected and how wall corners are constructed.

### **Sheathing**

5-17. Sheathing forms the surface of the concrete. It should be smooth, especially if the finished surface is to be exposed. It is normally 1-inch (3/4-inch dressed) tongue- and-groove lumber or 3/4-inch plywood. Concrete is plastic when placed in the form, so sheathing should be watertight tongue-and-groove lumber or plywood gives a watertight surface. Reinforce sheathing to prevent bulging from the weight of the concrete.

### **Studs**

5-18. Vertical studs make the sheathing rigid. These studs are generally made from 2 x 4 lumber. Studs also require reinforcing when they extend more than 4 feet.




Figure 5-5. Concrete wall form




Figure 5-6. Constructing wall panels

### Wales

5-19. Double wales reinforce the wall form. They also tie wall panels together and keep them in a straight line. They run horizontally and are lapped at the corners.

### **Braces**

5-20. Braces give the forms stability. The most common brace uses a horizontal member and a diagonal member nailed to a stake and to the stud or wale. The diagonal member of the brace should make a 30° angle with the horizontal member. Additional bracing may be provided by strongbacks (vertical members) behind the wales or in the corner formed by intersecting wales. (Braces are not part of the form design and are not considered as providing additional strength.)

### **Shoe Plates**

5-21. Shoe plates are nailed into the foundation or footing and must be carefully placed to maintain the wall dimensions and alignment. Studs are tied into the shoe plate.

### **Spreaders**

- 5-22. Spreaders must be placed near each *tie wire*. Spreaders are cut to the same length as the thickness of the wall and placed between the two sheathing surfaces of the forms. They are not nailed, but are held in place by friction.
- 5-23. Spreaders are removed as the forms are filled (figure 5-7), so that they will not become embedded as the concrete hardens. A wire is attached to the spreaders to allow them to be pulled out of the form after the concrete has put enough pressure on the walls to allow easy removal. The wire fastened to the bottom spreader passes through a hole drilled off center in each spreader above it. Pulling on the wire will remove the spreaders one after another as the concrete level rises in the forms.




Figure 5-7. Removing wood spreaders

### Tie Wires

5-24. Tie wires hold the forms secure against the lateral pressures of unhardened concrete. Double strands are always used. Ties keep wall forms together as the concrete is positioned; figure 5-8, page 5-8, shows two ways of doing this. The wire should be No. 8 or 9 gauge, black, annealed iron wire. Barbed wire may be used in an emergency. Tie spacing should be the same as the stud placing, but never more than 3 feet. Each tie is formed by looping the wire around a wale, bringing it through the form, and looping it around the wale on the opposite side. The tie wire is made taut by twisting it with a smooth metal rod or a spike.

*Note.* Wire ties should be used only for low walls or when tie rods are not available.

### Tie Rods

- 5-25. An alternate to tie wires and spreaders, the tie rod and spreader combination is shown in figure 5-9, page 5-9. After the form is removed, each rod is broken off at the notch. If appearance is important, the holes should be filled with a mortar mix.
- 5-26. The use of a wood strip as a wedge when curtain walls and columns are placed at the same time is shown in figure 5-10, page 5-9. In removing the forms, the wedge is removed first.




Figure 5-8. Wire ties for form walls




Figure 5-9. Tie rod and spreader combination




Figure 5-10. Wall form for curtain walls

### **COLUMN FORMS**

- 5-27. Sheathing runs vertically in column forms to save saw cuts. Corner joints are firmly nailed to ensure watertight construction. Battens or narrow strips of boards (cleats) are placed directly over the joints to fasten the several pieces of vertical sheathing together.
- 5-28. A column and footing form is shown in figure 5-11, page 5-10. The column form is erected after the steel reinforcement is assembled and is tied to dowels in the footing. The form should have a **cleanout** hole in the bottom to help remove debris. The lumber removed to make the cleanout holes should be nailed to the form so that it can be replaced before the concrete is positioned.

### **BEAM AND GIRDER FORMS**

- 5-29. Figure 5-12, page 5-10, shows both beam and girder forms. The type of construction of these forms depends on whether the form is to be removed in one piece or whether the bottom is to be left until the concrete is strong enough for shoring to be removed. Beam forms receive little bursting pressure but must be shored at close intervals to prevent sagging.
- 5-30. The bottom of the form is the same width as the beam; it is in one piece for its full width. Form sides are 1-inch tongue-and-groove material; they lap over the bottom (as shown). The sheath is nailed to 2 x 4

struts placed on 3-foot centers. A 1 x 4 piece is nailed along the struts to support the joists for the floor panel. The sides of the form are not nailed to the bottom but are held in position by continuous strips. Crosspieces nailed on top serve as spreaders. After erection, the slab panel joints hold the beam in place.

5-31. A beam and girder assembly is shown in figure 5-13. The beam bottom butts tightly against the side of the girder and rests on a 2 x 4 nailed to the girder side. Details in figure 5-13 show the clearances for stripping and the allowances for movement caused by the concrete's weight. The 4 x 4 posts are spaced to support the concrete and are wedged at the bottom or top for easy removal.




Figure 5-11. Column and footing form




Figure 5-12. Beam and girder forms




Figure 5-13. Beam, column and floor plan

### **FLOOR FORMS**

5-32. Floor panels are built as shown in figure 5-14, page 5-12. The 1-inch tongue-and-groove sheathing or 3/4-inch plywood is nailed to  $1 \times 4$  cleats on 3-foot centers. These panels are supported by  $2 \times 6$  joists. Spacing of joists depends on the thickness of the concrete slab and the span of the beams. If the slab spans the distance between two walls, the panels are used in the same manner as when beams support the floor slab.

### **STAIR FORMS**

5-33. A method for building stair forms up to 3 feet in width is shown in figure 5-15, page 5-13. The underside of the steps should be 1-inch tongue-and-groove sheathing. This platform should extend 12 inches beyond each side of the stairs to support stringer bracing blocks. The back of the panel is shored with  $4 \times 4$  pieces (as shown). The  $2 \times 6$  cleats nailed to the shoring should rest on wedges to make both adjustments and removal of the posts easy. The side stringers are  $2 \times 12$  pieces cut as required for the treads and risers. The face of the riser should be 2-inch material, beveled (as shown).

### FORM REMOVAL

- 5-34. Forms should be built to allow easy removal without danger to the concrete. Before concrete is placed, forms are treated with oil or other coating material to prevent the concrete from sticking. The oil should penetrate the wood to prevent water absorption. A light bodied petroleum oil will do. On plywood, shellac is more effective than oil. If forms are to be reused, painting helps preserve the wood.
- 5-35. If form oil is not available, wetting with water may be substituted in an emergency to prevent sticking.
- 5-36. Wood wedges should be used to wedge forms against concrete, rather than a pinchbar or other metal tool. To avoid breaking the edges of concrete, forms should not be jerked off after wedging has been started at one end. Forms to be reused should be cleaned and oiled immediately. Nails should be removed as forms are stripped.

### **CAUTION**

- -- Permit only workmen doing the stripping in the immediate area.
- -- Do not remove forms until the concrete has set.
- -- Pile stripped forms immediately to avoid congestion, exposed nails, and other hazards.




Figure 5-14. Floor slab form




Figure 5-15. Stairway slab form

This page intentionall	y left blank.	

### Chapter 6

# **Rough Framing**

After the foundation is built and the batter boards are removed, the carpenter builds the framework. The framework consists of beams, trusses, walls and partitions, flooring, ceilings, sheathing and siding, stairways, roof framing and coverings (chapter 7), and doors and windows (chapter 8). This chapter familiarizes the carpenter with materials, tools, and techniques used to build the framework.

### **TYPES OF FRAMING**

6-1. Framing consists of *light*, *heavy*, and *expedient* framing.

### LIGHT FRAMING

- 6-2. There are three principal types of framing for light structures: western, balloon, and braced. Figure 6-1, page 6-2, illustrates these types of framing and specifies the nomenclature and location of the various members.
- 6-3. Light framing is used in barracks, bathhouses, and administration buildings. Figure 6-2, page 6-3, shows some details of a 20-foot wide building (such as ground level, window openings, braces, and splices) and labels the framing parts.
- 6-4. Much of light framing can be done in staging areas while staking out, squaring, and floor framing is being done. Subflooring can begin when a portion of the floor joists has been laid. The better-skilled men should construct the frame, and with good coordination, a large force of men can be kept busy during framing.

### **Western Frame**

6-5. The western or platform frame (figure 6-1, 1, page 6-2) is used extensively in military construction. It is similar to the braced frame, but has boxed-sill construction at each floor line. Also note that cross bridging is used between the joists and bridging is used between the studs. The platform frame is preferred for one-story structures since it permits both the bearing and nonbearing walls (which are supported by the joist) to settle uniformly.

#### **Balloon Frame**

6-6. The balloon frame (figure 6-1, 2, page 6-2) is a widely used type of light framing. The major difference between balloon and braced framing in a multistory building is that in balloon framing the studs run the full length, from sill to rafters. It is customary for second-floor joists to rest on a 1-x 4-inch ribbon that has been set into the studs. The balloon frame is less rigid than a braced frame.




Figure 6-1. Framing for light structures

### **Braced Frame**

6-7. A braced frame (figure 6-1, 3) is much more rigid than a balloon frame. Exterior studs extend only between floors and are topped by girts that form a sill for the joists of the succeeding floor. Girts are usually 4 x 6 inches. With the exception of studs, braced frame members are heavier than those in balloon framing. Sills and corner posts are customarily 4 x 6 inches. Unlike the studs, corner posts extend from sill

to plate. Knee braces, usually 2 x 4 inches, are placed diagonally against each side of the corner posts. Interior studding for braced frames is the same as for balloon-frame construction.




Figure 6-2. Light-framing details

### **HEAVY FRAMING**

6-8. Heavy-frame buildings are more permanent, and are normally used for warehouses and shops. Heavy framing is seldom used in TO construction. Figure 6-3, page 6-4, shows the details of heavy framing. Heavy framing consists of framing members at least 6 inches in dimension (timber construction). Long, unsupported areas between walls are spanned by built-up roof trusses.




Figure 6-3. Heavy-framing details

### **EXPEDIENT FRAMING**

- 6-9. Some field conditions require expedient framing techniques. For example—
  - Light siding. Chicken wire and water-resistant bituminous paper can be sandwiched to provide adequate temporary framing in temperate climates.
  - Salvaged framing. Salvaged sheet metal, such as corrugated material or gasoline cans, can be used as siding in the construction of emergency housing.
  - Local timber. Poles trimmed from saplings or bamboo can be constructed into reasonably sound framing and may be secured with native vines if necessary.
  - Wood-substitute framing. Adobe (soil, straw, and water—mixed until spreadable) can be used to form walls, floors, and foundations. A similar mixture may be used to form sun-dried bricks.
  - Excavations. Proper excavation and simple log cribbing may also be covered with sod and carefully drained to give adequate shelter.

### **CONNECTIONS**

6-10. Weak points in a structure usually occur at the connections (joints and splices) between pieces of lumber. However, these connections can be structurally sound if done correctly. Such weak points are usually a sign of poor workmanship.

### **JOINTS**

6-11. Joints are connections between two pieces of timber that come together at an angle. The types of joints most commonly used in carpentry are butt joints and lap joints.

### **Butt Joints**

6-12. A butt joint is formed by placing the end of one board against another board so that the boards are at an angle (usually a right angle), forming a corner. The types of butt joints are shown in figure 6-4 and are described below.




Figure 6-4. Butt joints

### Straight Butt Joint

6-13. This joint is formed by placing the square-cut end of one board against the square face of another. The butt end of one board should be square and the face of the other board smooth so that they fit perpendicular to each other. Select the right type of nails or screws to hold such a joint securely. For framing, butt joints are secured by 8d or 10d nails that are toenailed to strengthen the joint. The end grain is the weakest part of a piece of wood when used in joints. A butt joint is made at either one or two end-grain

parts. It will be no stronger than the quality of those parts. A butt joint is, therefore, the weakest type of joint. This is especially true if the joint is made of two pieces of wood only.

### Oblique Butt Joint

6-14. This joint is formed by butting the mitered end of one board against the face of another board. Bracing is typically made with this joint. It should not be used where great strength is required. The strength of the oblique butt joint depends upon the nailing. The nail size depends upon the timber size. Nails should be toenailed to strengthen the joint; not too many nails should be used.

#### Miter Butt Joint

6-15. This joint is formed by bringing the mitered ends of two boards together to form the desired angle. This joint is normally used at corners where a straight butt joint would not be satisfactory. To form a right-angle miter joint (the most commonly used), cut each piece at a 45° angle so that when the pieces are joined they will form a 90° angle. The miter joint is used mostly in framing. *However, it is a very weak joint and should not be used where strength is important.* 

### Lap Joints

6-16. The lap joint is the strongest joint. Lap joints (figure 6-5) are formed in one of two ways: a plain lap joint or a half-lap splice joint.

### Plain Lap Joint

6-17. This joint is formed by laying one board over another and fastening the two with screws or nails. This is the simplest and most often used method of joining. This joint is as strong as the fasteners and material used.

### Half-Lap Splice Joint

6-18. This joint is formed by cutting away equal-length portions (usually half) from the thickness of two boards. The two are then joined so that they overlap and form a corner. Overlapping surfaces must fit snugly and smoothly. Overlaps should be sawed on the waste side of the gauge line, to avoid cutting laps oversize by the thickness of the cut. *This joint is relatively strong and easy to make*.

*Note.* Some useful variations of the half-lap joint are the cross-lap, the middle-lap, and the mitered half-lap joints.




Figure 6-5. Lap joints

### **SPLICES**

6-19. Splices connect two or more pieces of material that extend in the same line. The joint will be as strong as the unjoined portions. The type of splice used depends on the type of stress and strain that the spliced timber must withstand.

- Vertical supports (longitudinal stress) require splices that resist compression.
- Trusses, braces, and joists (transverse and angular stress) require splices that resist tension.
- Horizontal supports, such as girders or beams, require splices that resist bending tension and compression.
- For example, splices for resisting compression are usually worthless for resisting tension or bending. Figure 6-6, page 6-8, shows splice types; figure 6-7, page 6-9, shows splice stresses.
- Compression-Resistant Splices. Compression-resistant splices support weight or exert pressure and will resist compression stress only. The most common types of compression-resistant splices are the *butt splice* and the *halved splice*.
- **Butt Splice.** This splice is constructed by butting the squared ends of two pieces of timber together and securing them in this position with two wood or metal pieces fastened on opposite sides of the timber. The two short supporting pieces keep the splice straight and prevent buckling. Metal plates used as supports in a butt splice are called *fishplates*. Wood plates are called *scabs* and are fastened in place with bolts or screws. Bolts, nails, or corrugated fasteners may be used to secure scabs. If nails are used with scabs, they are staggered and driven at an angle away from the splice. Too many nails, or nails that are too large, will weaken a splice.
- Halved Splice. This splice is made by cutting away half the thickness of equal lengths from the
  ends of two pieces of timber, then fitting the tongues (laps) together. The laps should be long
  enough to provide adequate bearing surfaces. Nails or bolts may be used to fasten the halved
  splice.

*Note.* To give the halved splice resistance to tension as well as compression, fishplates or scabs may be used.




Figure 6-6. Splices




Figure 6-7. Splice stresses

### **Tension-Resistant Splices**

6-20. In members such as trusses, braces, and joists, the joint undergoes stress in more than one direction; this creates tension, buckling the member in a predictable direction. Tension-resistant splices provide the greatest practical number of bearing surfaces and shoulders within the splice.

### Square Splice

6-21. This splice is a modification of the compression halved splice. Notches are cut in the tongues or laps to provide an additional locking shoulder. The square splice may be fastened with nails or bolts.

*Note.* It may be greatly strengthened by using fishplates or scabs.

### Long, Plain Splice

6-22. This splice is a hasty substitute for the square splice. A long overlap of two pieces is desirable to provide adequate bearing surface and enough room for fasteners to make up for the lack of shoulder lock.

### **Bend-Resistant Splices**

- 6-23. Horizontal timbers supporting weight undergo stress at a splice that results in compression of the upper part; this has a tendency to crush the fibers. Tension of the lower part also tends to pull the fibers apart. Bend-resistant splices resist both compression and tension. Make a bend-resistant splice as follows:
  - Step 1. Cut oblique, complementary laps in the end of two pieces of timber.
  - **Step 2.** Square the upper lap (bearing surface) to butt it against the square of the other lap. This offers maximum resistance to crushing.
  - **Step 3.** Bevel the lower tongue.
  - **Step 4.** Fasten a scab or fishplate along the bottom of the splice to prevent separation of the pieces.

*Note.* When this splice cannot be done, a butt joint, halved splice, or square splice secured by fishplates or scabs may be used.

### **SILLS**

6-24. There are four types of wood sill construction: platform construction, balloon-framed construction, braced-framed construction, and the builtup sill. The sill is the foundation that supports a building and is the first part of a building to be set in place. It rests directly on the foundation posts or on the ground and is joined at the corners and spliced when necessary. Figure 6-8 shows the most common sills. The type of sill used depends on the type of construction used in the frame. To prevent air from entering into the building, spread a thin bed of mortar on top of the foundation wall. This also provides a solid base for the sill. Another technique is to use a sill sealer made of fiberglass. Place insulation material and a termite shield under the sill if desired.

### PLATFORM CONSTRUCTION

- 6-25. Box sills are commonly used with platform framing, which is the most common type of framing. These may be used with or without the sill plate.
- 6-26. The sill or sill plate is anchored to the foundation wall for supporting and fastening joists with a header at the end of the joists resting on the foundation wall. In this type of sill, the sill is laid edgewise on the outside edge of the sill plate.

### **BALLOON-FRAMED CONSTRUCTION**

6-27. "T" sills are usually used in balloon framing. There are two types of T-sills: one for dry, warm climates and one for colder climates. They are made the same, except that in the latter case the joists are nailed directly to the studs and sills and headers are used between the floor joists.

### **BRACED-FRAMING SILLS**

6-28. Braced-framing sills (figure 6-8) are usually used in braced-framing construction. The floor joists are notched and nailed directly to the sill and studs.




Figure 6-8. Types of sills

### **BUILT-UP SILLS**

- 6-29. If posts are used in the foundation, use either sills made of heavy, single timbers or built-up sills. Built-up sills are made with two or more light timbers, such as 2 x 4s. A built-up sill is used when heavy, single timbers are not available and lighter lumber (such as a 2 x 4) alone would not support the building load. Figure 6-9 shows how to make a corner joint for a builtup sill.
- 6-30. Whether heavy timber or built-up sills are used, the joints should be over posts. The size of the sill depends on the load to be carried and the spacing of the posts. The sill plates are laid directly on the post or, in expedient framing, directly on graded earth. When earth floors are used, nail the studs directly to the sill.




Figure 6-9. Corner joint of a built-up sill

### **GIRDERS**

- 6-31. The distance between two outside walls is usually too great to be spanned by a single joist. A *girder is* used for intermediate support when two or more joists are needed to cover the span. A girder is a large beam that supports other smaller beams or joists. A girder may be made of timber, steel, reinforced concrete, or a combination of these materials.
- 6-32. Wooden girders are more common than steel in light-frame buildings. Built-up and solid girders should be of seasoned wood. Common types of wood girders include solid, built-up, hollow, and glue-laminated. Hollow beams resemble a box made of 2 x 4s, with plywood webs. They are often called box beams. Built-up girders are usually made of several pieces of framing lumber (figure 6-10, page 6-12). Built-up girders warp less easily than solid wooden girders and are less likely to decay in the center.




Figure 6-10. Built-up girder details

6-33. Girders carry a large part of the building weight. They must be rigid and properly supported at the foundation walls and on the columns. They must be installed properly to support joists. The ends of wood girders should bear at least 4 inches on posts.

### **CAUTION**

Precautions must be taken to avoid or counteract any future settling or shrinking, which would cause distortion of the building.

6-34. A girder with a ledger board is used where vertical space is limited. This provides more headroom in basements and crawl spaces. A girder with joist hangers is used where there is little headroom or where the joists must carry an extremely heavy load. These girders are shown in figure 6-11.




Figure 6-11. Joist-to-girder attachment

### **SIZE REQUIREMENTS**

6-35. Carpenters should understand the effect of length, width, and depth on the strength of wood girders before attempting to determine their size.

6-36. Principles that govern the size of a girder are the—

- Distance between girder posts.
- Girder load area.
- Total floor load on the girder per square foot.
- Load on the girder per linear foot.
- Total load on the girder.
- Material to be used.
- Wood moisture content and types of wood used, since some woods are stronger than others.

6-37. A girder should be just large enough to support an ordinary load. Any size larger than that wastes material. For greater carrying capacity, it is better to increase a girder's depth (within limits) than its width. When the depth of a girder is doubled (the width of lumber, such as  $2 \times 8$  or  $2 \times 6$ ), the safe load increases four times. For example, a girder 3 inches wide and 12 inches deep will carry four times as much weight as a girder 3 inches wide and 6 inches deep. Table 6-1, page 6-14, gives the sizes of built up wood girders for various loads and spans.


Table 6-1. Sizes of built-up wood girders

(Based on Douglas fir 4-square guideline framing; deflection not over 1/360 of span; allowable fiber stress 1,600 lb/in<sup>2</sup>)

LOAD PER LINEAR FOOT OF	LENGTH OF SPAN (FEET)					
	6	7	8	9	10	
GIRDER	NOMINAL SIZE OF GIRDER REQUIRED (INCHES)					
750	6 x 8	6 x 8	6 x 8	6 x 10	6 x 10	
900	6 x 8	6 x 8	6 x 10	6 x 10	8 x 10	
1050	6 x 8	6 x 10	8 x 10	8 x 10	8 x 12	
1200	6 x 10	8 x 10	8 x 10	8 x 10	8 x 12	
1350	6 x 10	8 x 10	8 x 10	8 x 12	10 x 12	
1500	8 x 10	8 x 10	8 x 12	10 x 12	10 x 12	
1650	8 x 10	8 x 12	10 x 12	10 x 12	10 x 14	
1900	8 x 10	8 x 12	10 x 12	10 x 12	10 x 14	
1950	8 x 12	10 x 12	10 x 12	10 x 14	12 x 14	
2100	8 x 12	10 x 12	10 x 14	12 x 14	12 x 14	
2250	10 x 12	10 x 12	10 x 14	12 x 14	12 x 14	
2400	10 x 12	10 x 14	10 x 14	12 x 14		
2550	10 x 12	10 x 14	12 x 14			
2700	10 x 12	10 x 14	12 x 14			
2850	10 x 14	12 x 14	12 x 14			
3000	10 x 14	12 x 14				
3150	10 x 14	12 x 14				
3300	12 x 14	12 x 14				

- 1. The 6" girder is figured as being made with three pieces 2" dressed to 1 3/4" thickness.

- The 6 girder is figured as being made with four pieces 2' dressed to 1 3/4" thickness.
   The 8" girder is figured as being made with four pieces 2" dressed to 1 3/4" thickness.
   The 10" girder is figured as being made with five pieces 2" dressed to 1 3/4" thickness.
   The 12" girder is figured as being made with six pieces 2" dressed to 1 3/4" thickness.
   For solid girders, multiply the above loads by 1.130 when a 6" girder is used; 1.150 when an 8" girder is used; 1.170 when a 10" girder is used; and 1.180 when a 12" girder is used.



### LOAD AREA

- 6-38. A building load is carried by foundation walls and the girder. Because the ends of each joist rest on the girder, there is more weight on the girder than on any of the walls. Before considering the load on the girder, it may be well to consider a single joist.
- 6-39. Example 1. Suppose a 10-foot plank weighing 5 pounds per foot is lifted by two men. If the men were at opposite ends of the plank, they would each support 25 pounds.
- 6-40. Now assume that one of these men lifts the end of another 10-foot plank of the same weight as the first one. A third man lifts the opposite end of that plank. The two men on the outside are each now supporting one-half of the weight of one plank (25 pounds apiece), but the man in the center is supporting one-half of each of the two planks (50 pounds).
- 6-41. The two men on the outside represent the foundation walls. The center man represents the girder. The girder carries one-half of the weight, and the other half is equally divided between the outside walls. However, the girder may not always be located halfway between the outer walls.
- 6-42. *Example 2*. Imagine the same three men lifting two planks that weigh 5 pounds per foot. One of the planks is 8 feet long and the other is 12 feet long. The total length of these two planks is the same as before. The weight per foot is the same, so the total weight in both cases is 100 pounds.
- 6-43. One of the outside men is supporting one-half of the 8-foot plank) or 20 pounds. The man on the opposite outside end is supporting one-half of the 12-foot plank, or 30 pounds. The man in the center is supporting one-half of each plank (50 pounds). This is the same total weight he was lifting before.

*Note.* To determine the girder load area: a girder will carry the weight of the floor on each side to the midpoint of the joists that rest upon it.

### FLOOR LOAD

6-44. After the girder load area is known, the total floor load per square foot must be determined, for safety purposes. Both dead and live loads must be considered.

#### Dead Load

- 6-45. The dead load consists of all building structure weight. The dead load per square foot of floor area is carried directly or indirectly to the girder by bearing partitions. The dead load varies according to the construction method and building height. The structural parts in the dead load are—
  - Floor joists for all floor levels.
  - Flooring materials, including the attic if it is floored.
  - Bearing partitions.
  - Attic partitions.
  - Attic joists for the top floor.
  - Ceiling laths and plaster, including the basement ceiling if it is plastered.
- 6-46. The total dead load for a light-frame building similar to an ordinary frame house is the dead-load allowance per square foot of all structural parts added together.
  - The allowance for an average subfloor, finish floor, and joists without basement plaster should be 10 pounds per square foot.
  - If the basement ceiling is plastered, allow an additional 10 pounds per square foot.
  - If the attic is unfloored, make a load allowance of 20 pounds for ceiling plaster and joists when girders or bearing partitions support the first-floor partition.
  - If the attic is floored and used for storage, allow an additional 10 pounds per square foot.

#### Live Load

- 6-47. The live load is the weight of furniture, persons, and other movable loads, not actually a part of the building but still carried by the girder. The live load per square foot will vary according to the building use and local weather conditions. Snow on the roof is also a part of the live load.
  - Allowance for the live load on floors used for living purposes is 30 pounds per square foot.
  - If the attic is floored and used for light storage, allow an additional 20 pounds per square foot.
  - The allowance per square foot for live loads is usually governed by local building specifications and regulations.
- 6-48. The load per linear foot on the girder is easily figured when the total load per square foot of floor area is known.
- 6-49. *Example*. Assume that the girder load area of the building shown in figure 6-12 is sliced into 1-foot lengths across the girder. Each slice represents the weight supported by 1 foot of the girder. If the slice is divided into 1-foot units, each unit will represent 1 square foot of the total floor area. To determine the load per linear foot of girder, multiply the number of units by the total load per square foot.
- 6-50. Note in figure 6-12, that the girder is off-center. Remember that half of the load is supported by the girder and half by the foundation walls. Therefore, the joist length to be supported on one side of the girder is 7 feet (one half of 14 feet) and the other side is 5 feet (one half of 10 feet), for a total distance of 12 feet across the load area. Since each slice is 1 foot wide, it has a total floor area of 12 square feet.
- 6-51. Assume that the total floor load for each square foot is 70 pounds. Multiply the length times the width to get the total square feet supported by the girder (7 feet x 12 feet = 84 square feet).

84 square feet x 70 pounds per square feet (live and dead load) = 5,880 pounds total load on the girder

### **BUILT-UP GIRDERS**

- 6-52. Figure 6-10, page 6-11, shows a built-up girder. Notice that the joists rest on top of the girder. This type of girder is commonly used in frame building construction. To make a built-up girder, select lumber that is as free from knots and other defects as possible.
- 6-53. Built-up girders are usually made of three pieces of framing lumber nailed together. (The pieces must be nailed securely to prevent individual buckling.) For proper arrangement of the pieces of lumber, the end grains should match the example in figure 6-13. The nailing pattern should be square across the ends of the board (1 1/2 inches from each end) and then diagonal every 16 inches as shown in figure 6-13. This pattern increases the strength of the girder. A typical two- or three-piece girder of 2-inch lumber should be nailed on both sides with 16d common nails.




Figure 6-12. Girder load area




Figure 6-13. Built-up girder lumber arrangement

### **SPLICING**

6-54. Methods for splicing girders differ according to whether the girder is built-up or solid-beam.

### **Built-Up Girders**

6-55. The lumber for a built-up girder should be long enough so that no more than one joint will occur over the span between footings. The joints in the beam should be staggered, and the planks must be squared at each joint and butted tightly together.

### **Solid-Beam Girders**

- 6-56. To splice solid beams, use half-lap joints or butt joints (figure 6-14.) See Splices on page 6-7.
- 6-57. **Half-Lap.** Sometimes a half-lap joint is used to join solid beams (figure 6-14). This is done by performing the following steps:
  - **Step 1.** Place the beam on one edge so that the annual rings run from top to bottom.
  - **Step 2.** Lay out the lines for the half-lap joint as shown in figure 6-14.
  - Step 3. Make cuts along these lines, then check with a steel square to ensure a matching joint.
  - **Step 4.** Repeat the process on the other beam.
  - **Step 5.** Nail a temporary strap across the joint to hold it tightly together.
  - **Step 6.** Drill a hole through the joint with a drill bit about 1/16 inch larger than the bolt to be used, and fasten the joint with a bolt, a washer, and a nut.
- 6-58. **Butt Joints.** When a strapped butt joint is used to join solid beams (figure 6-14), the ends of the beams should be cut square. The straps, which are generally 18 inches long, are bolted to each side of the beams.




Figure 6-14. Butt and half-lap joints

### **GIRDER SUPPORTS**

6-59. When building a small frame building, the carpenter should know how to determine the proper size of girder supports (called *columns* or *posts*).

- 6-60. A *column* or *post* is a vertical member that supports the live and dead loads placed upon it. It may be made of wood, metal, or masonry.
  - Wooden columns may be solid timbers or several pieces of framing lumber nailed together with 16d or 20d common nails.
  - *Metal columns* are made of heavy pipe, large steel angles, or I-beams.
- 6-61. A column must have a bearing plate at the top and bottom which distributes the load evenly across the column. Basement posts that support girders should be set on masonry footings. Columns should be securely fastened at the top to the load-bearing member and at the bottom to the footing on which they rest.
- 6-62. Figure 6-15 shows a solid wooden column with a metal bearing cap drilled to permit fastening it to the girder. The bottom of this type of column may be fastened to the masonry footing by a metal dowel. The dowel should be inserted in a hole drilled in the bottom of the column and in the masonry footing. The base is coated with asphalt at the drilling point to prevent rust or rot.
- 6-63. A good arrangement of a girder and supporting columns for a 24- x 40-foot building is shown in figure 6-16, page 6-20.
  - Column B will support one-half of the girder load between wall A and column C.
  - Column C will support one-half of the girder load between columns B and D.
  - Column D will share equally the girder loads with column C and wall E.




Figure 6-15. Use of metal cap and masonry footing




Figure 6-16. Column spacing

### **GIRDER FORMS**

6-64. Forms for making concrete girders and beams are made from 2-inch-thick material dressed on all sides. The bottom piece of material should be constructed in one piece to avoid using cleats. The temporary cleats shown in figure 6-17 are nailed on to prevent the form from collapsing when handled.




Figure 6-17. Girder and beam form

### **FLOORING**

6-65. After the foundation and deck framing of a building are completed, the floor is built.

### **FLOOR JOISTS**

6-66. Joists are the wooden members, usually 2 or 3 inches thick, that make up the body of the floor frame (figure 6-18). The flooring or subflooring is nailed to the joists. Joists as small as 2 x 6 are sometimes used in light frame buildings. These are too small for floors with spans over 10 feet, but are frequently used for ceiling joists.




Figure 6-18. Floor joists

- 6-67. Joists usually carry a uniform load of materials and personnel; these are live loads. The weight of joists and floors is a dead load. The joists carry the flooring load directly on ends nearest the sills, girders, bearing partitions, or bearing walls. Joists are spaced 16 or 24 inches apart, center to center. Sometimes the spacing is 12 inches, but where such spacing is made necessary by the load, heavier joists should be used.
- 6-68. To support heavily concentrated loads or a partition wall, you may need to double the joist or place two joists together. Two typical reinforced joists are shown in figure 6-19, page 6-22.
- 6-69. In joining joists to sills, be sure that the connection can hold the load that the joist will carry. The joist-connecting method in figure 6-20, A, page 6-23, is used most often because it provides the strongest joint. The methods shown in figure 6-20, B and C, are used when it is not desirable to use joists on top of the sill. The ledger plate should be securely fastened. If the joist must be notched, it should not be notched to the sill and girder over one-third of its depth to prevent splitting (figure 6-20, D).
- 6-70. Joists must be level when framed to girders. If the girder is not the same height as the sill, the joist must be notched as shown in figure 6-20, C. If the girder and sill are the same height, the joists must be framed to keep the joist level. The joist is always placed crown up. This counteracts the weight on the joists. In most cases there will be no sag below a straight line.
- 6-71. The simplest way to carry joists on steel girders is to rest them on top (as shown in figure 6-20, E), provided headroom is not restricted. If there is a lack of headroom, use straps or hangers (iron stirrups) as shown in figure 6-20, F. These are among the strongest joist supports.
- 6-72. In connecting joists to girders and sills where posts are used, a 2 x 4 is nailed to the face of the sill or girder, flush with the bottom edge. This is called a ledger. These pieces should be nailed securely with 20d nails spaced 12 inches apart. When 2 x 6 or 2 x 8 joists are used, it is better to use 2 x 4 ledgers. This prevents joists from splitting at the notch.

- 6-73. When joists are 10 inches or more deep, 2 x 4s may be used as ledgers without reducing the strength of the joists. If a notch is used, joist ties may be used to overcome this loss of strength. These ties are short 1 x 4 boards nailed across the joists. Board ends are flush with the top and bottom edges of the joists.
- 6-74. Overhead joists are joined to plates as shown in figure 6-21, A and B, page 6-24. The inner end of the joist rests on the partition wall plates. If a joist is to rest on plates or girders, the joist is cut long enough to extend the full width of the plate or girder. Alternatively, the joists are cut to meet in the center of the plate or girder and connected with a scab. When the ends of two joists lie side by side on the plate, they should be nailed together. Joists may also be joined to girders with ledgers (figure 6-21, C and D).




Figure 6-19. Reinforced joists




Figure 6-20. Sill and joist connections

### Floor Joists For Platform Construction

6-75. Check the plans to determine the size and direction of the joists. If the sizes for joists are not specified on the plans, consult tables 6-2 and 6-3, pages 6-24 and 6-25, to determine the appropriate size.

# FLOOR BRIDGING

6-76. Joists tend to twist from side to side, especially when used over a long span. Floor frames are bridged for stiffening and to prevent unequal deflection of the joists. This stiffening also enables an overloaded joist to receive some help from the joists on either side of it. A pattern for the bridging stock is obtained by placing a piece of material between the joists, then marking and sawing it. When sawed, the cut will form the correct angle.

6-77. The three kinds of bridging are: *solid (horizontal) bridging, cross bridging,* and *compression bridging* (figure 6-22, page 6-25). Cross bridging is used most often. It is very effective and requires less time than horizontal bridging. Cross bridging looks like a cross and is made of pieces of lumber, usually diagonally cut 1 x 3 or 2 x 3 between the floor joists. Each piece is nailed to the top of each joist and forms a cross (x) between the joists. Cross bridging should be made so that the two pieces of the cross are against each other. Compression is metal bridging between joists.




Figure 6-21. Top plates and ledgers

Table 6-2. Allowable spans for floor joists using nonstress-graded lumber

Size of Floor Joists (Inches)	Spacing of Floor Joists (Inches)	Maximum Allowable Span (Feet and Inches)								
		Group I		Group II		Group III		Group IV		
		Plastered Ceiling Below	Without Plastered Ceiling Below	Plastered Ceiling Below	Without Plastered Ceiling Below	Plastered Ceiling Below	Without Plastered Ceiling Below	Plastered Ceiling Below	Without Plastered Ceiling Below	
2 x 6	12	10-6	11-6	9-0	10-0	7-6	8-0	5-6	6-0	
	16	9-6	10-0	8-0	8-6	6-3	7-0	6-0	5-0	
	24	7-6	8-0	6-6	7-0	5-6	6-0	4-0	4-0	
2 x 8	12	14-0	15-0	12-6	13-6	10-3	11-6	8-0	8-6	
	16	12-6	13-6	11-0	11-6	9-0	10-0	7-0	7-6	
	24	10-0	11-0	9-0	9-6	7-6	8-0	6-0	6-6	
2 x 10	12	17-6	19-0	16-6	17-6	13-6	14-6	10-6	11-6	
	16	15-6	16-6	14-6	15-6	12-0	13-0	9-6	10-0	
	24	13-0	14-0	12-0	13-0	10-0	10-6	7-6	8-6	
2 x 12	12	21-0	23-0	21-0	21-6	17-6	19-6	13-0	14-6	
	16	18-0	20-0	18-0	19-6	15-6	16-6	12-0	13-0	
	24	15-0	16-6	15-0	16-3	12-6	13-6	10-0	10-6	
<b>Note.</b> The group classifications in this table refer to the species and minimum grades of nonstress-graded lumber. See table 6-3.										




Figure 6-22. Type of bridging

6-78. Bridging should be nailed at the tops with 8d or 11 Id nails, and the bottoms should be left free until the subfloor is laid. This allows the joists to adjust to their final position and keeps the bridging from pushing up the joists and causing unevenness in the floor. The bottom ends of the bridging may then be nailed, forming a continuous truss across the floor. This prevents overloaded joists from sagging.

6-79. Cutting and fitting the bridging by hand is a slow process. A power saw should be used if it is available. One line of bridging should be placed on joists more than 8 feet long. On joists more than 16 feet long, two lines should be used.

Table 6-3. Group classification—nonstress-graded lumber

Species	Minimum Grade		
Group I			
Douglas Fir and Larch	Construction		
Group II			
Bald Cypress	No. 2		
Douglas Fir (South)	Construction		
Fir, White	Construction		
Hemlock, Eastern	No. 1		
Hemlock, West Coast and Western	Construction		
Pine, Red (Norway Pine)	No. 1		

Table 6-3. Group classification—nonstress-graded lumber

Species	Minimum Grade
Redwood, California	Select Heart
Spruce, Eastern	No. 1
Spruce, Sitka	Construction
Spruce, White and Western White	Construction
Group III	
Cedar, Western	Construction, West Coast Studs
Cedar, Western Red and Incense	Construction
Douglas Fir and Larch	Standard, West Coast Studs
Douglas Fir (South)	Standard
Fir, Balsam	No. 1, Standard
Fir, White	West Coast Studs
Hemlock, Eastern	No. 2, Standard
Hemlock, West Coast and Western	West Coast Studs
Pine, Ponderosa, Lodgepole, Sugar, and Idaho White	Construction
Redwood, California	Construction
Redwood, California (studs only)	Two Star
Spruce, Engelmann	Construction, Standard
Spruce, Sitka	West Coast Studs
Spruce, White and Western White	Standard
Group IV	
Cedar, Western	Utility
Cedar, Western Red and Incense	Utility
Douglas Fir and Larch	Utility
Douglas Fir (South)	Utility
Fir, White	Utility
Hemlock, West Coast and Western	Utility
Pine, Ponderosa, Lodgepole, Sugar, and Idaho White	Utility
Redwood, California	Merchantable
Redwood, California (studs only)	One Star
Spruce, Engelmann	Utility
Spruce, Sitka	Utility
Spruce, White and Western White	Utility

# **FLOOR OPENINGS**

6-80. Floor openings for stairwells, ventilators, and chimneys are framed by a combination of *headers* and *trimmers*. Headers run at right angles to the direction of the joists and are doubled. Trimmers run parallel to the joists and are actually doubled joists. The joists are framed at right angles to the headers of the opening

frame. These shorter joists, framed to headers, are called *tail beams, tail joists*, or *header joists*. The number of headers and trimmers needed at any opening depends upon—

- The shape of the opening—whether it is a simple rectangle or contains additional angles.
- The direction in which the opening runs, in relation to the joist direction.
- The position of the opening, in relation to partitions or walls.

6-81. Figure 6-23, shows examples of openings. One runs parallel to the joist and requires two headers and one trimmer. The other runs at right angles to the joists and requires one header and two trimmers. The openings shown in figure 6-24, page 6-28, are constructed with corner angles supported in different ways. The cantilever method (shown on the right of figure 6-24) requires that the angle be fairly close to a supporting partition with joists from an adjacent span that run to the header.




Figure 6-23. Floor openings

6-82. To frame openings of the type shown in figure 6-25, page 6-28—

- **Step 1.** Headers 1 and 2 are nailed to trimmers A and C with three 20d nails.
- **Step 2.** Headers 1 and 2 are nailed to short joists X and Y with three 20d nails.
- **Step 3.** Headers 3 and 4 are nailed to headers 1 and 2 with 16d nails spaced 6 inches apart.
- **Step 4.** Trimmers A and C are nailed to headers 3 and 4 with three 20d nails.

Step 5. Trimmers B and D are nailed to trimmers A and C with 16d nails spaced 12 inches apart.




Figure 6-24. Double headers and trimmers




Figure 6-25. Floor-opening construction

# **SUBFLOORS**

6-83. The subfloor (figure 6-26, page 6-30), if included in the plans, is laid diagonally on the joist framework and nailed with 8d to 10d nails. Subflooring boards 8 inches wide or more should have at least three nails per joist. Where the subfloor is more than 1 inch thick, larger nails should be used. The subfloor is normally laid before the walls are framed so that it can be walked on while walls are being framed.

### FINISH FLOORS

6-84. A finish floor in the TO is normally of 3/4-inch material, square-edged or tongue-and-groove (figure 6-27, page 6-31). Finish flooring varies from 3 1/2 to 7 1/2 inches wide. It is laid directly on floor joists or on a subfloor and nailed with 8d common nails in every joist. When a subfloor exists, building paper is used between it and the finish floor to keep out dampness and insects.

6-85. In warehouses, where heavy loads are to be carried on the floor, 2-inch material should be used for the finish floor. Such flooring is also face-nailed with 16d or 20d nails. It is not tongue-and-groove, and it ranges in width from 4 to 12 inches. The joints are made on the center of the joist.

#### **Wood Floors**

6-86. Wood floors must be strong enough to carry the load. The type of building and its intended use determine the arrangement of the floor system, the thickness of the sheathing, and the approximate spacing of the joists.

#### **Concrete Floors**

- 6-87. Concrete floors may be constructed for shops where earthen or wood floors are not suitable. These include aircraft repair and assembly shops, shops for heavy equipment, and certain kinds of warehouses.
- 6-88. After the earth has been graded and compacted, concrete is placed on the ground. The floor should be reinforced with steel or wire mesh. The foundation wall may be placed first and the concrete floor placed after the building is completed. This gives protection to the concrete floor while it sets.
- 6-89. Drainage is provided for the floor area around the footing and the area near the floor, to prevent flooding after heavy rains. A concrete floor is likely to be damp unless it is protected.




Figure 6-26. Subfloor

# **Miscellaneous Floors**

- 6-90. These types of floors include *earth, adobe brick, duckboard, or rushes*. Miscellaneous flooring is used when conventional materials are unavailable or where there is a need to save time or labor. Such floors may be used if facilities are temporary or if required by the special nature of a structure. Selection of material is usually determined by availability.
- 6-91. Duckboard is widely used for shower flooring. Earthen floors are common; they conserve both materials and labor if the ground site is even without extensive grading. Rush or thatch floors are primarily an insulating measure and must be replaced frequently.




Figure 6-27. Square-edged and tongue-and-groove finish flooring

# WALLS AND PARTITIONS

6-92. Once the floor is in place, it is used to support the wall frame. Wall framing (figure 6-28, page 6-32) consists of studs, diagonal bracing, cripples, trimmers; headers, and fire blocks. It is supported by the floor sole plate. The vertical members of the wall framing are the studs. They support the top plates and the upper part of the building, or everything above the top plate line. Studs support the lath, plaster, and insulation on the inside and wall sheathing on the outside.

6-93. Walls and partitions, which are classed as framed constructions, are composed of studs. Studs are usually closely spaced, slender, 2 x 4 vertical members. They are arranged in a row with their ends bearing on a long horizontal member called a *bottom plate* or *sole plate*, and their tops are capped with another plate, called a top plate. Double top plates are used to tie walls and partitions together. The bearing strength of stud walls is determined by the strength of the studs. Figure 6-29, page 6-33, shows a typical wall construction.

6-94. Partition walls divide the inside space of a building. In most cases, these walls are framed as part of the building. Where floors are to be installed, the partition walls are left unframed.

The two types of partition walls are bearing and nonbearing. The bearing type supports ceiling joists; the nonbearing type supports only itself, and may be put in at any time after the other framework is installed. Only one cap or plate is used. A sole plate should be used in every case, as it helps distribute the load over a larger area.

6-95. Partition walls are framed the same as outside walls; door openings are framed as outside openings. Where there are corners or where one partition wall joins another, corner posts or T-posts are used as in the outside walls. These posts provide nailing surfaces for the inside wall finish. Partition walls in a TO onestory building may or may not extend to the roof. The top of the studs has a plate when the wall does not extend to the roof. If the wall extends to the roof, the studs are joined to the rafters.




Figure 6-28. Typical wall-frame details

#### **CORNER POSTS**

6-96. A corner post forms an inside corner and an outside corner which provides a good nailing base for inside wall coverings. Figures 6-30 and figure 6-31, page 6-34, show two of the most common types of corner posts as they would appear constructed. The stude used at the corners of frame construction are usually built up from three or more ordinary studes to provide greater strength. These built-up assemblies are called *corner posts*. They are set up, plumbed, and temporarily braced. Corner posts may also be made in any of the following ways (figure 6-32, page 6-35):

- A 4x 6 with a 2 x 4 nailed on the board side, flush with one edge (figure 6-32, A,). This type of corner is for a 4-inch wall. Where walls are thicker, heavier timber is used.
- A 4 x 4 with a 2 x 4 nailed to each of two adjoining sides (figure 6-32, B).
- Two 2 x 4s nailed together with blocks between them and a 2 x 4 flush with one edge (figure 6-32, C). This is the most common method.
- A 2 x 4 nailed to the edge of another 2 x 4, the edge of one flush with the side of the other (figure 6-32, D). This type is used extensively in the TO where no inside finish is needed.




Figure 6-29. Typical wall construction




Figure 6-30. Corner-post construction using ordinary 2 x 4 studs




Figure 6-31. Alternate corner-post construction using ordinary 2 x 4 studs

### **PARTITION POSTS**

6-97. There are two types of partition posts—T-posts and double T-posts.

#### **T-Posts**

6-98. Whenever a partition meets another wall, a stud wide enough to extend beyond the partition on both sides is used. This provides a solid nailing base for the inside wall finish. This type of stud is called a T-post and is made in any of the following ways (figure 6-33, page 6-36):

- A 2 x 4 may be nailed and centered on the face side of a 4 x 6 (figure 6-33, A).
- A 2 x 4 may be nailed and centered on two 4 x 4s nailed together (figure 6-33, B).
- Two 2 x 4s may be nailed together with a block between them and a 2 x 4 centered on the wide side (figure 6-33, C).
- A 2 x 4 may be nailed and centered on the face side of a 2 x 6, with a horizontal bridging nailed behind them to give support and stiffness (figure 6-33, D).

#### **Double T-Posts**

6-99. When a partition is finished on one side only, the partition post used is a simple stud, set in the outside wall, in line with the side of the partition wall, and finished as shown in figure 6-34, page 6-37. These posts are nailed in place along with the corner posts. The exact position of the partition walls must be determined before the posts are placed. When walls are more than 4 inches thick, wider timber is used.

6-100. In special cases (for example, where partition walls cross), a double T-post is used. It is made as described above, and by nailing another 2 x 4 to the opposite wide side, as shown in figure 6-34, A, B, and C (C is the most common).




Figure 6-32. Corner-post construction using both 2-inch and 4-inch lumber




Figure 6-33. T-Post construction




Figure 6-34. Partition posts

# **STUDS**

6-101. After the sills, plates, and braces are in place and the window and door openings are laid out, the studs are placed and nailed with two 16d or 20d nails through the plates. The remaining studs are laid out on the sills or soles by measuring, from one corner, the distances the studs are to be set apart. Studs are normally spaced 12, 16, or 24 inches on center, depending upon the outside and inside finish material. If vertical siding is used, studs are set wider apart since the horizontal girts between them provide a nailing surface.

6-102. To double the post of the door opening, the outside studs are first placed into position and nailed securely. Then short studs (or *trimmers*) the size of the vertical opening are cut and nailed to the inside face of the outside studs as shown in figure 6-35, page 6-38, on the sole plate.

6-103. The sill of a window opening must be framed. This sill is specified single or double. When it is double, the top header is nailed to the opening studs at the correct height and the trimmer next. The sill headers are toenailed to the trimmer. The door header is framed as shown in figure 6-35. The jack stud rests on the sole plate.




Figure 6-35. Door and window framing

#### **GIRTS**

6-104. Girts are always the same width as the studs and are flush with the face of the stud, both outside and inside. They are used in hasty construction when the outside walls are covered with vertical siding. Studs are placed from 2 to 10 feet apart, with girts spaced about 4 feet apart, running horizontally between them. The vertical siding acts in the same way as the studs and helps carry the weight of the roof. This type of construction is used extensively in the TO.

#### TOP PLATE AND SOLE PLATE

6-105. The *top plate* ties the studding together at the top and forms a finish for the walls. It supports the lower ends of the roof rafters. The top plates serve as connecting links between the wall and the roof, just as the sills and girders are connecting links between the floors and the walls. The plate is made up of one or two pieces of framing lumber the same size as the studs.

6-106. If the studs at the end of the building extend to the rafters, no plate is used at the end of the building. When used on top of partition walls, the plate is sometimes called the cap. Where the plate is doubled, the first plate or bottom section is nailed with 16d or 20d nails to the top of the corner posts and to the studs. The connection at the corner is made as shown in figure 6-36. After the single plate is nailed securely and the corner braces are nailed into place, the top part of the plate is nailed to the bottom section with 10d nails. The plate may be nailed over each stud or spaced with two nails every 2 feet. Care must be taken to make sure all joints are staggered. The edges of the top section and the corner joints are lapped.

6-107. All partition walls and outside walls are finished either with a 2 x 4 or with a piece of lumber the same thickness as the wall. This lumber is laid horizontally on the floor or joists. It carries the bottom end of the studs, and is called the *sole* or *sole plate*. The sole should be nailed with two 16d or 20d nails at each joist it crosses. If it is laid lengthwise on top of a girder or joist, it should be nailed with two nails every 2 feet.




Figure 6-36. Top-plate and sole-plate construction

# **BRIDGING**

6-108. Frame walls are bridged, in most cases, to make them more sturdy. There are two methods of bridging—horizontal or diagonal (figure 6-37, page 6-39).

### Horizontal

6-109. Horizontal bridging is nailed between the studs horizontally and halfway between the sole and top plates. This bridging is cut to lengths that correspond to the distance between the studs at the bottom. Such bridging not only stiffens the wall but also helps straighten studs.

# Diagonal

6-110. Diagonal bridging is nailed between the studs at an angle. It is more effective than the horizontal type since it forms a continuous truss and keeps the walls from sagging. Whenever possible, interior partitions and exterior walls should be bridged alike.




Figure 6-37. Types of wall bridging

# PLUMBED POSTS AND STRAIGHTENED WALLS

6-111. After the corner post, T-post, and intermediate wall studs have been nailed to the plates or girts, the walls must be plumbed and straightened so that permanent braces and rafters may be installed. This is done by using a level or plumb bob and a chalk line.

# **Plumbing Posts**

- 6-112. There are two methods for plumbing posts.
- 6-113. **Method 1.** To plumb a corner with a plumb bob—
  - **Step 1.** Attach a string to the bob. The string should be long enough to extend to or below the bottom of the post.
  - **Step 2.** Lay a rule on top of the post so that 2 inches of the rule extend over the post on the side to be plumbed.

- **Step 3.** Hang the bob line over the rule so that the line is 2 inches from the post and extends to the bottom of it, as shown in figure 6-38.
- **Step 4.** With another rule, measure the distance from the post to the center of the line at the bottom of the post. If it does not measure 2 inches, the post is not plumb.
- **Step 5.** Move the post inward or outward until the distance from the post to the center of the line is exactly 2 inches, then nail the temporary brace in place.
- **Step 6.** Repeat this procedure from the other outside face of the post. The post is then plumb.

*Note.* This process is carried out for each corner post of the building. If a plumb bob or level is not available, use a rock, half-brick, or small piece of metal.

- 6-114. **Method 2.** An alternative method of plumbing a post is shown in the inset in figure 6-38. 1b use this method—
  - **Step 1.** Attach the plumb-bob string securely to the top of the post to be plumbed. Be sure that the string is long enough to allow the plumb bob to hang near the bottom of the post.
  - **Step 2.** Use two blocks of wood, identical in thickness, as gauge blocks.
  - **Step 3.** Tack one block near the top of the post between the plumb-bob string and the post (gauge block 1).
  - **Step 4.** Insert the second block between the plumb-bob string and the bottom of the post (gauge block 2).
  - **Step 5.** If the entire face of the second block makes contact with the string, the post is plumb.




Figure 6-38. Plumbing a post

### **Straightening Walls**

- 6-115. The following procedure is carried out for the entire perimeter of the building. Inside partition walls should be straightened the same way (figure 6-39).
  - **Step 1.** Plumb one corner post with a level or a plumb bob. Nail temporary braces to hold the post in place. Repeat this procedure for all corner posts.
  - **Step 2.** Fasten a chalk line to the outside of one corner post at the top and stretch the line to the corner post at the opposite end of the building. Then fasten the line to this post.
  - **Step 3.** Place a 3/4-inch block under each end of the line for clearance.
  - **Step 4.** Place temporary braces at intervals small enough to hold the wall straight.
  - **Step 5.** Nail the brace when the wall is far enough away from the line to permit a 3/4-inch block to slide between the line and the plate.




Figure 6-39. Straightening a wall

# **BRACING**

6-116. Bracing is used to stiffen framed construction and make it rigid. Bracing may be used to resist winds, storms, twists, or strains. Good bracing keeps corners square and plumb. Bracing prevents warping, sagging, and shifting that could otherwise distort the frame and cause badly fitting doors and windows and cracked plaster. The three methods commonly used to brace frame structures are let-in, cut-in, and diagonal-sheathing bracings (figure 6-40).

# **Let-In Bracing**

6-117. Let-in bracing is set into the edges of studs, flush with the surface. The studs are always cut to let in the braces; the braces are never cut. Usually 1 x 4s or 1 x 6s are used, set diagonally from top plates to sole plates, or between top or sole plates and framing studs.




Figure 6-40. Three methods of bracing

#### **Cut-In Bracing**

6-118. Cut-in bracing is toenailed between studs. It usually consists of 2 x 4s cut at an angle to permit toenailing. They are inserted in diagonal progression between studs running up and down from corner posts to the sill or plates.

# **Diagonal-Sheathing Bracing**

6-119. The strongest type of bracing is diagonal sheathing. Each board braces the wall. If plywood sheathing 5/8 inch thick or more is used, other methods of bracing may be omitted.

### **EXTERIOR WALLS**

6-120. The exterior surfaces of a building usually consist of vertical, horizontal, or diagonal sheathing and composition, sheet metal, or corrugated roofing. However, in TOs, those materials are not always available and substitutes must be provided. Concrete blocks, brick, stone rubble, metal, or earth may be substituted

for wood in treeless regions. In the tropics, improvised siding and roofs can be made from bamboo and grasses. Roofing felt, sandwiched between two layers of light wire mesh, may serve for wall and roof materials where the climate is suitable. Refer to TMs 5-302-1 and 5-302-2 for details on substitute, expedient, and improvised construction.

6-121. The following paragraphs cover the types of sheathing, siding, and building paper that may be used.

# **Sheathing**

- 6-122. Sheathing is nailed directly onto the framework of the building. It is used to strengthen the building; provide a base wall onto which the finish siding can be nailed; act as insulation; and, in some cases, be a base for further insulation. Some of the common types of sheathing are—
  - Wood, 1 inch thick by 6, 8, 10, or 12 inches wide of No. 1 common square or matched-edge material.
  - Gypsum board, 1/2 inch thick by 4 feet wide and 8 feet long.
  - Fiberboard, 25/32 inch thick by 2 or 4 feet wide and 8, 9, 10, or 12 feet long.
  - Plywood, 1/4, 3/8, 1/2, or 5/8 inches thick by 4 feet wide and 8, 9, 10, or 12 feet long.

#### Wood

6-123. Wood wall sheathing comes in almost all widths, lengths, and grades. However, it is normally 6 to 12 inches wide and 3/4 inch thick. Lengths are selected for economical use and the sheathing is either square- or matched-edge. Sheathing 6 or 8 inches wide should be nailed with two 8d nails at each stud crossing. Wider boards should be nailed with three 8d nails. It is laid on tight, with all joints made over the studs. It may be nailed on horizontally or diagonally (figure 6-41); however, diagonal application adds much greater strength to the structure. If the sheathing is to be put on horizontally, start at the foundation and work toward the top. If it is to be put on diagonally, start at a bottom corner of the building and work toward the opposite wall.




Figure 6-41. Horizontal and diagonal sheathing

#### Gypsum Board

6-124. This type of sheathing is made by casting a gypsum core into a heavy, water-resistant, fibrous envelope. The long edges of the 4 x 8 boards are tongue and grooved. Each board is 1/2 inch thick. Gypsum board is generally used with wood siding. Gypsum board should be nailed with 13/4- or 2-inch galvanized roofing nails spaced 7 inches on center. Gypsum board can be nailed (together with the wood siding) directly to the studs (figure 6-42). Gypsum sheathing is fireproof, water resistant, and windproof. It does not warp or absorb water and does not require the use of building paper.

#### Plywood

- 6-125. Plywood is highly recommended for wall sheathing (figure 6-42). It adds a lot more strength to the frame than using diagonally applied wood boards. When this sheathing is used, corner bracing can be omitted. For this reason and because of their large size, weight, and stability, plywood panels are faster and easier to apply. Plywood provides a tight, draft-free installation of high insulation value.
- 6-126. The minimum thickness of plywood wall sheathing should be 1/4 inch for 16-inch stud spacing, and 3/8 inch for 24-inch stud spacing. The panels should be installed with the face grain **parallel** to the studs. A little more stiffness can be gained by installing them across the studs, but this requires more cutting and fitting. Use 6d common nails for 1/4-, 3/8-, and 1/2-inch panels. At the edges of the panels, space the nails not more than 6 inches on center; elsewhere, not more than 12 inches on center.




Figure 6-42. Gypsum and plywood sheathing

#### Siding

6-127. The siding for exterior walls should be decay-resistant, hold tight at the joints, and take and hold paint well.

#### **Wood Siding**

6-128. Wood siding should be decay-resistant, well-seasoned lumber. It should hold tight at the joints and take and hold paint well. It ranges from 1/2 to 3/4 inch thick by 12 inches wide.

#### Vertical Wood Siding

6-129. Vertical wood siding (figure 6-43) is nailed securely to girts with 8d or 10d nails. The cracks are covered with wood strips called battens. To make this type of wall more weatherproof, some type of tar paper or light roll roofing may be applied between the siding and the sheathing.

### Horizontal Wood Siding

6-130. Horizontal wood siding (figure 6-43) is cut to various patterns and sizes to be used as the finished outside surface of a structure. There are two types *beveled siding* and *drop siding* (figure 6-43).




Figure 6-43. Vertical and horizontal wood siding

### Beveled

6-131. Beveled siding is made with beveled boards, thin at the top edge and thick at the butt. It is the most common form of wood siding. It comes in 1 inch for narrow widths, and 2 inches and over for wide types. Beveled siding is usually nailed at the butt edge, through the top edge of the board below. Very narrow siding is quite often nailed near its thin edge, like shingles. It is nailed to solid sheathing over which building paper has been attached. Window and door casings are first framed. The siding butts are put against the edges of these frames. Corners may be mitered, or the corner boards may first be nailed to the sheathing. Siding is then fitted against the edges.

#### Drop

6-132. Drop siding is used as a combination of sheathing and siding or with separate sheathing. It comes in a wide variety of face profiles and is either shiplapped or tongue and grooved. If used as a combined sheathing and siding material, tongue-and-groove lumber is nailed directly to the studs with the tongue up. When sheathing is not used, the door and window casings are set after the siding is up. If sheathing is first used and then building paper is added, drop siding is applied with beveled siding, **after** the window and door casings are in place.

#### Corrugated-Metal Siding

6-133. Corrugated metal is often used as wall cover since it requires little framing, time, and labor. It is applied vertically and nailed to girts. Nails are placed in the ridges. Sheathing can be used behind the iron with or without building paper. Since tar paper used behind metal will cause the metal to rust, a resin-sized paper should be used.

#### Vinyl and Aluminum Siding

- 6-134. Vinyl and aluminum sidings are popular, low-maintenance, low-cost wall covering. They can be backed with polystyrene or other board reinforcement, both to give the siding a strong base and an insulating R factor value.
- 6-135. Figure 6-44, page 6-48, shows the most common vinyl and aluminum sidings and installation accessories. Some variations exist between manufacturers, but the basic rules for installation are universal. They are—
  - Nail in the center of slots.
  - Do not nail tightly, leave loose for contracting and expanding.
  - Leave at least 1/4-inch clearance at all stops.
  - Do not stretch tight.
  - Strap and shim all uneven walls.
  - **Step 1.** Place outside and inside corners with the bottom of the trim even with the area to weatherproof. Use a level or transit to maintain a constant horizontal line.
  - **Step 2.** Using a level, transit, or chalk line, place the bottom of the starter strip level with the bottom of the corner trim. The starter strip will but the edge of the trim.
  - **Step 3.** Snap the bottom of the siding onto the starter strip and slide it tight into the corner trim, then out 1/4 inch to allow for expansion and contraction of materials in changing temperatures. Nail with roofing nails, 16 inches on center, in the center of the slot, without driving the nails home (leaving approximately 1/16 of an inch between the nailhead and the wall sheathing).
  - **Step 4.** Attach additional pieces of siding in a like manner, except the additional pieces will be placed on top of earlier placed pieces (as top end and bottom ends, like male and female ends in tongue-and-groove materials). Lap tight, then pull away 1/4 inch.




Figure 6-44. Vinyl and aluminum sidings

*Note.* When ending a "run" into a corner or a J-channel, cut so that installation is 1/4 inch from butt to trim.

**Step 5.** Install J-channels on surfaces where the siding run breaks (as in a window or door). The J-channel provides a weatherproof surface.

6-136. On vertical breaks, butt the siding as described in the previous paragraph. On horizontal breaks, install the undersill trim inside the J-channel. The undersill trim is a fastening device. On surfaces such as the top of the door or window trim, this channel will hold pieces of siding that were cut (removing the part of siding that "snaps" onto the top of previous pieces) tight, keeping them from flapping in the breeze. On surfaces such as where the siding butts into the soffit or below windows, a slotting tool is used to pierce the part of the siding that slides into the undersill trim. This pierce pushes out part of the siding and forms a catch. This is used when siding is pushed into the undersill trim, providing fastening for the top of a section of siding where nailing is not possible.

#### **Building Paper**

- 6-137. Building paper comes in several types. The most common type is resin-sized. It is generally red or buff in color (sometimes black). It comes in rolls, usually 36 inches wide; each roll containing 500 square feet and weighing 18 to 50 pounds. Normally, this building paper is not waterproof.
- 6-138. Another type is heavy paper saturated with a coal-tar product, sometimes called sheathing paper. This type is waterproof and insulates against heat and cold. In wood-frame buildings to be covered with siding, shingles, or iron, building paper is used to protect against heat, cold, or dampness. Building paper is

applied horizontally from the bottom of the wall, and nailed with roofing nails at the laps. Overlapping the paper helps water runoff. Care must be taken not to tear the paper. The waterproof paper is also used in the built-up roof when the roof is nearly flat. Several layers are used, with tar between the layers.

# **CEILINGS**

- 6-139. Ceiling joists form the framework of the ceiling of the room. They are usually lighter than floor joists but must be large enough and strong enough to resist bending and buckling.
- 6-140. Ceiling joists are usually installed 16 inches or 24 inches on center, starting at one side of the building and continuing across, parallel to the rafters (figures 6-45 and 6-46, page 6-50). Extra joists, if needed, may be placed without affecting the spacing of the prime joists.




Figure 6-45. Built-up plate supporting joist and roof rafters




Figure 6-46. One method of bracing attic plate

6-141. Selecting and installing the ceiling joists are much the same as for floor joists. Ceiling joists are nailed to both the plates and the rafters, if possible, and lapped and nailed over bearing partitions. Joists that lie beside rafters on a plate are cut at the same pitch as the rafter, flush with the top of the rafter. Joists are installed crown or camber up.

# WALL OPENINGS

6-142. In addition to doors and windows (chapter 8), other wall openings are needed.

#### **STOVEPIPES**

- 6-143. Stovepipes may extend outside a building through a side wall to eliminate the need for flashing and waterproofing around the pipe (figure 6-47 and figure 6-48, page 6-52). The opening should be cut in an area selected to avoid cutting studs, braces, plates, or other structural members. Sheathing must be cut back in a radius 6 inches greater than that of the pipe. Safety thimbles or other insulation must be used on the inside and outside of the sheathing. Sheet metal insulation may be constructed and used as a single insulator on the outside.
- 6-144. Make the opening for the stovepipe as follows:
  - **Step 1.** Cut a hole through the sheet metal where the stovepipe will penetrate.
  - **Step 2.** Mark a circle on the metal 1/2 inch larger in diameter than the pipe. Then make another circle within this circle, with a diameter 2 inches less than the diameter of the first.
  - **Step 3.** With a straightedge, draw lines through the center of the circle from the circumference. These marks should be from 1/2 to 3/4 inch apart along the outer circumference.




Figure 6-47. Framing for stovepipe

- **Step 4.** Cut out the center circle, then cut to the outside of the circle along the lines drawn.
- **Step 5.** After the lines have been cut, bend the metal strips outward at a 45° angle.
- **Step 6.** Force the pipe through the hole to the desired position.

Note. Very little water will leak around this joint.




Figure 6-48. Installing stovepipe

#### **VENTILATORS**

6-145. Ventilation is necessary to prevent condensation in buildings. Condensation may occur in the walls, in the crawl space under the structure, in the basement, on windows, and in many other places. Condensation is most likely to occur during the first six to eight months after a building is built and in extreme cold weather when interior humidity is high. Proper ventilation under the roof allows moisture-laden air to escape during the winter heating season and allows the hot, dry air of the summer season to escape. The upper areas of a structure are usually ventilated by louvers or ventilators. (Types of ventilators are shown in figure 6-49.)

### **Upper Structure**

- 6-146. One of the most common methods of ventilating is to use wood or metal louver frames. There are many types, sizes, and shapes of louvers.
- 6-147. Determine the size and number of ventilators by the size of the area to be ventilated. One square foot of vent should be placed for each 150 square feet of floor space **without** soffit vents and for each 300 square feet of floor space **with** soffit vents. The minimum net open area should be 1/4 square inch per square foot of ceiling area.
- 6-148. Louver frames are usually 5 inches wide. The back edge of the frame should be rabbeted out for a screen, a door, or both. Louvers have <sup>3</sup>/<sub>4</sub>-inch slats, which are spaced about 1 3/4 inches apart. The slats should have sufficient slant or slope to prevent rain from driving in. For the best results, upper-structure louvers should be placed as near to the top of the gable as possible.




Figure 6-49. Types of ventilators

# **Crawl Spaces**

6-149. Crawl spaces under foundations (of structures without basements) should be well ventilated. Air circulation under the flooring prevents excessive condensation which causes warping, swelling, twisting, and rotting of the lumber. The crawl space ventilators are usually called *foundation louvers*. They are set into the foundation as it is built. A good foundation vent should be equipped with a copper or bronze screen and adjustable shutters for opening and closing the louver. Louver sizes should be figured on the same basis as upper-structure louvers 1/4 square inch for each square foot of under-floor space.

# **STAIRWAYS**

- 6-150. Stair work is made up of the framing on the sides, known as stringers (or carriages), and the steps known as treads. Sometimes risers are framed into the stairs at the back of the treads. The stringers (or carriages) are 2 to 3 inches thick and 8 or more inches wide. They are cut to form the step of the stairs.
- 6-151. There are usually three stringers to a stair if stairs are more than 36 inches wide—one at each of the two outer edges and one at the center. Floor joists must be properly framed around the stairwell (or well hole) to have enough space for the stair framing and the finished trim.
- 6-152. Step stringers are fastened at the top and bottom as shown in figures 6-50 and 6-51, page 6-54. These figures also show the foundation and give the sizes of the step treads, as well as installation methods and post construction. The types of steps shown are the most common in field construction.




Figure 6-50. Typical stairway




Figure 6-51. Step construction

# **STAIRWAY FRAMING**

6-153. To frame simple, straight, string stairs (figure 6-52)—

**Step 1.** Take a narrow piece of straight stock, called a story pole, and mark on it the distance from the lower-floor to the upper-floor level. This is the lower-room height, plus the thickness of the floor joists and the rough and finished flooring. It is also the total rise of the stairs. Keep

- in mind that a flight of stairs forms a right triangle. The rise is the height of the triangle, the run is the base, and the length of the stringers is the hypotenuse.
- **Step 2.** Set dividers at 7 inches, the average distance from one step to another.
- **Step 3.** Step off this distance on the story pole.
- **Step 4.** Adjust the divider span slightly if this distance will not divide evenly into the length of the story pole. Step off this distance again.
- **Step 5.** Continue this adjusting and stepping off until the story pole is marked off evenly. The span of the dividers must be near 7 inches. This represents the rise of each step.
- **Step 6.** Count the number of spaces stepped off evenly by the dividers on the story pole. This will be the total number of risers on the stairs.
- **Step 7.** Measure the length of the stairwell opening for the length of the run of the stairs. This length may also be obtained from the plans. The stairwell-opening length forms the base of a right triangle. The height and base of the triangle have now been obtained.




Figure 6-52. Complete stairway detail

### RISERS AND TREADS

6-154. To determine the width of each tread, divide the number of risers less one—since there is always one more riser than tread—into the run of the stairs. This number is used on the steel square in laying off the run and rise of each tread and riser on the stringer stock. These figures will be about 7 and 10 inches, respectively, since the ideal run and rise totals 17 inches. Lay off the run and rise of each step on the stringer stock equal to the number of risers previously determined by dividing the story pole into equal spaces. The height, base, and hypotenuse of the right triangle are now complete.

6-155. The following are two rules of thumb that may be used to check the dimensions of risers and treads:

- Riser height + tread width = between 17 and 19 inches.
- Riser height x tread width = between 70 and 75 inches.

6-156. If the sum of the height of the riser and the width of the tread falls between 17 and 19 inches and the product of the height of the riser and the width of the tread equals between 70 and 75 inches, the design is satisfactory.

# Chapter 7

# **Roof Systems and Coverings**

The roof's main purpose is to keep out the rain, cold, or heat. It must be strong enough to with stand high winds; sloped to shed water; and, in areas of heavy snow, it must be constructed more rigidly to bear the extra weight. This chapter will familiarize carpenters with the most common types of roof construction and materials. This chapter also covers reroofing.

# ROOF FRAMING

7-1. Roofs for TOs are chosen to suit the building; the climate; the estimated length of time the building will be used; and the material, time, and skill required for construction. TO constraints dictate simple design as shown in figure 7-1.




Figure 7-1. Types of roofs

### ROOFING TERMS

7-2. When framing a roof (figure 7-2, page 7-2), carpenters must be familiar with commonly used roofing terms (figure 7-3, page 7-2, and figure 7-4, page 7-4).




Figure 7-2. Framing a roof




Figure 7-3. Common roof-framing terms

### **RAFTERS**

- 7-3. Rafters make up the main framework of all roofs. They are inclined members spaced from 16 to 48 inches apart. They vary in size, depending on length and spacing. The tops of inclined rafters are fastened to the ridge or another rafter, depending on the type of roof. Rafters rest on the top wall plate.
- 7-4. Rafters are nailed to the plate, not framed into it. Some are cut to fit the plate, while in hasty construction they are merely laid on top of the plate and nailed in place. They may extend a short distance beyond the wall to form the eaves and protect the sides of the building.

7-3

## **Types of Rafters**

7-5. Examples of most types of rafters are shown in figure 7-3. The four types are—

#### Common Rafters

7-6. These are framing members that extend at right angles from the plate line to the roof ridge. They are called common rafters because they are common to all types of roofs and are used as the basis for laying out other types of rafters.

## Hip Rafters

7-7. These are roof members that extend diagonally from the corner of the plate to the ridge.

## Valley Rafters

7-8. These rafters extend from the plate to the ridge along the lines where two roofs intersect.

# Jack Rafters

- 7-9. These are a common rafter. The three kinds of jack rafters are the—
  - Hip jack, which extends from the plate to the hip rafter.
  - Valley jack, which extends from the ridge of the valley rafter.
  - Cripple jack, which is placed between a hip rafter and a valley rafter. The cripple jack rafter is also part of a common rafter, but it touches neither the ridge of the roof nor the rafter plate.

Basic Triangle. The basic triangle is the most elementary tool used in roof framing. When framing a roof, the basic right triangle is formed by the horizontal lines (or run), the rise (or altitude), and the length of the rafter (the hypotenuse). Any part of the triangle can be computed if the other two parts are known. Use the following equation:

The square of the hypotenuse of a right triangle is equal to the sum of the squares of the two sides. In roofing terms—

Rafter length<sup>2</sup> = run<sup>2</sup> + rise<sup>2</sup>

Rise. The rise of a rafter is the vertical (or plumb) distance that a rafter extends upward from the plate.

Span of a Roof. The span of any roof is the shortest distance between the two opposite rafters' seats.

Cut of a Roof. The cut of a roof is the rise over the run (such as 4/12 roof) or the pitch of the roof.

Horizontal Line. A horizontal line is one level with the building foundation.

Line Length. In roof framing, line length is the hypotenuse of a triangle whose base is the run and whose altitude is the total rise.

Total Rise. The total rise is the vertical distance from the wall plate to the top of the ridge.

Run. Run always refers to the level distance any rafter covers-normally, one-half the span.

Unit of Run (or unit of measurement). Unit of measurement, 1 foot (or 12 inches), is the same for the roof as for any other part of the building. Using this common unit of measurement, the framing square is used in laying out large roofs (Figure 7-5, page 7-4).

Pitch. Pitch signifies the amount that a roof slants and the ratio of rise (in inches) to run (inches). Using this method, 4, 6, or 8 inches rise per foot of run would give a pitch of 4-12, 6-12, or 8-12. (Figure 7-6, page 7-4, shows how to determine roof pitch.)

Plumb Line. The line formed by the cord on which the plumb bob is hung.

Bird's Mouth. A cutout, near the bottom of a rafter, that fits over the top plate. The cut that fits the top of the plate is called the seat; the cut for the side of the plate is called the heel.

Overhang. The part of a rafter that extends past the outside edge of the walls of a building. When laying out a rafter, this portion is in addition to the length of a rafter and is figured separately. The overhang is often referred to as the tailpiece.

Plate. The wall-framing member that rests on the top of the wall studs.

Ridge. The highest horizontal roof member. It ties the rafters together at the upper end.

Figure 7-4. Roofing terms




Figure 7-5. Use of framing square




Figure 7-6. Determining roof pitch

#### **COLLAR TIE AND BEAM**

7-10. A collar tie or beam (figure 7-7, page 7-6) is a piece of stock (usually 1 x 4, 1 x 6, 1 x 8, or 2 x 4) fastened in a horizontal position to a pair of rafters between the plate and the ridge of the roof. This type of beam keeps the building from spreading. Most codes and specifications require them to be 5 feet apart or every third rafter, whichever is less. Collar ties are nailed to common rafters with four 8d nails to each end of a 1-inch tie. If 2-inch material is used for the tie, they are nailed with three 16d nails at each end. This type of bracing is used on small roofs where no ceiling joists are used and the building is not wide enough to require a truss.

7-11. In small roofs that cover only narrow buildings in which the rafters are short, there is no need for interior support or bracing. In long spans, the roof would sag in the middle if it were not strengthened in some way. To support long rafters, braces or other types of supports must be installed.




Figure 7-7. Collar tie or beam

#### Rafter Layout

7-12. Rafters must be laid out and cut with slope, length, and overhang exactly right so that they will fit when placed in the roof.

#### Scale or Measurement Method

- 7-13. The carpenter should first determine the length of the rafter and the length of the lumber from which the rafter may be cut. If he is working from a roof plan, he learns the rafter lengths and the width of the building from the plan. If no plans are available, the width of the building must be measured.
  - **Step 1.** To determine the rafter length, first find one-half of the horizontal distance (total run) of the rafter. The amount of rise per foot will not be considered yet. (For example, if the building is 20 feet wide, half of the span will be 10 feet. See the example below.)
  - **Step 2.** After the length has been determined, lay the timber on sawhorses (saw benches), with the crown or bow (if it has any) as the top side of the rafter. If possible, select a straight piece for the pattern rafter. If a straight piece is not available, have the crown away from the person laying out the rafter.
  - **Step 3.** Hold the square with the tongue in your left hand, the blade in your right, and the heel toward your body. Place the square as near the upper end of the rafter as possible. (For example, in figure 7-8 (step 1) the figures 8 on the tongue and 12 on the blade are placed along the timber edge that is to be the top edge of the rafter.)
  - **Step 4.** Mark along the outside tongue edge of the square, which will be the plumb cut at the ridge.
  - **Step 5.** Since the length of the rafter is known to be 12 feet and 1/6 inch, measure the distance from the top of the plumb cut and mark it on the timber. Hold the square in the same manner with the 8 mark on the tongue directly over the 12-foot 1/6-inch mark. Mark along the tongue of the square to give the plumb cut for the seat (figure 7-8, step 2).




Figure 7-8. Scale or measurement method

- **Step 6.** Measure off, perpendicular to this mark, the length of overhang along the timber. Make a plumb-cut mark in the same way, keeping the square on the same edge of the timber (figure 7-8, step 3). This will be the tail cut of the rafter. Often, the tail cut is made square across the timber.
- **Step 7.** The level cut or width of the seat is the width of the plate measured perpendicular to the plumb cut, as shown in figure 7-8, step 4. Using a try square, square the lines down on the sides from all level and plumb-cut lines. Now the rafter is ready to be cut (figure 7-8, step 5).

#### EXAMPLE - Rafter layout, step 1: determine rafter length

As an example, use a rise per foot of 8 inches. To determine the approximate overall length of the rafter, measure on a steel carpenter square the distance between 8 on the tongue and 12 on the blade, because 8 is the rise and 12 is the unit of run. This distance is 14 5/12 inches. This represents the line length of a rafter with a total run of 1 foot and a rise of 8 inches. Since the run of the rafter is 10 feet, multiply 10 by the line length for 1 foot. The answer is 144 2/12 inches, or 12 feet and 1/6 inch. The amount of overhang (normally 1 foot) must be added if an overhang is to be used. This makes a total of 13 feet, which is an odd length for timber. Use a 14-foot timber.

Rafter length = total run x line length + overhang  $10 \times 14 = 5/12$  inches =  $144 \times 2/12$  inches = 12 feet + 1 foot = 13 feet

## Step-Off Method

7-14. The rafter length of any building may be determined by "stepping it off by successive steps with the square, as follows:

- **Step 1.** Step off the same number of steps as there are feet in the run. For example, if a building is 20 feet 8 inches wide, the run of the rafter would be 4 inches over 10 feet.
- **Step 2.** This 4 inches is taken care of in the same manner as the full-foot run; that is, with the square at the last step position, make a mark on the rafters at the 4-inch mark (figure 7-9, step 1).
- **Step 3.** With the square held for the same cut as before, make a mark along the tongue. This is the line length of the rafter. The seat cut and hangover are made as described above and shown in figure 7-9, steps 2, 3, and 4.

*Note*. When laying off rafters by any method, be sure to recheck the work carefully. When two rafters have been cut, it is best to put them in place to see if they fit. Minor adjustments may be made at this time without serious damage or waste of material.




Figure 7-9. Step-off method

#### Table Method

- 7-15. The framing square may have one or two types of rafter tables on the blade. One type gives both the line length of any pitch of rafter per foot of run and the line length of any hip or valley rafter per foot of run. The difference in length of the jack rafter, spaced 16 or 24 inches (on center), is also shown in the table. Where the jack, hip, or valley rafter needs side cuts, the cut is given in the table. The other type of table gives the actual length of a rafter for a given pitch and span.
- 7-16. *Rafter Table, Type 1*. Type 1 (figure 7-10, page 7-10) appears on the face of the blade. This type is used to determine the length of the common, valley, hip, and jack rafters and the angles at which they must be cut to fit at the ridge and plate.
- 7-17. To use the table, the carpenter must first know what each figure represents.
  - The row of figures in the first line represents the length of common rafters per foot of run, as the title at the left-hand end of the blade indicates.
  - Each set of figures under each inch division mark represents the length of rafter per foot of run, with a rise corresponding to the number of inches over the number. (For example, under the 16-inch mark appears the number 20.00 inches. This number equals the length of a rafter with a run of 12 inches and a rise of 16 inches. Under the 13-inch mark appears the number 17.69 inches, which is the rafter length for a 12-inch run and a 13-inch rise.) See the Type 1 layout example below.

*Note.* The other five lines of figures in the table will not be discussed, as they are seldom used in the TO.

7-18. The remaining procedure for laying out the rafters after the length has been determined is as described previously.

#### EXAMPLE - Rafter layout, table method, Type 1

NOTE: To use the table for laying out rafters, the width of the building must first be known.

Suppose the building is 20 feet 8 inches wide and the rise of the rafters is to be 13 inches per foot of run. The total run of the rafter will be 10 feet 4 inches (or 10 1/3 feet). Look at the first line of Figure 7-10. Under the 13-inch mark appears the number 17.69, which is the length (in inches) of a rafter with a run of 1 foot and a rise of 13 inches. To find the length of this rafter, use the following formula:

Rafter length = total run x length of common rafter per ft of run + 12

10 1/3 x 17.69 inches = 182.79 inches 182.79 inches + 12 = 15 3/12 feet




Figure 7-10. Rafter table, type 1

7-19. *Rafter Table, Type 2.* Type 2 (figure 7-11) appears on the back of the blade of some squares. This shows the run, rise, and pitch of rafters of the seven most common pitches of roof.




Figure 7-11. Rafter table, type 2

- 7-20. The figures are based on the horizontal measurement of the building from the center to the outside.
- 7-21. The rafter table and the outside edge of the back of the square, both the body and tongue, are in twelfths. (The inch marks may represent twelfths of an inch or twelfths of a foot.) This table is used in connection with the marks and figures on the **outside** edge of the square. At the left end of the table are figures representing the run, the rise, and the pitch:
  - In the first column, the figures are all 12 (12 inches or 12 feet). They represent the run of 12.
  - The second column of figures represents various rises.
  - The third column of figures (in fractions) represents the various pitches.
- 7-22. These three columns of figures show that a rafter with a run of 12 and a rise of 4 has a 1/6 pitch, 12 and 6 has a 1/4 pitch, and 12 and 12 has a 1/2 pitch. For example, use this scale for—
  - A roof with a 1/6 pitch (or the rise of 1/6 the width of the building) and a run of 12 feet. Find 1/6 in the table, then follow the same line of figures to the right until directly beneath the figure 7-12, page 7-12. Here appear the numbers 12, 7, 10, which is the rafter length required and

7-11

- which represents 12 feet 7 inches, and 10/12 of an inch. They are written as follows: 12 feet 7 10/12 inches.
- A roof with a 1/2 pitch (or a rise of 1/2 the width of the building) and a run of 12 feet. The rafter length is 16, 11, 6, or 16 feet 11 6/12 inches.
- A roof with a run of more than 23 feet. For example, if the run is 27 feet, find the length for 23 feet, then find the length for 4 feet and add the two. The run for 23 feet with a pitch of 1/4 is 25 feet 8 5/12 inches. For 4 feet, the run is 4 feet 5 8/12 inches. The total run for 27 feet is 30 feet 2 1/12 inches.

Note. When the run is in inches, the rafter table reads inches and twelfths instead of feet and inches.

- 7-23. See the Type 2 rafter table layout example at the top of the next page.
- 7-24. After the length of the rafter has been found, the rafter is laid out as explained previously.

#### EXAMPLE - Rafter layout, table method, Type 2

If the pitch is 1/2 and the run is 12 feet 4 inches, add the rafter length of a 12-foot run to that of a rafter length of a 4-inch run, as follows:

- For a run of 12 feet and 1/2 pitch, the length is 16 feet 11 6/12 inches.
- For a run of 4 inches and 1/2 pitch, the length is 5, 7, 11. In this case, the 5 is inches, the 7 is twelfths, and the 11 is 11/12 of 1/12, which is nearly 1/12.
- Add it to the 7 to make it 8, making a total of 5 8/12 inches, then add the two lengths together.
- This sum is 17 feet 5 2/12 inches.

Rafter lengths are given in the table. The overhang must be added. NOTE: When the roof has an overhang, the rafter is usually cut square to save time. When the roof has no overhang, the rafter cut is plumb, but no notch is cut in the rafter for a seat. The level cut is made long enough to extend across the plate and the wall sheathing. This type of rafter saves material, although little protection is given to the side wall.

## **TRUSSES**

7-25. A truss is a framed or jointed structure composed of straight members connected only at their intersections in such a way that if loads are applied at these intersections, the stress in each member is in the direction of its length. Straight, sound timber should be used in trusses. The types of trusses used in building construction are shown in figure 7-12. (The Howe and Fink trusses are most commonly used.) Truss terms are listed in figure 7-13, page 7-13.




Figure 7-12. Types of trusses

- 7-26. Trusses are used for large spans to give wide, unobstructed floor space for such large buildings as shops and hangars. Sometimes small buildings are trussed to save material. These small trusses act as rafters and give the roof rigidity.
- 7-27. The web members of a truss divide it into triangles. The members indicated by heavy lines normally carry tensile stresses for vertical loads. Sometimes the top chords of these trusses slope slightly in one or two directions for roof drainage, but this does not change the type of truss. The necessary number of subdivisions, or panels, depends upon the length of the span and the type of construction.

#### **Truss Supports**

7-28. Trusses are supported by bearing walls, posts, or other trusses. To brace a truss to a wall or post, knee braces are used as shown in figure 7-14, page 7-12. These braces tend to make a truss of the entire building by tying the wall to the roof.

#### **Purlins**

- 7-29. Purlins are used in roof construction to support corrugated sheet metal if it is used, or to support the sheathing of roofs framed with trusses.
  - In small roofs, purlins are inserted between the rafters and nailed through the rafters.
  - In large buildings where heavy trusses are used, the purlins are continuous members that rest on the trusses and support the sheathing.
  - In small buildings, such as barracks, mess halls, and small warehouses, 2 x 4s are used for purling, with the narrow side up.

Bottom Chord. A member that forms the lower boundary of the truss.

Top Chord. A member that forms the upper boundary of the truss.

Chord Member. A member that forms part of either the top or bottom chord.

Member. The component that lies between any adjacent joints of a truss; it can be of one or more pieces of structural material.

Web Member: A member that lies between the top and bottom chords.

Joint. Any point in a truss where two or more members meet; sometimes called a panel point.

Panel Length. The distance between any two consecutive joint centers in either the top or bottom chords.

Pitch. The ratio of the height of truss to the span length.

Height of Truss. The vertical distance at midspan from the joint center at the ridge of a pitched truss, or from the centerline of the top chord of a flat truss, to the centerline of the bottom chord.

Span Length. The horizontal distance between the centers of the two joints located at the extreme ends of the truss.




Figure 7-13. Truss terms

Figure 7-14. Knee braces

## **Truss Layout**

- 7-30. To lay out a truss, use figure 7-15, page 7-14, and the following steps:
  - **Step 1.** Get the material to a level spot of ground where work benches will be almost level.
  - **Step 2.** Obtain from the blueprints the measurement of all pieces to be used in the truss.

- **Step 3.** Lay out the length on the different sizes of timber and cut them accurately.
- **Step 4.** After all lengths are cut, lay them in their correct position to form a truss.
- **Step 5.** Nail them together temporarily.
- **Step 6.** Lay out the location of all holes to be bored. Recheck the measurements for accuracy.
- **Step 7.** Bore holes to the size called for on the print. Use a brace and bit or the woodborer that accompanies the air compressor. Bore holes perpendicular to the face of the timber.
- **Step 8.** After the holes have been bored, dismantle the truss and withdraw the nails.




Figure 7-15. Truss layout

#### **Truss Assembly**

- 7-31. Assembling a truss after it has been cut and bored is simple (figure 7-16). In most cases, timber connectors are used where different members of the truss join. Straight, sound timber should be used in trusses.
  - Assemble the truss with the timber connectors in place.
  - Place the bolts in the holes and tighten them.
  - Place washers at the head and nut ends of each bolt.
- 7-32. Rafters are usually made into trusses, as shown in figure 7-17. Two rafters are connected at the top, using a collar tie well nailed into both rafters. Before any ties or chords are nailed, the rafters should be spread at the lower end to equal the width of the building. This is done by using a template or by measuring the distance between the seat cuts with a tape.
- 7-33. A 1 x 6 or 2 x 4 chord is nailed across the rafters at the seat cut to tie them together. This chord forms a truss with the two rafters. A hanger or vertical member of 1 x 6 is nailed to the rafter joint and extends to the chord at midpoint, tying the rafter to the chord.
- 7-34. In wide buildings where the joists or chords must be spliced and there is no support underneath, the rafter and joists support one another as shown in figure 7-18, page 7-17.
- 7-35. If no additional bracing is needed, the truss is set in place on the plates. If additional bracing is needed, a knee brace is nailed to the chord. The knee brace forms a 45° angle with the wall stud. For easier erection, the knee brace may be omitted until the rafter truss is set in place.

7-36. Rafter framing without the use of ridgeboards may be done rapidly by using a truss assembly jig or template. The template is laid out to form a pattern conforming to the exact **exterior** dimensions of the truss.




Figure 7-16. Truss assembly




Figure 7-17. Assembling a typical truss

## Layout

- 7-37. Lay out a template as shown in figure 7-19, page 7-18, and as follows:
  - **Step 1.** Measure and mark a straight line on any selected surface. Mark the exact length of the joists that will form the truss chord. This is baseline A.

- **Step 2.** From the center of the baseline and at right angles to it, lay out a centerline (C) to form the leg of a right triangle, the base of which is half the length of the baseline (A), and the hypotenuse of which (B) is the length of the rafter measured as indicated.
- **Step 3.** Nail 2 x 4 x 8 blocks flush with the ends of baseline A and centerline C as shown in figure 7-19. Mark the centerline on the center jig blocks.

## Assembly

- 7-38. Assemble with a template as shown in figure 7-19, page 7-18, and as follows:
  - **Step 1.** Start the assembly by setting a rafter in the jig with the plate cut fitted over the jig block at one end of the baseline. The peak is flush with the centerline on the peak jig block. Nail a holding block outside the rafter at point D.
  - **Step 2.** Lay one 2 x 4 joist or chord in place across the base blocks.
  - **Step 3.** Lay two 2 x 4 rafters in place over the joist.
  - **Step 4.** Center one end of a 1 x 6 hanger under the rafter peak. Center the rafters against the peak block.
  - **Step 5.** Nail through the rafters into the hanger using six 8d nails.
  - **Step 6.** Line up one end of the chord.
  - **Step 7.** Nail through the rafter with 16d nails.
  - **Step 8.** Line up the other end of the chord.
  - **Step 9.** Nail as above.
  - **Step 10**. Center the bottom of the hangers on top of the chord and nail with 8d nails.




Figure 7-18. Truss- or rafter-support detail

#### **Installation of Trusses**

7-39. After the rafters are assembled into trusses, they must be placed on the building (figure 7-20, page 7-19). Assemble the first set of rafters either in the end section of the building or at the center. Raise rafter trusses into position (by hand) and nail them into place with 16d nails. (Temporary workbenches may be built for the workers to stand on while erecting trusses.) These trusses must be temporarily braced at the end section of the building until the sheathing is applied. Knee braces are not used on every rafter truss unless needed. Install trusses as follows:

- **Step 1.** Mark the proper positions of all truss assemblies on the top plate. The marks must show the exact position on the face of all rafters (such as south or north).
- **Step 2.** Rest one end of a truss assembly, peak down, on an appropriate mark on the top plate on one side of the structure.
- **Step 3.** Rest the other end of the truss on the corresponding mark of the top plate on the other side of the structure.
- **Step 4.** Rotate the assembly into position using a pole or rope.
- **Step 5.** Line up and secure the rafter faces flush against the marks.
- **Step 6.** Raise, align, and nail the three assemblies into position. Nail temporary 1 x 6 braces across these three assemblies. Repeat with the other assemblies as they are brought into position. Check the rafter spacing at the peaks as the braces are nailed on.
- **Step 7.** Braces may be used as a platform when raising those trusses for which there is not enough room for rotation (figure 7-21, page 7-20).




Figure 7-19. Laying out and assembling with a template

# **ROOF OPENINGS**

- 7-40. Major roof openings are those that interrupt the normal run of rafters or other roof framing. Such openings may be for ventilators, chimneys, trap-door passages, or skylight or dormer windows. Figure 7-22, page 7-20, shows roof-opening construction.
- 7-41. Roof openings are framed by headers and trimmers. Double headers are used at right angles to the rafters, which are set into the headers in the same way as joists in floor-opening construction. Trimmers are actually double rafter construction in roof openings. Nailing strips may be added if needed.




Figure 7-20. Erecting rafter trusses

# ROOF DECKING

7-42. Procedures for installing plywood sheathing is similar to installing wall sheathing except it is laid perpendicular to the rafters and trusses.

# **ROOF COVERINGS**

7-43. Asphalt and asbestos-cement roof coverings are most frequently used on pitched-roof structures. Built-up roofing is used mainly on flat or nearly flat roofs.

#### ASPHALT AND ASBESTOS-CEMENT ROOFING

- 7-44. Asphalt roofing comes in rolls (usually 3 feet wide) called *rolled roofing*, in rolled strips (usually 15 inches wide and 3 feet long), and as individual shingles. The type most commonly used is the flat strip, often called a strip shingle.
- 7-45. A 1 x 3 square-butt shingle is shown in figure 7-23, page 7-21. This shingle should be laid 5 inches to *the weather*, meaning that 7 inches of each course should be overlapped by the next higher course. The lower, exposed end of a shingle is called the *butt*. The shingle shown in figure 7-23 has a square butt

divided into three tabs. Various other butt shapes are manufactured. Asbestos-cement roofing usually consists of individual shingles.




Figure 7-21. Temporary bracing




Figure 7-22. Roof-opening construction

7-21

#### **Laying Asphalt Roofing**

- 7-46. The first step in covering a roof is to erect a scaffold to a height which will bring the eaves about waist-high to a man standing on the scaffold.
- 7-47. Before any roof covering is applied, the roof sheathing must be swept clean and carefully inspected for irregularities, cracks, holes, or other defects. No roofing should be applied unless the sheathing boards are absolutely dry.
- 7-48. An underlay of roofing felt is first applied to the sheathing. Roofing felt usually comes in 3-footwide rolls and should be laid with a 2-inch top lap and a 4-inch side lap.
- 7-49. Bundles of shingles should be distributed along the scaffold before work begins. There are 27 strips in a bundle of 1 x 3 asphalt strip shingles. Three bundles will cover 100 square feet.
- 7-50. After the first course at the eaves (the *starter course*) is laid by inverting the first course of shingles or the starter strip of mineral-surfaced roll roofing, each course that follows is begun by stretching a guideline or by snapping a chalk line from edge to edge. This positions the course.
- 7-51. Figure 7-24, page 7-22, shows the method of laying a 1 x 3 asphalt strip-shingle roof. Strip shingles should be nailed with 1-inch copper or hot-dipped, galvanized roofing nails, two to each tab; this means six nails to each full strip. Nails should be placed about 6 1/2 inches from the butt edges to ensure that each nail will be covered by the next course (*blind-nailing*) and driven through two courses.
- 7-52. An asbestos-cement roof is laid in about the same way as the asphalt strip shingles.




Figure 7-23. Square-butt asphalt strip shingle

#### **Applying Shingles at Hips and Valleys**

- 7-53. One side of a hip or valley shingle must be cut at an angle to obtain an edge line that will match the line of the hip or valley rafter. One way to cut these shingles is to use a pattern made as follows:
- 7-54. Select a piece of 1 x 6 material about 3 feet long. Determine the unit length of a common rafter in the roof. Set the framing square back up on the piece to the unit run of a common rafter on the tongue and the unit length of a common rafter on the blade, as shown in figure 7-25, A, page 7-22. Draw a line along the tongue. Saw the piece along this line and use it as a pattern to cut the shingles as shown in figure 7-25, B.




Figure 7-24. Laying an asphalt-shingle roof




Figure 7-25. Laying out a pattern

# **Installing Flashing**

7-55. Places especially susceptible to leakage in roofs and outside walls are made watertight by the installation of *flashing*. Flashing is sheets or strips of a watertight, rustproof material (such as galvanized sheet or sheet copper alloy for valleys and felt for hips). Flashing deflects water from places that are susceptible to leakage. The places in a roof most subject to leakage are the lines along which adjoining roof surfaces intersect (such as the lines followed by ridges, hips, and valleys) and the lines of intersection between roof surfaces and the walls of dormers, chimneys, skylights, and the like.

7-56. Ridge lines and hip lines naturally tend to shed water; therefore, they are only moderately subject to leakage. A strip of felt paper usually makes a satisfactory ridge or hip flashing. The ridge or hip is then finished as shown in figure 7-26. Squares are made by cutting shingles into thirds. The squares are then blind-nailed to the ridge or hip as shown in figure 7-26.




Figure 7-26. Hip or ridge flashing

- 7-57. Since water gathers in the roof valleys, they are more subject to leakage. Valley flashing varies with the manner in which the valley is to be finished. There are two common types of valley finish: the *open valley* and the *closed valley*.
- 7-58. Figure 7-27 shows part of an open valley. The roof covering does not extend across the valley. The flashing consists of a prefabricated piece of galvanized iron, copper, zinc, or similar metal, with a splash rib or ridge down the center and a small crimp at the edges. The flashing is nailed down to the valley, with nails driven in the edges (outside the crimps), as shown in figure 7-27. Care must be taken not to drive nails through the flashing inside the crimps, to avoid leakage. Figure 7-28, page 7-24, shows an open valley using rolled roofing.




Figure 7-27. Open-valley flashing




Figure 7-28. Open-valley flashing details using roll roofing

7-59. In the closed valley, the roof covering extends across the valley. Sheet metal flashing is cut into small **sheets measuring about** 18 x 10 inches, called *shingle tins*. This flashing is laid under each course of shingles, along the valley, as the course is laid. After the first course of the double course at the eaves is laid, the first sheet of flashing is placed on top of it. The second course is laid over this one so that the metal is partly covered by the next course. This procedure is continued all the way up the valley.

7-60. Shingle tins measuring about 5 x 7 inches may also be used to lay flashing up the side walls of dormers, chimneys, skylights, and similar openings. Each tin is bent at a right angle so that part of the tin extends up the side wall and the rest lies flat on the roof covering. This is called *side flashing*. In addition to the side flashing, a dormer, chimney, or skylight has a strip of flashing called an apron along the bottom of the outer wall or face. A chimney or skylight has a similar strip, called the *saddle flashing*, along the bottom of the inner wall or face. Figure 7-29 shows vertical wall flashing.




Figure 7-29. Vertical wall flashing

#### **BUILT-UP ROOFING MATERIAL**

7-61. The following building papers are used on a built-up roof. Their purpose is to prevent the seepage of bitumen through roof sheathing on which a built-up roof has been applied.

- Rosin paper is a felt paper, usually pale red, filled with rosin compound.
- Kraft paper is a light brown paper that is usually glazed.
- Sisal kraft consists of two layers of glazed kraft paper with a center section of sisal embedded in a black bituminous compound and laminated by heat and pressure.
- Roofing felt is a felt paper that has been saturated with a bituminous compound (heavy pitch or asphalt oils). The basic ingredients are usually either asbestos or rag felts. The roll may vary from 32 to 36 inches wide. Weights for built-up roofing vary from 15 to 65 pounds per square. The 15-pound felt is most commonly used because of its light weight.
- 7-62. A binder is used to bond the roofing felt together and form a watertight seal. Asphalt and coal tar are the two main types of bituminous binders used. Drying out of the binder causes deterioration of built-up roofs. If this did not happen, a built-up roof would last indefinitely. Asphalt is the preferred binder. It is used on roofs sloping up to 6 inches per foot (1/4 pitch). Asphalt has a melting point of 350° to 410°F. A roof covered with asphalt should be protected with a covering of slag, gravel, or other protective material. Tar has a lower melting point (300° to 350°F) than asphalt, so it will move more easily; therefore, it is not recommended for roofs having a slope of more than 3 inches per foot (1/8 pitch).
- 7-63. Aggregate, crushed stone, or gravel from 1/4 to 5/8 inch in diameter is embedded in a coat of asphalt or tar to hold the roof covering down. It also prevents the binding from disintegrating because of the weather.
- 7-64. Gravel stops on slag or gravel-surfaced roofs, and metal-edge strips on smooth-surfaced built-up roofs are used to finish all exposed edges and eaves to prevent wind from getting under the edges and causing blowoffs. The gravel stop also prevents the loss of gravel or slag off the edge of the roof. The *flashing flange* of the gravel stop or edge strip is placed over the last ply of felt. It should be nailed securely to the roof deck and double felt stripped. Then the finished coat of bitumen and surfacing or cap sheet should be applied. The lip of the gravel stop should extend a minimum of 3/4 inch above the roof deck. The lip of the edge strip should be a maximum of 1/2 inch above the deck. Both should be securely fastened to the fascia board

#### REROOFING

7-65. This section provides information on reroofing for the following types of roofs: asphalt-shingle roofs, asphalt-prepared roll roofings, built-up roofs, slate roofs, tile roofs, asbestos-cement roofs, metal roofs, and wood-shingle roofs.

# **ASPHALT-SHINGLE ROOFS**

- 7-66. The following types of asphalt strip shingles are used for reroofing hospitals and mobilization-type buildings with pitched roofs. These shingles are applied directly over the existing roll roofings.
- 7-67. Standard-weight shingles should be four-tab,  $10 \times 36$  inches, and intended for a 4-inch maximum exposure. Weight per square (100 square feet) applied should be approximately 210 pounds. Shingles are fastened with 1 1/4- or 1 1/2-inch nails with heads having a minimum diameter of 3/8 inch. Zinc-coated nails are best.
- 7-68. *Thick-butt shingles* should be three-tab, 1 x 3 feet, and intended for a 5-inch maximum exposure. The entire surface of the shingles should be covered with mineral granules. The bottom part of each shingle, including the part intended to be exposed and a section at least 1 inch above the cutout sections, should be thicker than the remainder of the shingle. Weight per square applied should be approximately 210 pounds. Shingles are fastened with 1 1/2- or 1 3/4-inch nails with heads having a minimum diameter of 3/8 inch. Zinc-coated nails are best.

# **Preparation of Roof Decks**

7-69. The following steps assume that the roof decks are covered with smooth or mineral-surfaced, asphalt-prepared roofing and that the shingles will be applied directly over the existing roofing.

- **Step 1.** Drive in all loose and protruding nails flush with the existing roll roofing.
- **Step 2.** Cut out all vertical and horizontal buckles and wrinkles in the existing roofing. Nail down the edges of the cuts with 3/4-inch or 1-inch roofing nails so that the entire roof deck is smooth.
- **Step 3.** If shingles are applied over smooth-surfaced roofing or over mineral-surfaced roofing which does not match the shingles, apply an 18-inch starting strip of mineral-surfaced roll roofing at the eaves. Use roofing surfaced with granules of the same type and color as the shingles.
- **Step 4.** Before the strips are applied, unroll them carefully and lay them on a smooth, flat surface until they lie perfectly flat.
- **Step 5.** Nail starter strips at the top at about 18-inch intervals. The lower edge, bent down and nailed to the edge of the sheathing board, should extend about 3/4 inch beyond the edge of the board to form a drip edge. Space the nails in the edge of the sheathing board 6 inches apart.
- 7-70. A starter strip need not be used if the shingles are the same color as the existing roofing and the existing roofing is not buckled. Figure 7-30 shows an example of roof replacement.

#### **Application of Shingles**

7-71. Shingles are attached in different ways, depending on the type.

#### Standard-Weight, Four-Tab, 10- x 36-Inch Shingles

7-72. Start the first course with a full shingle placed so that one edge, cut off flush with the tab, is also flush with the side of the roof. The bottoms of the tabs are placed flush with the eaves. Place nails about 3/4 inch above each cutout section and in the same relative position at each end of the shingle. Use two nails at every cutout. Nail at the center first, then above the cutout sections nearest the center, and finally at the ends. Nailing may start at one end and proceed regularly to the other. Complete the first course with full-width shingles applied so that the ends barely touch each other.




Figure 7-30. Roof replacement

- 7-73. Start the second course with a shingle from which half a tab has been cut. Place it so that the bottoms of the tabs are flush with the tops of the cutout sections of the shingle in the first course. Complete this course with full-width shingles.
- 7-74. Start the third course with a shingle from which one tab has been cut; the fourth with one from which one and one-half tabs have been cut; and so on, until eventually a full shingle is used again.

#### Thick-Butt, Three-Tab Shingles

7-75. Follow the same method described for standard shingles. Always nail these shingles through the thick part, about 3/4 inch above the cutout sections. The importance of nailing through the thick part of asphalt shingles cannot be emphasized too strongly. Practically all difficulties experienced with asphalt shingles on Army buildings have resulted from nailing the shingles too high.

#### Hips and Ridges

7-76. Finish hips and ridges with individual shingles furnished especially by the manufacturer or with shingles cut from strip shingles. Hips and ridges may also be finished with a strip of mineral-surfaced roofing 9 inches wide, bent equally on each side and nailed on 2-inch centers 3/4 inch from the edges.

#### **Open Valleys**

7-77. Open valleys may be flashed with 90-pound, 18-inch-wide mineral-surfaced asphalt roll roofing (figure 7-31, page 7-28) placed over the valley underlayment. It is centered in the valley with the surfaced side down and the lower edge cut flush with the eaves flashing. When it is necessary to splice the material, the ends of the upper segments are laid to overlap the lower segments 12 inches and are secured with asphalt plastic cement. A 36-inch-wide strip is placed over the first strip, centered in the valley with the surfaced side up and secured with nails.




Figure 7-31. Open-valley flashing

7-78. Before shingles are applied, a chalk line is snapped on each side of the valley for its full length. The lines should start 3 inches from the valley on both sides. The chalk lines serve as a guide in trimming the shingle units to fit the valley. The upper corner of each end shingle is clipped to direct water into the valley (figure 7-31). Each shingle is cemented to the valley lining with asphalt cement to ensure a tight seal. No exposed nails should appear along the valley flashing.

#### Closed Valleys

7-79. Closed valleys can be used only with strip shingles (figure 7-32). This method has the advantage of doubling the coverage of the shingles throughout the length of the valley. A valley lining made from a 36-inch-wide strip of 55-pound (or heavier) roll roofing is placed over the valley underlayment and centered in the valley (figure 7-32).

7-80. Valley shingles are laid over the lining by either of two methods:

- Applying both roof surfaces at the same time, with each course in turn woven over the valley.
- Covering each surface to the point approximately 36 inches from the center of the valley and the valley shingles woven in place later.
- 7-81. Either way, the first course at the valley is laid along the eaves of one surface over the valley lining and extended along the adjoining roof surface for at least 12 inches. The first course of the adjoining roof surface is then carried over the valley on top of the previously applied shingle. Each course thereafter is laid alternately, weaving the valley shingles over each other.
- 7-82. The shingles are pressed tightly into the valley and nailed in the usual manner except that no nail should be located closer than 6 inches to the valley centerline and two nails are used at the end of each terminal strip (figure 7-32).




Figure 7-32. Closed-valley flashing using woven strip shingles

#### ASPHALT-PREPARED ROLL ROOFINGS

7-83. There are two types of asphalt-prepared roll roofing: mineral-surfaced and smooth-surfaced.

#### Mineral-Surfaced Roll Roofing

7-84. Mineral-surfaced, asphalt-prepared, two-ply roofing should consist of a layer of 15-pound asphalt-saturated felt and two plies of roll roofing, cemented together with hot asphalt. Cut roll-roofing material into lengths of 18 or 20 feet, stacked free from wrinkles and buckles in protected piles. Maintain the roofing material at a temperature of at least 50°F for 24 hours before laying.

7-85. First, cover the roof areas with a layer of 15-pound asphalt-saturated felt, with all joints lapped 2 inches. Nail as required to prevent blowing off during the application of roofing. Next, lay either plain, dry unsurfaced roofing or dry mineral-surfaced roofing as a starter sheet. Lay this upside down parallel to and flush with the eaves. Nail through tin or fiber disks on 12-inch staggered centers; that is, with one row of nails on 12-inch centers placed not more than 2 inches from the lower edge, and with a second row on 12-inch centers staggered with respect to the first and about 8 inches above the first.

7-86. Over the lower half of this sheet, apply a uniform coating of hot asphalt at the rate of 30 pounds per 100 square feet. Place the first sheet of roll roofing in the asphalt. Cover the entire roof area, lapping each successive sheet, to obtain a two-ply roofing with a 2-inch head lap. Cement the lower or mineral-surfaced portion of each sheet with hot asphalt to the preceding sheet. Nail the edge through tin or fiber disks on 12-inch staggered centers. Use two rows of nails. Place the first row on 12-inch centers not more than 2 inches above the mineral surfacing and the second row on 12-inch centers staggered with respect to the first and about 8 inches above the first.

7-87. Perform the work in such a way that no fastenings or asphalt will show on the finished surface. Apply the asphalt immediately before unrolling the sheet of roofing. Do not apply the asphalt more than 3 feet ahead of the roll. Step the edge of each sheet into the asphalt so that all laps are securely sealed. Place

the end laps 6 inches in width with the underlying edges nailed on 6-inch centers, asphalt-cement the overlying edges, and step down firmly. Place one ply of roofing at eaves and edges, turn down neatly, and secure it with a wood member nailed on 8-inch centers.

# **Smooth-Surfaced Roll Roofing**

7-88. Before laying the roll-roofing material, cut it into 18-or 20-foot lengths. Stack them free of wrinkles and buckles in protected piles, and maintain them at a temperature of at least 50°F for 24 hours.

7-89. For TO construction, apply single-ply roll roofing horizontally with at least 4-inch side laps and 6-inch end laps. Nail the underlying edges of laps through tin or fiber disks on 6-inch centers. Cement overlying laps with hot asphalt or an approved cold-applied sealing compound. Step down firmly on the edges to provide proper adhesion. Double the roofing over the ridge with at least 4-inch laps. Turn roofing down neatly at eaves and edges. Nail the roofing in place on 6-inch centers. Figure 7-33 shows an example.

## **BUILT-UP ROOFS**

7-90. Buildings with roofs of relatively low pitch (less than 2 inches per foot), originally roofed with asphalt-prepared roll roofings, should be reroofed with smooth-surfaced asphalt built-up roofing or with coal-tar-pitch built-up roofing.

7-91. Use smooth-surfaced asphalt built-up roofing on buildings with original smooth-surfaced roll roofing.

7-92. Use asphalt built-up roofing or coal-tar-pitch built-up roofing on mobilization-type buildings with roofs of relatively low pitch (usually 1/2 inch per foot), originally roofed with wide-selvage, mineral-surfaced roll roofing. If the roof is nearly flat so water collects and stands, the latter type of roofing is best. Asphalt roofs may be smooth- or mineral-surfaced. Coal-tar-pitch roofs must be mineral-surfaced.




Figure 7-33. Smooth-surfaced roll roofing

## **Asphalt Built-Up Roofs**

7-93. Prepare the roof deck by driving in all loose and protruding nails and cutting out all buckles and wrinkles. Then apply a three-ply, smooth-surfaced asphalt built-up roof as follows:

**Step 1.** Lay one layer of 15-pound asphalt-saturated felt over the entire surface. Lap each sheet 3 inches horizontally and vertically and nail the laps on 12-inch centers. Also nail through the

- center of each sheet on 12-inch centers staggered with respect to the nails at the horizontal laps. Use nails long enough to penetrate into the sheathing at least 3/4 inch. They should be driven through tin or hard fiber disks.
- **Step 2.** Mop the entire surface with a uniform coating of hot asphalt, using 25 pounds per 100 square feet.
- **Step 3.** Over this coating of asphalt, lay two additional layers of 15-pound, 36-inch, asphalt-saturated felt. Lap each sheet 19 inches, and lap the sheet ends not less than 6 inches. Nail these felts through tin or hard fiber disks 1 inch from the back edge on 12-inch centers. Use nails long enough to penetrate into the wood sheathing at least 3/4 inch.
- **Step 4.** Mop each of these sheets the full width of the lap with hot asphalt, using 25 pounds per 100 square feet.
- **Step 5.** Apply a uniform mopping of hot asphalt over the entire surface, using 30 pounds per 100 square feet of roof surface.

*Note.* Do not heat asphalt above 400°F. Lay the felt while the asphalt is hot, taking care to keep the surface free from wrinkles or buckles.

- 7-94. The materials needed per 100 square feet of roof surface for the three-ply, smooth-surfaced asphalt built-up roof are—
  - Asphalt: 80 pounds.
  - Asphalt-saturated felt: 45 pounds.
- 7-95. If the existing roofing is so rough that it is impossible to obtain a smooth surface by the method described above, remove the original roofing and apply a three-ply, smooth-surfaced, asphalt built-up roof. Substitute 30-pound asphalt-saturated felt for the 15-pound felt originally specified.
- 7-96. If a slag or gravel-surfaced roof is desired for mobilization-type buildings, at step 5 above, apply 45 pounds of hot asphalt instead of 30 pounds per 100 square feet. Into this hot coating, place 300 pounds of roofing slag or 400 pounds of roofing gravel per 100 square feet of roof surface.

#### Coal-Tar-Pitch Built-Up Roofs

- 7-97. Prepare the roof surface as previously described, then apply a three-ply, coal-tar-pitch built-up roof as follows:
  - **Step 1.** Apply one layer of 15-pound coal-tar-saturated felt over the entire roof surface. Prepare it as described in step 1 of "Asphalt Built-Up Roofs."
  - **Step 2.** Mop the entire surface with a uniform coating of hot coal-tar pitch, using 30 pounds per 100 square feet.
  - **Step 3.** Over this coating of coal-tar pitch, lay two additional layers of 15-pound coal-tar-saturated felt 36 inches wide. Lap each sheet 19 inches over the preceding sheet. If 32-inch felt is used, lap each sheet 17 inches. Nail the felt 1 inch from the back edge on 12-inch centers through tin or hard fiber disks. Use nails long enough to penetrate into the wood sheathing at least 3/4 inch. Lap the ends of the sheets at least 6 inches.
  - **Step 4.** Mop each sheet the full width of the lap with hot coal-tar pitch, using 25 pounds per 100 square feet.
  - **Step 5.** Apply a uniform pouring of hot coal-tar pitch over the entire surface. Use 55 pounds per 100 square feet. While the pitch is hot, place over it 300 pounds of roofing slag or 400 pounds of roofing gravel per 100 square feet.
- 7-98. The materials required per 100 square feet of roof surface are—
  - Coal-tar pitch: 110 pounds.

- Coal-tar-saturated felt: 45 pounds.
- Roofing slag: 300 pounds.

or

• Roofing gravel: 400 pounds.

*Note.* Do not heat the coal-tar pitch above 375°F. Lay the felt while the coal-tar pitch is still hot, taking care to keep the surface free from wrinkles or buckles.

#### SLATE ROOFS

7-99. Very old slate roofs sometimes suffer failure because of the nails used to fasten the slates. In such cases, remove and replace the entire roof, including the felt underlay materials. Remove or drive in any protruding nails. Make every effort to obtain a smooth, even deck similar to the original one. Apply 30-pound asphalt-saturated felt horizontally over the entire roof deck. Lap the sheets not less than 3 inches. Turn them up 6 inches or more on vertical surfaces and over 12 inches or more on ridges and hips. Secure the sheets along laps and exposed edges with large-head roofing nails spaced about 6 inches apart.

- 7-100. Re-lay all original slates that are in good condition. Replace defective slates with new slates of the same size, matching the original color and texture as nearly as possible.
- 7-101. Recommended slate sizes for large new buildings are 20 or 22 inches long; for small new buildings, 16 or 18 inches long. Use slates of uniform length, in random widths, and punched for a head lap of not less than 3 inches.
- 7-102. Lay roof slates with a 3-inch head lap. Fasten each slate with two large-head slating nails and drive them so that their heads just touch the slate. Do not drive the nails "home." The opposite is true of wood shingles; therefore, workmen accustomed to laying wood shingles must nail slate carefully.
- 7-103. Bed all slates in an approved elastic cement on each side of hips and ridges within 1 foot of the top and along gable rakes within 1 foot of the edge. Match slate courses on dormer roofs with those on the main roof. Lay slate with open valleys.

## TILE ROOFS

7-104. Before reroofing with tiles, restore the roof deck as nearly as possible to its original condition. Replace defective boards and apply asphalt-saturated felt (30-pound type) or prepared roofing. Lap the sheets not less than 3 inches. Turn them up on vertical surfaces for at least 6 inches and over ridges and hips for at least 12 inches. Secure the sheets along laps and exposed edges with large-head roofing nails spaced about 6 inches apart.

7-105. Tiles must be free from fire cracks or other defects that will impair the durability, appearance, or weather tightness of the finished roof. Special shapes are provided for eaves starters, hips, ridges, top fixtures, gable rakes, and finials. Special shapes for field tile at hips and valleys may be factory-molded or may be job cut from whole tile and rubbed down to clean, sharp lines. Roof tiles for use on Army buildings are generally furnished in one or more of the following types:

- Mission tiles are straight-barrel-type, molded to a true arc and machine-punched for one nail and
  a 3-inch head lap. Use regular cover tile for ridges and hips. Finish with plain mission finials.
  Eaves closures and hip starters are available. Approved sizes are generally 8 inches wide by 14
  to 18 inches long.
- Spanish tiles are S-shaped and machine-punched for two nails and a 3-inch head lap. Eaves closures and hip starters are available. Use mission-type cover tiles for hips and ridges. Approved sizes are generally 9 1/2 to 12 inches wide by 12 to 18 inches long.
- *Slab-shingle tiles* are the flat, noninterlocking type, punched for two nails and a 2-inch head lap. Approved sizes are 6 to 10 inches wide, 15 inches long, and 1/2 inch thick.

#### **Mission and Spanish Tiles**

- 7-106. Before starting to lay tiles, mop the wood nailing strips with hot asphalt. Fill the spaces in back of the cant strips with asphalt cement. Lay tiles with open valleys. Set eaves closures back 3 inches from the lower edge of eaves tiles. Lay pan tiles with uniform exposure to the weather. Lay cover tiles in a uniform pattern, except where otherwise necessary to match existing roofs. Give all tiles a minimum lap of 3 inches and extend pan tiles 1 inch over the rear edge of the gutter.
- 7-107. Cut the tiles so that they meet projections with finished joints and point them up with roofer's cement. Waterproof the spaces between field tiles and wood nailing strips at ridges and hips with a fill of roofer's cement. Fit all tiles properly and then secure them with nails long enough to penetrate at least 1 inch into the wood base.
- 7-108. Fill spaces between pan and cover tiles in the first row at the eaves with solid cement mortar made of one part Portland cement, three parts fine sand, and enough clean water to form a plastic mix. Wet all tiles before applying mortar, then press them firmly into the mortar bed. Match the tile courses on dormer roofs with those on the main roof. Cut surplus mortar off neatly. Point up all open joints. Remove loose mortar from exposed surfaces.
- 7-109. Where hurricane winds can be expected, consider reinforcing tile roofs by laying all field tiles in Portland cement mortar. To do this, fill the ends of tiles at eaves, hips, ridges, rakes, and spaces beneath ridges solid with cement mortar. Fill the full width of laps between the tiles, both parallel and perpendicular to the eaves, with cement mortar.

## **Slab-Shingle Tiles**

7-110. Lay slab-shingle tiles with a 2-inch head lap. Secure each tile with two large-head roofing nails. Double the tiles at eaves and project them 1 inch over the rear edge of gutters. Lay all tiles within 1 foot of hips, ridges, and abutting vertical surfaces in roofer's cement. Lay 10- or 12-inch tiles with 1-inch head lap on the sides of dormers. Match the tile courses on dormer roofs with those on the main roof. Lay tile roofs with open valleys.

## **ASBESTOS-CEMENT ROOFS**

- 7-111. Before reroofing with asbestos-cement shingles, restore the roof deck as nearly as possible to its original condition. Replace defective boards, and apply new 30-pound asphalt-saturated felt or prepared roofing in horizontal courses. Lap the sheets not less than 3 inches. Turn them up at least 6 inches on vertical surfaces and over at least 12 inches on ridges and hips. Secure the sheets along laps and exposed edges with large-head roofing nails spaced about 6 inches apart.
- 7-112. Re-lay all asbestos-cement shingles that are in good condition. Replace defective shingles with new shingles of the same size, matching the originals as nearly as possible in color and texture.
- 7-113. Lay each shingle with a 2-inch head lap and secure it with two large-head slating nails. Drive the nails so that their heads just touch the shingles. Do not drive the nails "home" as in laying wood shingles. Bed all shingles on each side of hips and ridges within 1 foot of the edge in an approved elastic slater's cement. Project the shingles 1 inch over the rear edges of gutters. Lay shingles with a 1-inch head lap on sides of dormers. Match the shingle courses on dormer roofs with those on the main roof. Lay shingles with open valleys.

#### METAL ROOFS

7-114. To conserve critical materials, replace metal roofs with nonmetallic roofing materials.

## **WOOD-SHINGLE ROOFS**

- 7-115. When old roofing is removed—
  - Restore the roof deck as nearly as possible to its original condition. Replace rotted boards and pull out or drive down all protruding nails.

- Install flashings and apply new shingles.
- 7-116. If the existing shingle roofs can be made smooth and can be nailed properly, apply new wood shingles directly over weathered wood-shingle roofs. Reroof over existing wood shingles as follows:
  - **Step 1.** Nail down or cut off curled and warped shingles. Nail loose shingles securely, and remove or drive down protruding nails.
  - **Step 2.** Cut off the old first-course shingles at the eaves just below the butts of the second course. Replace them with a 1 x 3 or 1 x 4 strip nailed flush with the eaves line.
  - **Step 3.** Cut back the shingles at the gable ends about 3 inches. Replace them with a 1 x 2, 1 x 3, or 1 x 4 strip nailed flush with the gable end.
  - **Step 4.** Remove weathered shingles at the ridge. Replace them with a strip of beveled siding, thin edge down, to provide a solid base for nailing the ridge shingles. Treat the hip the same as the ridges.
  - **Step 5.** Fill open valleys with wooden strips level with the old shingle surface or with a narrow strip placed across the 'V" of the valley to act as a support for new flashings.
  - **Step 6.** Inspect flashings carefully. Replace terne and galvanized flashings. Reuse old flashings if they are in good condition.
  - **Step 7.** Use the following nails in applying shingles over an existing roof:
  - 5d box or special overroofing nails, 14-gauge, and 1 3/4 inches long for 16- and 18-inch shingles.
  - 6d nails, 13-gauge, and 2 inches long for 24-inch shingles.

One square of roofing will need about 3 1/2 pounds of nails.

**Step 8.** Apply new shingles as recommended by their manufacturer.

This page intentionall	y left blank.	

# **Chapter 8**

# **Doors and Windows**

This chapter covers the rough framing and finish carpentry for doors and windows. Before putting the exterior covering on the outside walls of a building, prepare the door and window openings for the frames.

# **DOORS**

8-1. Before the exterior covering is put on the outside walls, the door openings are prepared for the frames. Square off uneven pieces of sheathing and wrap heavy building paper around the sides and top of the door opening. Since the sill must be worked into a portion of the rough flooring, no paper is put on the floor. Position the paper at a point even with the inside portion of the stud to a point about 6 inches on the sheathed walls, and tack it down with small nails.

**Note.** Rough openings are usually made 2 1/2 inches larger each way than the size of the door to be hung. (For example, a 2-foot 8-inch by 6-foot 8-inch door would need a rough opening of 2 feet 10 1/2 space allows for the jambs, the wedging, and the clearance space for the door to swing.

#### **Types Of Doors**

8-2. Doors, both exterior and interior, are classified as job-built or mill-built. This classification is further broken down as batten, panel, and flush doors (figure 8-1).




Figure 8-1. Types of doors

**Note.** No hinged interior door should open or swing against a natural entry, swing into hallways, or be obstructed by other swinging doors.

#### **Job-Built Doors**

- 8-3. The batten door is the most commonly used and most easily constructed type of job-built door. It can be constructed in several ways, such as—
  - Using diagonal boards nailed together in two layers, at right angles to each other. This type of door is often used as the core for metal-sheathed fire doors.
  - Using vertical boards that are tongue-and-grooved or shiplapped. The door is held rigid by two to four cross pieces, called ledgers, which may or may not be diagonally braced. If two additional pieces forming the sides of the door and corresponding to the ledgers are used, these are called frames.
- 8-4. In hasty construction (on-site prefabrication), the carpenter makes a batten door from several 2 x 6 boards with ledgers and braces, as follows:
  - Nail the ledgers with their edges 6 inches from the ends of the door boards.
  - Place a diagonal board between the ledgers. It begins at the top-ledger end, opposite the hinge side of the door, and runs to the lower ledger, diagonally across the door. On an outside door, use roofing felt on the weather side to cover the boards.
  - Nail wooden laths around the edges and across the middle of the door to hold the roofing felt in place.

*Note.* When these doors are hung, 1/4 inch of clearance should be left around the door to allow for expansion.

Fasten T-strap hinges to the door ledgers and the hinge blocks on the door casing or post.

#### **Mill-Built Doors**

8-5. The usual exterior door is the panel type (figure 8-2). It consists of stiles, rails, and filler panels. Two frequently used interior doors are the flush and the panel types (figure 8-2).

#### Panel Doors

8-6. Panel doors consist of vertical members called stiles and horizontal members called rails. Stiles and rails form the framework into which panels are inserted. Additional vertical and horizontal members called muntins are used to divide the door into any number of panels. Panels may be solid wood, plywood, particleboard or louvered or have glass inserts.

#### Flush Doors

- 8-7. Flush doors have flat surfaces on both sides and consist of a wood frame with thin sheets of material (plywood veneer, plastic laminates, hardboard, or metal) applied to both faces. Flush doors have either a solid or hollow core.
  - Solid-core doors have a solid particle board or woodblock core which is covered with layers of veneer. They are usually used as exterior doors. Solid-core doors provide better sound insulation and have less tendency to warp.
  - Hollow-core doors have a lightweight core made of various materials that are covered with layers of veneer. They are usually used as interior doors and are less expensive to produce.

8-3




Figure 8-2. Mill-built doors

# **Specialty Doors**

8-8. Specialty doors include double doors, sliding doors, and folding doors.

# **DOOR FRAMES**

8-9. Door frames are made of the following parts: the head casing, the jambs (head and two sides), and the sill (on exterior doors only). (The principal parts of a door frame are shown in figure 8-3, page 8-4.) Doors and frames may be fabricated in the shop and installed separately; they may also be Remanufactured (prehung), purchased ready for installation.




Figure 8-3. Principal parts of a door frame

8-10. Door-frame layout calculations begin with the size of the door (height, width, and thickness), as given on the door schedule. Construction information for door frames is usually given in detail drawings like those shown in figure 8-4. In the type of frame shown in figure 8-4, the door jambs (linings of the framing of door opening are rabbeted to depths of 1/2 inch. The rabbet prevents the door from swinging through the frames. A strip of wood may be used instead a rabbet. The door stop also serves to weather proof the door. Most project drawings call for rabbeted exterior door jambs.




Figure 8-4. Types of door frames

#### **Exterior Door Frames**

- 8-11. Exterior door frames are made up of two side jambs, a head jamb, a sill, and a stop. They are constructed in several ways. In hasty construction (on-site prefabrication), the frames will be as shown in figure 8-5, page 8-6. This type requires no frame construction because the studs on each side of the opening act as a frame. Studs are normally placed 16 inches apart on center. Extra studs are added at the sides of door and window openings. Headers are usually used at the top and bottom of such openings.
- 8-12. The siding is applied to the outside wall before exterior doors are hung. The casing is then nailed to the sides of the opening. It is set back the width of the stud. A 3/4- x 3/4-inch piece is nailed over the door but set back the width of the stud; it supports the drip cap. Hinge blocks are nailed to the casing where the hinges are to be placed. The door frame is now ready for the door to be hung.
- 8-13. On an outside door, the outside casings and the sill are considered parts of the door frame. A prefabricated outside door frame—delivered to the site assembled—looks like the righthand view of Figure 8-3. It usually has the door installed, and the entire unit slides between studs.




Figure 8-5. Single outside door

# **Interior Door Frames**

8-14. Interior door frames, like outside frames, are constructed in several ways. In hasty construction (onsite prefabrication), the type shown in figure 8-6 is used. Interior door frames are made up of two side jambs, a head jamb, and stop moldings which the door closes against. Interior door frames have no sill and no casing, otherwise they are the same as the exterior frames. Figure 8-6 shows the elevation of a single inside door.

*Note.* Both outside and inside door frames may be modified to suit climatic conditions.




Figure 8-6. Single inside door

# **Door Jambs**

8-15. Door jambs (figure 8-7, page 8-8) are the linings of the framing in door openings. The casing and stops are nailed to the door jambs, and the door is hung from them. Door openings should allow 1/2 inch between the frame and the jamb (figure 8-8, page 8-9) to permit plumbing and leveling of jambs. Inside jambs are made of 3/4-inch stock; outside jambs are made of 1 3/8-inch stock. The width of the stock varies with the thickness of the walls. Inside jambs are built up with 3/8- x 1 3/8-inch stops nailed to the jamb. Outside jambs are usually rabbeted to receive the door.

### 8-16. Jambs are made and set as follows:

- Step 1. Cut the side jambs of an entrance door to the height of the door, less the depth of the head jamb rabbet (if any), plus the—
- Diagonal thickness of the sill, plus the sill bevel allowance.
- Thickness of the threshold, if any.
- Thickness of the head jamb.
- Height of the side-jamb lugs.
- Step 2. Cut the head jamb to the width of the door, less the combined depths of the side-jamb rabbets (if any), plus the combined depths of the head-jamb dadoes (grooves).




Figure 8-7. Door jambs

*Note.* Regardless of how carefully rough openings are made, be sure to plumb the jambs and level the heads when jambs are set.

- Step 3. Level the floor across the opening to determine any variation in floor heights at the point where the jambs rest on the floor.
- Step 4. Cut the head jamb with both ends square. Allow the width of the door plus the depth of both dadoes and a 3/16-inch door clearance.
- Step 5. From the lower edge of the dado, measure a distance equal to the height of the door plus the clearance required under it. Mark it and cut it square. On the opposite jamb, do the same. Make additions or subtractions on this side for floor variations, if any.
- Step 6. Nail the side jambs and jamb heads together with 8d common nails, through the dado into the head jamb.




Figure 8-8. Jam allowances

- Step 7. Set the jambs into the opening. Place small blocks on the subfloor under each jamb. Blocks should be as thick as the finished floor will be. This allows room for the finished floor to go under the door.
- Step 8. Plumb the jambs and level the jamb head. Wedge the sides with shingles between the jambs and the studs, to align them. Nail them securely in place. Take care not to wedge the jamb unevenly. Use a straightedge 5 or 6 feet long inside the jambs to help prevent uneven wedging.
- Step 9. Check the jambs and the head carefully. Jambs placed out of plumb will tend to swing the door open or shut, depending on the direction in which the jamb is out of plumb.

#### SWING

8-17. The hand of a door describes the direction in which a door is to swing and from which side it is hinged. The hand is determined from the outside of the door. A standard door has the hinges on the right or left and swings away from you. A reverse door has the hinges on the right or left and swings toward you.

#### DOOR HARDWARE

- 8-18. Most doors are hung with the loose-pin butt hinge. The pin may be removed and as a result, the door can be removed without the hinges being unscrewed. Doors should be hinged so that they open in the direction of the natural entry, open out in public buildings, and swing against a blank wall whenever possible and never into a hallway. Exterior doors use three hinges to reduce warpage caused by the difference in exposure on opposite sides and to support wider and heavier exterior doors. Interior doors use two hinges.
- 8-19. When installing hinges, the gain is the cutout or mortise made to receive a leaf of the hinge. The depth is determined by the hinge's thickness, and the width is determined by the hinge's size. Setback is the distance that the hinge is placed away from the side of the door, usually 3/16 inch.
- 8-20. The door closer is a device that closes a door and controls the speed and closing action of the door. Install the door closer according to the manufacturer's instructions.

### **DOOR INSTALLATION**

- 8-21. Doors, both mill-built and job-built, are installed in the finished door frames as described in the following steps (figure 8-9):
  - Step 1. Cut off the stile extensions, if any.
  - Step 2. Plane the edges of the stiles until the door fits tightly against the hinge side and clears the lock side of the jamb by about 1/16 inch. Be sure that the top fits squarely to the rabbeted recess and that the bottom swings free of the finished floor by about 1/2 inch. The lock stile of the door must be beveled slightly so that the edge of the stile will not strike the edge of the door jamb.
  - Step 3. After proper clearances have been made, tack the door in position in the frame and wedge it at the bottom.
  - Step 4. Mark hinge positions with a sharp-pointed knife on the stile and the jamb. Hinge positions on the stile must be placed slightly higher than the lower door rail and slightly lower than the upper door rail to avoid cutting out part of the door-rail tenons that are housed in the stile. Three measurements must be marked:
  - The location of the butt on the jamb.
  - The location of the butt on the door.
  - The thickness of the butt on both the iamb and the door.
  - Step 5. Door butts (or hinges) (figure 8-10, page 8-12) are mortised into the door frames as shown in Figure 8-11, page 8-13. Use three butt hinges on all full-length exterior doors to prevent warping and sagging. Place the butts and mortise them with the utmost accuracy so that the door will open and close properly, and so that the door, when open, will not strike the casing. The butt pin must project more than half its thickness from the casing.
  - Step 6. Using the butt as a pattern, mark the butt dimension on the door edge and face of the jamb.
  - Step 7. Cut the marked areas, called gains, on the door jambs and door to fit the butts. Use a 1-inch chisel and mallet.
  - Step 8. Test the gains. The butts must fit snugly and exactly flush with the edge of the door and the face of the jamb.
  - Step 9. Screw half of each of the butt joints on the door and the other three parts on the jamb. Place the butts so that the pins are inserted from the top when the door is hung.
  - Step 10. Set the door against the frame so that the two halves of the top butt engage. Insert the top pin. Engage and insert pins in the bottom and center butts.




Figure 8-9. Hanging a door




Figure 8-10. Door butt (hinge)




Figure 8-11. Installing door butts (hinges)

# **Door Stops**

8-22. When fitting doors, the stops are usually nailed in place temporarily until the door has been hung. Stops for doors in single-piece jambs are generally 1/2 inch thick and 2 inches wide. They are installed with a butt joint at the junction of the side and head jambs. A 45° bevel cut at the bottom of the stop, about 1 to 1 1/2 inches above the finish floor, will eliminate a dirt pocket and make cleaning or refinishing the floor easier.

# **Finish Door Trim**

8-23. Door trim is nailed onto the jambs to provide a finish between the jambs and the wall to cover wedging and spaces between the frame and studs. This trim is called casing. Sizes vary from 1/2 to 3/4 inch thick and from 2 1/2 to 6 inches wide. Most trim has a concave back to fit over uneven plaster. The casing layout depends on the way the side and head casings are to be joined at the corners. The casings are usually set back about 1/4 inch from the faces of the jambs. Care must be taken to make miter joints fit properly. If trim is to be mitered at the top corners, a miter box, a miter square, a hammer, a nail set, and a block plane will be needed. (Door trim and stop are shown in figure 8-12, page 8-14.)




Figure 8-12. Door trim and stop

- 8-24. Door openings are cased up as follows:
  - Step 1. Leave a margin of 1/4 inch from the edge of the jamb to the casing, all around. Cut one (hinge-side first) of the side casings square and even with the bottom of the jamb. Cut the top or mitered end next, allowing a 1/4-inch margin at the top.
  - Step 2. Nail the casing onto the jamb, even with the 1/4-inch margin line. Start at the top and work toward the bottom. Use 4d finishing nails along the jamb side and 6d or 8d case nails along the outer edge of the casings. The nails along the outer edge will need to be long enough to go through the casing and into the studs. Set all nailheads about 1/8 inch below the surface of the wood with a nail set.
  - Step 3. Apply the casing for the other side and then the head casing.

# **LOCK INSTALLATION**

8-25. Two types of locks used in TO construction are the cylinder and tubular locks. Cylinder locks are sturdy, heavy-duty locks designed for installation in exterior doors. They provide high security. globular locks are light-duty locks. They are used for interior doors on bathrooms, bedrooms, passages, and closets. Since door locks differ, use lock-set installation instructions, or perform the following steps:

- Step 1. After placing the hinges in position, mark off the position of the lock on the lock stile, 36 inches from the floor level.
- Step 2. Hold the case of the mortised lock on the face of the lock stile. With a sharp knife, mark off the area to be removed from the edge of the stile that is to house the entire case.
- Step 3. Mark the position of the door-knob hub and the position of the key.
- Step 4. Mark the position of the strike plate on the jamb.
- Step 5. Bore out the wood to house the lock and the strike plate and mortises. (figure 8-13 shows the installation of the lock and the strike plate.)
- Step 6. Clean and install the lock set. The strike plate should be flush or slightly below the face of the door jamb.

8-26. Panic hardware is another type of lock. It is also known as a paretic bar or fire-exit bolt. It is often installed on the exit doors of public buildings. Slight pressure on the touch bar will retract the latch bolts at the top and bottom. Install panic hardware according to the manufacturer's instructions.




Figure 8-13. Installing lock and strike plate

# **WINDOWS**

- 8-27. The most common types of windows are double-hung and hinged (or casement) windows (figure 8-14, page 8-16). All windows consist of two parts, the frame and the sash.
- 8-28. The double-hung window (figure 8-14) is made of upper and lower sashes that slide vertically past one another. Screens can be located on the outside of a double-hung window without interfering with its operation. Ventilators and window air conditioners may be placed with the window nearly closed. However, for full ventilation of a room, only one-half of the area of the window can be used. Any current of air passing across its face is lost to the room. Its frame construction and operation are more involved than that of casement windows.
- 8-29. Casement windows (out-swinging or in-swinging) may be hinged at the sides, top, or bottom. Casements have the advantage of catching a parallel breeze and slanting it into a room.
  - Out-swinging. The casement window that opens out requires the window screen to be located on the inside with a device cut into its frame to operate the casement.

In-swinging. In-swinging casements, like double-hung windows, are clear of screens, but they
are extremely difficult to make watertight, particularly against a driving rainstorm.




Figure 8-14. Types of windows

# WINDOW FRAMES

- 8-30. Window frames are made of four basic parts: the head, the jambs (two), and the sill. (The sash is the framework that holds the glass in the window.) Where openings are provided, cut away the studs and for equivalent strength, double the studs on each side of the opening to form trimmers. Insert a header at the top. If the opening is wide, the header should also be doubled and trussed. At the bottom of the opening, insert the rough sill.
- 8-31. In hasty construction, millwork window frames are seldom used. Instead, simple openings are left in the walls with the stops all nailed to the stud. The sash may be hinged to the inside or outside of the wall or may be constructed to slide. The sliding sash with overlapping panes is most common in Army construction because it requires little installation time.
- 8-32. Sills have a usual slope of 1 to 5 inches so that they shed water quickly. They are wider than frames, usually extending about 1 1/2 inches beyond the sheathing. They also form a base for the outside finished casing.

# WINDOW SASHES

- 8-33. A window is normally composed of an upper and a lower sash. There are two ordinary types of wood sashes: fixed or movable. Fixed sashes are removable only with the aid of a carpenter. Movable sashes may slide up and down in channels in the frame (double-hung), or they may swing in or out and be hinged at the side (casement type).
- 8-34. Sliding sashes are counterbalanced by sash weights that weigh half as much as the sash. Sashes are classified as single or divided, according to the number of pieces of glass (or lights).
- 8-35. A sash may be made of 1 x 3 material with reinforced, rolled plastic material, which can be cut to any desired size. For hasty construction of window sashes, perform the following steps:

- Step 1. Make two frames with the glass substitute installed on one.
- Step 2. Nail the frames together. When the two frames are nailed together, they should be turned so that the joints are not over each other. This staggers the joints and strengthens the sash. Do not make the window sash larger than the available glass substitute. If the sash is too large for the glass substitute to cover, a muntin may be placed in the sash to hold the glass substitute; this should be fastened with corrugated metal fasteners. Where long sashes are made, a muntin should be placed in the center for added strength. Figure 8-15 shows the window frame and sash details.
- Step 3. Cut the side pieces to a length equal to the height of the sash, less the width of one piece of material.
- Step 4. Cut the top and bottom pieces the same length as the window, less the width of the material.
- Step 5. Fasten at the joints with corrugated metal fasteners.




Figure 8-15. Window frame and sash details

# **ACCESSORIES**

8-36. The following are a few items that can be added to a structure to enhance efficiency:

# WINDOW SCREENS

8-37. Screen sash is usually 3/4-inch stock; however, for large windows and doors 1 1/8-inch material is frequently used or 3/4-inch lumber is braced with a horizontal member.

#### Construction

8-38. Window screen sash is usually 13/4 or 2 1/4 inches wide. Screen may be attached by stapling or tacking. Cut the screen 1 inch wider and longer than the opening. Cover the edges with molding. Next,

rabbet the inside edges about  $3/4 \times 1/2$  inch. Attach the screen in the rabbet, and nail 3/8- x 1/2-inch molding flush with the sash face.

#### **Joints**

8-39. Window sashes may be made with open mortise, four tenons, and with rails tenoned into stiles; with half-lap corners; or with butt joints or corrugated fasteners. In either of the first two cases, the joints may be nailed or glued.

### **Attaching Screen Material**

8-40. When attaching screen material, start at one end and tack or staple it with copper staples, holding the screen tightly. Next, hand-stretch the screen along the side, working toward the other end. Attach it, making sure the weave is parallel to the ends and sides. Tack the sides and apply the molding. Copper staples should be used for bronze or copper screen and cadmium staples for aluminum screens.

#### **DOOR SCREENS**

8-41. Door screens are made as shown in Figure 8-16. Two separate frames are made of 1 x 4 material for the sides and top; 1 x 6 material is used for the bottom and middle pieces. (Figure 8-17 shows door screen sizes.) The first frame is made of two side pieces as long as the door. The crosspieces are as wide as the door, less the width of the two side pieces. This frame is put together with corrugated metal fasteners or triangular corner splices; then, the screen wire is applied. The second frame is made with the crosspiece as wide as the door. The side pieces are cut to correspond with the distance between the cross-pieces. The second frame is placed over the first frame and nailed securely. For push-and-pull plates, two short 1 x 4 braces are nailed to the side opposite the hinge side.




Figure 8-16. Door screen construction




Figure 8-17. Door screen sizes

# **HOODS OR CANOPIES**

8-42. Hoods or canopies are used in tropical climates to protect the screened opening at the ends of the buildings. They are framed to the end walls with short rafters, which are nailed to the building with knee braces. The rafters are nailed to the wall, their bottom edge flush with the bottom of the end plate. The rafters and braces are made of 2 x 4s nailed with 8d or 10d nails. The sheathing is of the same material as the roof sheathing and is covered with roll roofing. The hood should extend about 2 1/2 or 3 feet from the building. Figure 8-18, page 8-20, shows hood or canopy details.




Figure 8-18. Hood or canopy details

# **Chapter 9**

# **Finish Carpentry**

After the rough framing is complete and a building is weather-tight, carpenters begin the inside finish carpentry. However, finish carpentry may be optional for TO construction. This chapter covers the following interior wall, partition, and ceiling coverings: gypsum board (or sheetrock/wallboard), plywood, and fiberboard (or chipboard). It also covers interior wall and ceiling moldings. (Doors and windows are covered in chapter 8 and general information, such as floor and wall tile, suspended ceilings, and painting, is covered in appendix D.)

Over time, "sheetrock" has become the most common term for gypsum board. Also, the term "drywall" is often loosely used to mean gypsum board/sheetrock/wallboard. In this manual we will use, "sheetrock."

# INTERIOR WALL AND PARTITION COVERINGS

9-1. In current construction, sheetrock, plywood, and fiberboard are used instead of laths and plaster to cover walls. Sheetrock is normally applied in single (sometimes double) thickness as shown in figure 9-1, page 9-2.

*Note.* When covering walls and ceilings, always start with the ceiling. After the ceiling is started, begin covering the wall in one corner and work around the room. Make sure that joints break at the center line of a stud or ceiling joist.

### PLYWOOD AND FIBERBOARD

9-2. Plywood and fiberboard can be used for interior wall coverings; however, plywood is most commonly used. It comes in 4-feet-wide and 5-to 8-feet-long sheets, 1/4 to 3/4 inch thick. It is usually applied vertically from the floor to the ceiling. When plywood is correctly applied (with flush joints), the joints do not need to be concealed. However, to improve wall appearance, joints may be covered with moldings. These may be battens fastened over the joints or applied as splines between the panels. Less expensive plywood can be covered with paint or covered in the same way as plastered surfaces. To hang plywood (or fiberboard), see figure 9-1. Figure 9-2, page 9-3, shows how to fit sheetrock on rough or uneven walls.

#### SHEETROCK

9-3. Sheetrock saves time in construction and has a short drying time as compared to plaster. It is also fire-resistant. It requires moderately low moisture content of framing members. The drying of members will result in "nail pops," which cause the nailhead to form small humps on the surface. Misaligning sheetrock on the studs may cause a wavy, uneven appearance. Wood sheathing will correct misaligned studs on exterior walls.




Figure 9-1. Hanging sheetrock and wood panels




Figure 9-2. Fitting wall panels to uneven walls

# **Types of Sheetrock**

- 9-4. The following are some of the different types of sheetrock used in construction:
  - Gypsum board is the most commonly used wall and ceiling covering in construction today.
  - *Greenboard* or *blueboard* is moisture resistant and is used in bathrooms, laundries, and similar areas.
  - *Sound-deadening board* is a sublayer used with other layers of sheetrock (usually type X).
  - Backing board has gray paper lining both sides. It is used as a base sheet on multilayer applications and is not suitable for finishing and decorating.
  - Foil-backed board serves as a vapor barrier on exterior walls.
  - *Vinyl-surfaced board* is available in a variety of colors. It is attached with special sheetrock finishing nails, screws, or channels and is left exposed with no joint treatment

• *Plasterboard or gypsum lath is* used for a plaster base. It is not compatible with Portland cement plaster.

#### **Sheetrock Dimensions**

- 9-5. Sheetrock usually comes in sheets that are  $4 \times 8$ ,  $4 \times 9$ ,  $4 \times 10$ ,  $4 \times 14$ , and  $4 \times 16$  feet. Its thickness is 1/4, 3/8, 1/2, or 5/8 inch.
  - 1/4 or 3/8 inch is used effectively in renovations to cover existing finish walls with minor irregularities. This thickness is not adequate for single-layer application.
  - 1/2 inch is most commonly used. It is adequate for studs or ceiling joists spaced 16 or 24 inches on center.
  - 5/8 inch is widely used in multiple, fire-resistant combinations. It is recommended for single-layer walls.

# **Sheetrock Edges**

9-6. Sheetrock edges are tapered 1/16 inch thinner than the body of the sheet about 1 1/4 inch on each sheet edge. The shallow channel formed will be brought level with tape and joint compound.

### **Sheetrock Application**

9-7. Sheets may be applied either horizontally or vertically; specifications may indicate which method should be used.

#### **Sheetrock Fasteners**

9-8. Nails used are specially designed with oversized heads for greater holding power and treated to prevent rust and stains. The most common is the annular-ring nail. Other types of nails include the smooth-shank, the diamond-head (used to attach two layers of sheetrock or to attach sheetrock over existing materials), and the predecorated. The predecorated nails have smaller heads, are left exposed, and are colored to match the sheetrock.

#### Nails

9-9. If the sheetrock is single nailed, the nails should be spaced 6 to 7 inches apart on the ceilings and 6 to 8 inches apart on the walls (figure 9-3). If the sheetrock is double nailed, the centers of the nail pairs are approximately 12 inches apart, with each pair 2 to 2 1/2 inches apart and the outer edges 7 inches on center (figure 9-4). The distance from the edge should be 3/8 to 1/2 inch. Do not double nail around the perimeter of a sheet.




Figure 9-3. Sheetrock applied vertically




Figure 9-4. The double-nailing system for installing sheetrock

9-10. Drive each nail slightly below the surface, forming a "dimple." Be sure not to break the paper when driving nails. The dimple creates a pocket which is filled with joint compound. Screws are made of high-quality steel; use a power screw gun or an electric drill to drive them in just below the surface without breaking the paper.

#### Adhesives

9-11. Adhesives are used to bond single-ply sheetrock directly to the framing members, furring strips, masonry surfaces, insulation board, or other sheetrock. It must be used with nails or screws.

#### Joint Compound

9-12. Joint compound is used to apply tape over joints, to cover nailheads, and to smooth and level the surface. The powdered form is mixed with water to a desired consistency. It is also available ready mixed. This is the most common form and the easiest to work with.

# Joint Tape

9-13. Joint tape is applied with the first coat of joint compound. It reinforces joints and reduces cracking. The paper type may or may not be perforated. Perforated tape is easier to bed and cover than nonperforated tape. Fiber-mesh tape is self-sticking, which eliminates the need for the first coat of bedding joint compound.

#### Metal Accessories

- 9-14. Metal accessories include the corner bead and the casing bead. The corner bead is used on all exposed (outside) corners to ensure a clean finish and to protect the outside corners of sheetrock from edge damage It is nailed or screwed 6 inches on center to en sure that it is plumb.
- 9-15. The casing (stop) bead is used where sheetrock sheets butt at wall intersections or wall and exposed ceiling intersections or where otherwise specified. It is matched to the thickness of the sheetrock.

#### **Sheetrock Tools**

- 9-16. The following are tools used in the application of sheetrock:
  - The sheetrock hammer is used for hammering nails.
  - The sheetrock carrier (lifter) is used for carrying or lifting sheetrock.
  - Sheetrock knives are used to apply and finish joint compound. The 4-inch knife is used to bed the tape in the first layer of joint compound and for filling the dimples, the 6-inch knife is used for feathering out the second coat, and the 12-inch knife is used for the third/finish coat.
  - The corner trowel flexes from 90° to 103°. It is used to apply joint compound in interior corners.
  - The mud pan is used to hold and carry joint compound.
  - The corner-bead crimper is used to fasten the corner bead by crimping.
  - The T-square is used to lay out and guide a 90° cut on sheetrock.
  - The utility knife is used to score or cut the sheetrock (figure 9-5).
  - The keyhole saw is used for cutting out irregular shapes and openings (such as outlet-box openings).
  - Surform is used to smooth sheetrock edges after cutting.
  - The tape banjo is used to apply tape (dry) or joint compound and tape (wet).
  - Sandpaper and sponges are used for feathering or smoothing dried joint compound.
  - A chalk line is used to facilitate layout.
  - A 16-foot measuring tape is used for measuring the sheetrock.
  - A 4-foot hand level is used to plumb.
  - Saw horses are used for placing sheetrock on to make cuts.




Figure 9-5. Cutting sheetrock

#### **Sheetrock Installation**

9-17. There are three steps to installing sheetrock—hanging, finishing, and patching.

# Hanging Sheetrock

- 9-18. Apply sheetrock as follows:
  - **Step 1.** Install sheetrock on the ceiling first. Measure the distance from the inside edge of the top plate to the outside edge of the second ceiling joist. Measure and cut a piece 48 inches long and to the width measured above. Install and secure the sheet to the ceiling with sheetrock nails. Nail spacing on ceilings is 5 to 7 inches on center.
  - **Step 2.** Determine the starting point of the wall. Using a measuring tape, locate a section where the studs are  $\sim$  foot on center and where a full sheet could be laid horizontally. Check the layout

- to ensure that there will be no joints above or below the door or window openings. Sheets will be installed from the ceiling down to the floor, starting at the ceiling.
- Step 3. Install the first sheet. With the help of another person, place a sheet of sheetrock in position so that the edges fall on the center of the studs. Place the sheet snug against the ceiling, using a hand level to ensure that it is level. Secure the sheet with sheetrock nails 6 to 8 inches on center, 3/8 inch from the edge. Install succeeding sheets on the top half of the wall against installed sheets, ensuring that joints fall on the center of the studs and proper nail spacing is maintained. Using a utility knife or sheetrock saw, cut out openings for doors and windows.
- **Step 4.** Lay out the receptacles. Measure the distances from an inside corner to both sides of the receptacle box and record them. Measure the distance from the installed sheetrock to the top and bottom of the receptacle box, and record them. Measure and mark these dimensions for the receptacle cutout, allowing 1/16-inch clearance all around.
- **Step 5.** Cut out the opening for the receptacle. With a utility knife, drive a hole within the opening. Using a keyhole saw, cut out the opening. Use a slight undercut bevel so that the back opening is larger than the front opening.
- **Step 6.** Install the prepared sheet. Place the prepared sheet in position, ensuring that the receptacle fits in the opening without breaking the paper. Make adjustments to the opening if necessary. Secure the sheet to the studs with sheetrock nails. Using a Surform, smooth the rough edges of the openings as necessary.
- **Step 7.** Lay out and cut sheets for corner posts. Measure and cut the required number and sizes of sheets to cover corner posts. Scrap pieces of material may be used.
- **Step 8.** Install the corner bead. Using a corner-bead crimper, install the corner bead on the exterior corners of corner posts. Nails may be used if necessary.

#### Finishing Sheetrock

- 9-19. The finishing process consists of covering nailheads and covering seams (covering seams is also referred to as *finishing joints*). Finish sheetrock as follows:
  - **Step 1.** Check for improperly recessed nails by running the edge of a sheetrock knife over the nailheads. A clicking sound indicates a nail needing to be recessed.
  - **Step 2.** Use a 4-inch knife and mud pan with joint compound to apply a smooth coat of joint compound over the nails. Remove any excess compound.
  - **Step 3.** Use the knife and mud pan to apply a heavy coat of joint compound over a sheetrock joint, horizontal or vertical. A heavy coat is enough to ensure a good bond between the tape and sheetrock and to fill in tapered edges. Measure and cut the tape to the length required for a joint. Keeping the tape centered over the joint, start at one end of the joint and work toward the opposite end. Using the knife, press the tape into the compound, removing all excess compound. Work off all excess joint compound, being careful not to wrinkle the tape or leave air bubbles. Continue to tape all the joints in the same manner.
  - **Step 4.** Use a 4-inch knife to apply a heavy coat of joint compound over the sheetrock at the inside corner. Measure and cut the tape to the length required for the joint. Fold the tape in half lengthwise, keeping both edges even. Use a corner tape creaser if necessary. Apply the tape at the top and work downward, running the edge of your hand at the center of the tape to ensure that it is in the corner. Using the inside corner tool, press the tape into the compound, working off all excess compound and being careful not to wrinkle the tape or leave air bubbles.
  - **Step 5.** Apply the first coat of joint compound over the tape then apply a medium coat of joint compound. Feather the compound with the 6-inch knife to about 2 to 3 inches on each side of the joint. A good job of feathering and smoothing will minimize sanding later.

- **Step 6.** Apply the second coat of joint compound over the tape and nail coverings. The joint compound previously applied must be completely dry. Use the 4-inch knife to apply a thin coat of compound over the nails, removing any excess compound. Using the steps above, apply the second coating to the joints using the 6-inch knife and feathering out 6 to 8 inches on each side of the joint.
- **Step 7.** Apply the third coat of joint compound. The joint compound previously applied must be completely dry. Using the step above, apply the third coat using the 10-inch knife and feathering out 10 to 12 on each side of the joint. Nails should not require a third coat, but it may be applied if necessary.
- **Step 8.** Using a damp sponge or fine sandpaper, sand the surface to a smooth finish, ensuring that there are no voids and that the surface is ready to receive paint.

# Patching Sheetrock

- 9-20. There are several different methods of patching sheetrock, depending on the size of the hole.
- 9-21. For small holes, apply fiber-mesh tape directly over the hole. Cut the tape with joint compound and feather the edges. Sand or sponge the area smooth after it has dried.
- 9-22. For fist-size holes, cut out a rectangle around the hole with a keyhole saw. Cut a piece of backing (1 x 2 or 1 x 3) slightly larger than the opening itself. Glue or screw the backing into place. Cut a patch and glue it to the backing using either wallboard adhesive or mastic. Apply tape and coat it with compound. Feather the edges. Sand or sponge the area smooth after it has dried.
- 9-23. For large holes, mark and cut a rectangular section around the damaged area, reaching from the centers of the nearest studs. Cut a patch and screw or nail it to the studs. Apply tape and coat it with compound. Feather the edges. Sand or sponge the area smooth after it has dried.

# BASE MOLDING

- 9-24. The interior trim of a building should match or complement the design of the doors, the windows, and the building. Base molding is the trim between the finished wall and the floor. It is available in several widths and forms. Figure 9-6 page 9-10, shows the types of base molding.
- 9-25. Square-edge (or two-piece) baseboard consists of a square-edged baseboard topped with a small base cap. When the wall covering is not straight and true, small base molding will conform more closely to the variations than will a one-piece base alone. This type of baseboard is usually 5/8 x 3 1/4 inches or wider. Installation of square-edged baseboard is shown in figure 9-7, page 9-10.




Figure 9-6. Types of base molding

9-26. Narrow- and wide-ranch base (one-piece baseboard) are  $3/4 \times 3 \cdot 1/4$  inches or wider and vary from  $1/2 \times 2 \cdot 1/4$  inches to  $1/2 \times 3 \cdot 1/4$  inches or wider.




Figure 9-7. Installing base molding

- 9-27. A wood member at the junction of the wall and carpeting serves as a protective bumper; however, wood trim is sometimes eliminated. Most baseboards are finished with a 1/2- x 3/4-inch base shoe. A single-base molding without the shoe is sometimes placed at the wall-floor junction, especially where carpeting might be used.
- 9-28. Baseboard should be installed with a butt joint at the inside corners and a mitered joint at the outside corners. (The baseboard installation in figure 9-7 is done with square-edge baseboard.) It should be nailed to each stud with two 8d finishing nails. Base molding should have a *coped joint* at inside corners and a mitered joint at outside corners. A coped joint is one in which the first piece is square cut against the plaster or base and the second molding is coped. This is done by sawing a 46° miter along the inner line of the miter. The base shoe should be nailed into the subfloor with long, slender nails, but not into the baseboard itself. Then, if there is a small amount of movement in the floor, no opening will occur under the shoe. When several pieces of molding are needed, they should be joined with a lap miter (figure 9-8). When the face of the base shoe projects beyond the face of the molding, it abuts (figure 9-9, page 9-12).




Figure 9-8. Trim lap-miter joint




Figure 9-9. Base-shoe trimming

# **CEILING COVERINGS**

9-29. In current construction, sheetrock, plywood, and fiberboard are used instead of laths and plaster to cover ceilings.

# **SHEETROCK**

- 9-30. Cut the panels and treat the joints the same as for walls and partitions, making sure that joints break on the centers of ceiling joists.
- 9-31. A brace may be constructed and used to raise and hold a sheet in place when fitting and nailing the sheet to the ceiling joists. Nail sheets with the lengths going across ceiling joists to prevent sagging (figure 9-10).

# **PLYWOOD**

9-1. Plywood is hung the same on ceilings as on walls and partitions.




Figure 9-10. Brace for holding ceiling panels

#### **FIBERBOARD**

- 9-2. Fiberboard sheets are 1/2 to 2 inches thick. For a smooth cut on these sheets, use a utility knife. Fiberboard sheets are attached directly to the joists. To improve ceiling appearance, cover the joints between the sheets with batten strips of wood or fiberboard. Smaller pieces of fiberboard (tiles) require furring strips (wooden strips nailed across joints) (figure 9-11, page 9-14).
- 9-3. Fiberboard sheets also come in small (rectangular or square) pieces called *tiles*, which are often used for covering ceilings They may be made with a lap joint, which permits blind-nailing or stapling through the edge. They may also be tongue-and-grooved, fastened with 2d box nails driven through special metal clips.
- 9-4. For fiberboard tiles that need solid backing, place furring strips at right angles across the bottom of the joists. Place short furring pieces along the joists between the furring strips. Nail metal channels to furring strips and slide the tiles horizontally into them. In lowering ceilings (usually in older buildings), metal channels are suspended on wire. Some large (2 x 4 foot) tile panels are installed in individual frames.




Figure 9-11. Furring strips on ceiling joists

# **CEILING MOLDINGS**

- 9-5. Ceiling moldings are sometimes used at the junction of the wall and the ceiling to finish the sheetrock paneling (sheetrock or wood). Inside corners should be coped joints. This ensures a tight joint even if minor moisture changes occur. Figure 9-12 shows ceiling molding.
- 9-6. For sheetrock walls, a small, simple molding might be best. For large moldings, finish nails should be driven into the upper wallplates and also into the ceiling joist, when possible. (For plastered ceilings, a cutback edge at the outside of the molding will partially conceal any unevenness of the plaster and make painting easier where there are color changes.)




Figure 9-12. Ceiling molding

# Chapter 10

# **Nonstandard Fixed Bridge**

A bridge is a structure that carries a roadway over a depression or an obstacle. Bridges may be classified in different ways. Two general classifications, for example, are highway and railroad bridges. One of the bridges most commonly found in the TO is the nonstandard fixed bridge. This chapter discusses the construction of both the substructure and the superstructure of this important military bridge.

# **BRIDGE CLASSIFICATION**

- 10-1. A bridge completely supported by its two end supports (abutments) is called a *single-span* bridge. A bridge having one or more intermediate supports between the abutments is a *multispan* bridge. All supports of a fixed bridge transmit the load directly to the ground.
- 10-2. A nonstandard fixed highway bridge (figure 10-1) is a semipermanent bridge constructed from local materials or Class IV materials drawn from a depot. It differs from standard bridges, which are prefabricated bridges assembled at the site. The most common nonstandard fixed highway bridges are the simple, stringer-type (the stringers being logs) and those made of structural grade timber or structural steel.
- 10-3. A military bridge has two principal parts: the lower part (substructure) and the upper part (superstructure).




Figure 10-1. Nonstandard fixed highway bridge

# SUBSTRUCTURE

10-4. The substructure of a bridge supports the superstructure. The substructure consists of

#### **ABUTMENTS**

10-5. There are two types of end supports or abutments: footing and pile.

#### **Footing**

- 10-6. The footing abutment consists of—
  - Footings. Footings transmit the load to the ground. They receive the load from the sill and distribute it over a sufficient area to keep the support from sinking into the ground.
  - *Sill*. The abutment sill (figure 10-2) receives the load from the stringers and transmits it to the footings.
  - End dam. The end dam (or bulkhead) is a wall of planks at the end of the bridge to keep the approach road backfill from caving in between the stringers.




Figure 10-2. Timber sill abutment

# Pile

- 10-7. The pile abutment (figure 10-3) has three main parts:
  - Piles driven into the ground, transmitting the load to the soil.
  - A cap on top of the piles to receive the load from the stringers.
  - Sheeting fastened to the piles to hold the backfill in place.




Figure 10-3. Pile abutment and retaining wall

### INTERMEDIATE SUPPORTS

10-8. The following are some of the different types of intermediate supports.

#### **Pile Bent**

- 10-9. The pile bent (figure 10-4) consists of the bent cap, which provides a bearing surface for the stringers and transmits the load to the piles; and the piles, which transmit the load to the soil. The support for the loads may come either from column action, when the tip of the pile bears on a firm stratum such as rock or hard clay, or from friction between the pile and the soil into which it is driven. In both cases, earth pressure must give some lateral support; transverse bracing is also often used for this purpose.
- 10-10. The pile bent is used for highway bridges only. It is designed to carry both vertical and lateral loads and can be used for spans of up to 50 feet. Its ground-to-ground height is a function of its unbraced length.

#### **Trestle Bent**

- 10-11. The trestle bent (figure 10-4) is like the pile bent except that posts take the place of piles. The posts transmit the load from the cap to the sill, the sill transmits the load to the footings, and the footings transmit the load to the soil. The length of the posts varies according to the height of the bridge above the gap to be spanned. Transverse bracing like that used with the pile bent is provided.
- 10-12. The trestle bent is used for highway bridges only; however, unlike the pile bent, it is designed to carry vertical loads only. It can be used for spans of up to 30 feet and for ground-to-grade heights of up to 12 feet.




Figure 10-4. Pile bent and trestle bent

# **Pile-Bent Pier**

10-13. The pile-bent pier (figure 10-5, page 10-4) is composed of two or more pile bents with a common cap. The cap transmits the load to the corbels (short, stringer-like members) that, in turn, transmit the load to the individual bent caps and then to the piles and to the soil. Piers usually have cross bracing which ties the bents together, giving them longitudinal rigidity.

10-14. The use of multiple bents gives the pile-bent pier great strength. As a result, the pile-bent pier can be used for both highway and railroad bridges. It will carry both vertical and lateral loads, can be used for spans of up to 200 feet, and its ground-to-grade height is governed by its unbraced length.




Figure 10-5. Pile-bent pier

### **Trestle-Bent Pier**

- 10-15. The trestle-bent pier (timber-trestle pier) (figure 10-6) is the same as the pile-bent pier, except that it has sills and footings which transmit the load to the soil.
- 10-16. The trestle-bent pier is used for highway bridges only. It is designed to carry vertical loads only and can be used for spans of up to 60 feet and for ground-to-grade heights of up to 18 feet.

#### **Crib Pier**

- 10-17. The crib pier (figure 10-7, page 10-6) is quite different from pile and trestle piers. It is composed of logs or dimensioned timber fitted together in log-cabin style and is usually filled with rock or other stable fill material. The crib pier should be made so that it needs no exterior bracing. As an expedient, crib piers may be built to the height of the stringers, eliminating the trestle bents.
- 10-18. The crib pier is used for highway bridges only. It is for vertical loads only and can be used for a span of up to 50 feet and a ground-to-grade height of up to 12 feet.

### **BRACING**

- 10-19. Bracing consists of longitudinal bracing, transverse bracing, and diaphragms.
- 10-20. Longitudinal bracing (figure 10-8, page 10-7) is used to stabilize the bridge centerline.
- 10-21. Transverse bracing (figure 10-8) provides stability at right angles to the centerline. It is sometimes called sway or lateral bracing.




Figure 10-6. Trestle-bent pier

10-22. *Diaphragms* are braces between stringers to prevent them from deflecting laterally (buckling) under load. In spacing these diaphragms, the ratio of distance between diaphragms to the width of the top of stringer (L/b ratio) should not exceed 30 for timber.

L = distance between diaphragms

b = width of top of stringer

Example. If the stringer is 6 inches wide—

L = 30 L = 180 inches (15 feet)

10-23. In this example, diaphragms should be used every 15 feet between stringers 6 inches wide.




Figure 10-7. Crib pier

10-7




Figure 10-8. Bracing

## **CONSTRUCTION PROCEDURES**

10-24. The following paragraphs contain construction procedures for a trestle-bent bridge. This includes laying out the centerline and constructing abutments, retaining walls, and trestle bents.

## **Layout of Centerline**

- 10-25. The first task in constructing a trestle-bent bridge is laying out the centerline (figure 10-9, page 10-8):
  - **Step 1.** Stretch a line or tape representing the centerline across the stream or ravine.
  - **Step 2.** Attach the line to stakes driven into the ground at least 15 feet behind the proposed location of the abutment sills. For defiles wider than 100 feet, use intermediate stakes as needed to prevent sag.
  - **Step 3.** Place the line at the level of the intended top of the flooring or at some known distance above or below it.




Figure 10-9. Laying out a centerline

#### **Construction of Abutments**

- 10-26. Saving time in abutment construction is especially important on short bridges. Abutment and approach preparation often requires as much time as the rest of the bridge. Use the simplest abutment possible; often a timber sill with timber footings is adequate (page 10-2).
- 10-27. The end dam is installed after the stringers and planks.
- 10-28. After the centerline is fixed—
  - **Step 1.** Place the abutment sill at approximately its correct location under the tape. See that it is at right angles to the centerline by using a line from the centerline stake 15 feet behind the sill to each end of the sill. Both distances must be the same.
  - **Step 2.** Once the sill is properly located, mark its position and remove it to construct the foundation.
  - Remove the earth as needed to provide a level surface for footings. The sill must be level and supported equally by each footing when installed. Make sure that the surface supporting the footings is about 2 inches higher than its final position to allow for settling. Do not dig too deeply. If this is done by mistake, do not backfill with earth. Instead, raise the level with planking.
  - Place the two outside footings so that their outer edges are under the ends of the sill. Place the long dimension of the footings parallel to the bridge centerline.
  - Place the remaining footings, equally spaced, between and in line with the outside footings.
  - Place the sill on the footing centerline so that the load is in the middle of each footing. Place the sill with the largest dimension vertical.
  - Provide for drainage of the abutment area.

## **Construction of Retaining Walls**

10-29. Retaining walls and revetments, when needed, are part of the abutment construction. The simplest type of retaining wall is built of planks or logs supported by piles or posts. (Figure 10-10 shows an abutment and retaining wall; figure 10-11, page 10-10, shows retaining-wall details.)

- Use wing walls to prevent the earth from washing out behind the retaining wall.
- Drive piles or posts 4 feet into the ground.
- Fasten anchor cables from the top of the piles to a deadman behind the retaining wall or to the wing-wall end. These deadmen and anchors can be eliminated if two or three rows of piles, driven as far as they will go, are used.
- For long spans and heavy loads, the abutment and retaining wall are often constructed as a unit. This may also be necessary where steep banks and poor soil conditions exist.




Figure 10-10. Abutment and retaining wall




Figure 10-11. Retaining-wall details

## **Construction of Trestle Bents**

10-30. After the position of the near-shore abutment sill is established, locate the position of the first trestle bent:

- **Step 1.** Measure the length of the first span from the abutment sill along the centerline (figure 10-12).
- **Step 2.** Drive a small stake under the centerline where the center of the trestle bent is to be. Use a plumb bob if necessary.

- Step 3. Continue this procedure until all trestle bents and the far-shore abutment sill are located.
- **Step 4.** Excavate and place footings under the trestle bent the same as for the abutment (page 10-7). Outside footings under the trestle sill are centered under the outside posts of the bent.
- Measure the vertical distance from the centerline down to the top of the footings.
- If the centerline was placed at the intended top of the flooring, this distance minus the thickness of the tread, deck, and stringers gives the height of the trestle bent.
- If steel stringers are to be used, allow also for the thickness of the nailing strips.
- **Step 5.** To obtain the correct height of the trestle-bent posts, subtract the thickness of the cap and sill from the height of the trestle bent.




Figure 10-12. Determining trestle-bent height

#### **Additional Construction Procedures**

- 10-31. There are some additional procedures that should be followed when constructing a substructure.
  - Make the length of the cap and sill equal to the roadway width plus 2 feet.
  - Center the outside posts under the roadway edges 1 foot from the ends of the cap and sill. Space other posts evenly between the outside posts.
  - Use driftpins or bolts to fasten the sill and cap to the posts. Use scabbing instead of driftpins for fast erection.
  - Nail transverse bracing across both sides of the bent. Usually 3- x 12-inch planks are used. Fasten the bracing to each post that it passes over. Cut the bracing so that the ends extend beyond where they are nailed, to prevent splitting.
  - Put the bent into position, using a plumb bob to ensure that it is straight. Hold it in place with temporary braces nailed to stakes driven into the ground. Use these temporary braces until the permanent longitudinal bracing can be nailed to the outside posts of adjacent trestle bents.

## **SUPERSTRUCTURE**

10-32. The superstructure is the spanning structure consisting of stringers, flooring (decking and tread), and other features such as curbs, handrails, sidewalks, and end dams.

#### **STRINGERS**

10-33. When wood stringers are used, they are usually long enough to extend across the abutment sills and trestle caps on which they rest. Stringers of one span are lapped with those of the next span.

## **Placing Stringers**

- 10-34. After the abutment and trestle bents are in place, the stringers are installed (figure 10-13).
- 10-35. When stringers are lapped, place one outside stringer so that its inside face is under the inside face of one curb. Place the other outside stringer so that its outside face is under the inside face of the other curb. Stringers can then be lapped with a similar spacing on the next span. The remaining stringers are usually spaced evenly between the outside stringers. On some narrow one-lane bridges, stringers may be grouped closer together under the vehicle tracks.
- 10-36. When stringers are butted, or continuous across the span, place the outside faces of both outside stringers under the inside faces of the curbs.




Figure 10-13. Stringer placement

## **Fastening Stringers**

10-37. Fasten stringers (figure 10-14) as follows:

#### **Wood Stringers**

10-38. Fasten wood stringers by driving nails diagonally through the side of the stringer into the cap or by driftbolts. When using driftbolts, bore a hole, smaller in diameter and 3 inches shorter than the driftbolt, through the stringer and into the cap.

#### Steel Stringers

10-39. Fasten steel stringers by—

- Driving railroad spikes into the cap beside the flange.
- Driving 60d nails partially into the cap and bending them over the bottom flange.
- Driving nails or driftbolts through prebored holes in the bottom flange.

**Note.** When steel stringers are not fastened through their flanges, frequent inspection is necessary to be sure the stringers have not shifted. Fasten wood nail strips to the top flange of steel stringers to provide a means of fastening the flooring.




Figure 10-14. Fastening stringers

10-40. When a laminated deck (planks placed on edge) is to be installed, the planks may be fastened to steel stringers either by using metal clips provided for the purpose or by driving nails partially into the deck and bending them around the stringer flange (figure 10-15, page 10-14).




Figure 10-15. Open laminated deck, sectional view

## **FLOORING**

10-41. The flooring system of a typical timber-stringer trestle bridge consists of two main parts: the decking and the tread.

## **Decking**

10-42. The decking is the part of the structure that is laid on the stringers to form the roadway across the trestle bridge. Decking may be laminated or solid plank.

#### Laminated

- 10-43. Laminated decks may be solid or open with uniform spacing between members.
  - For an open laminated deck (figure 10-16) where the planks are long enough to reach completely across the width, use two spacing blocks between laminations. Place spacers on the stringer nearest one-third the length of the lamination. Where the laminations are not long enough (usually true for two-lane bridges), lap the laminations on a central stringer. Put a spacer block at each outside stringer.
  - For a solid laminated deck, place laminations solidly against one another.




Figure 10-16. Open laminated deck

## Solid Plank

- 10-44. For a solid-plank deck (figure 10-17, page 10-16), lay planks horizontally, at right angles to the stringers. Leave a 1/4-inch space between planks to allow for swelling when wet.
- 10-45. Extend the decking about 2 feet at approximately 5-foot intervals to support the handrail posts (figure 10-18, page 10-16).

## **Tread**

10-46. The tread consists of planks placed over the decking and between (but not under) the curbs. The planks are usually 2 or 3 inches thick, of varying lengths, and are laid parallel to the direction of traffic. On one-lane bridges, the tread is limited to the path of the wheels or track. Two-lane bridges are fully covered with tread. (Figure 10-19, page 10-17, shows tread placement.)




Figure 10-17. Solid-plank deck




Figure 10-18. Extended deck for handrail support




Figure 10-19. Tread placement

#### **CURBS**

10-47. A curb system on a timber-trestle bridge is used to guide traffic on the bridge. When assorted sizes of lumber are available, make curbs of 6-  $\times$  6-inch timber supported on 6-  $\times$  12-  $\times$  30-inch curb risers, spaced on about 5-foot centers. The curb is usually bolted to the decking with 1/2-inch bolts, two per curb riser.

#### HANDRAILS

10-48. Handrails (figure 10-20, page 10-18) mark the bridge route and provide safety for pedestrians crossing the bridge. Make handrails of 2- x 4-inch or larger material, if available. Over a laminated deck, make handrail posts and knee braces of the same material as the deck so that they can be fastened snugly between the laminations, which are extended to receive them.

10-49. For solid-plank decks, toenail 4 x 4 posts, or two 2 x 4s nailed together, to the extended planks. Make the posts 42 inches high and space them on 5-foot centers. Place the posts so that the distance from the inside face of the curb to the inside face of the handrail is at least 10 inches.

## **SIDEWALKS**

10-50. If sidewalks are necessary, form them by extending the decking an additional 36 inches. Place stiffening members underneath the outside edge. Support them with braces attached to the stringers, where necessary.

## END DAM

10-51. The end dam is the wall that withstands the earth pressure of the abutment of a bridge (see figure 10-1, page 10-1). After the stringers and flooring are in place, construct an end dam of flooring planks across the end of the stringers. The end dam should extend across the roadway from the top of the footing to the top of the tread. After placement of the end dam, complete the approach up to the top of the bridge deck. Post the traffic-control and classification signs. The bridge is now ready for traffic.




Figure 10-20. Standard curb and handrail

## Chapter 11

## **Timber-Pile Wharves**

Wharves are used for loading and unloading ships. This chapter describes how a carpenter constructs a timber-pile wharf. The topics covered include—

- Layout and installation of piles for pile-wharf construction.
- Construction of a wharf superstructure.
- Installation of docking hardware.

(For more detailed information on timber-pile wharves, see TM 3-34.41.)

## TYPES OF WHARVES

- 11-1. Wharf is an overall term that applies to any waterfront structure designed to make it possible for vessels to lie alongside the shore for loading and unloading. The term *wharf* is confined in practice to the T- and U-type *marginal* wharves (figure 11-1, page 11-2). A marginal wharf usually consists of a timber or steel superstructure supported by a series of timber, steel, or concrete pile bents.
- 11-2. The other structures shown in figure 11-1 are called *piers*, except the *quay*. A quay is a reinforced landing place made toward the sea or at the side of a harbor. All structures shown in Figure 11-1 may consist of fill supported by bulkheads.

## TYPES OF PILES

11-3. To protect a wharf against normal wear and tear, three types of piles are used: bearing, fender, and mooring piles. The types of piles are discussed in the following paragraphs:

## **BEARING PILES**

11-4. Bearing piles support the wharf or pier framework and decking. The piles should be straight and measure at least 6 inches across the top, 18 inches across the butt (bottom), and from 60 to 80 feet in length. Pile length varies according to the depth of the water and condition of the bottom. Bearing piles should be spaced from center to center 6 to 10 feet apart in one direction and 5 feet apart in the other direction.

## **FENDER PILES**

11-5. The force of a moving ship coming in direct contact with bearing piles is enough to collapse an unprotected wharf. To protect and absorb the initial shock, fender piles are placed about 2 1/4 feet out from the centerline of the outside row of bearing piles. These piles are placed about 18 feet apart and along the sides where ships dock.




Figure 11-1. Common wharves

#### MOORING PILES

11-6. Mooring piles are aligned with the outside row of bearing piles and are spaced about 30 feet apart. This type of pile is braced along the outside row of bearing piles and usually extends to about 4 feet above the floor (or deck) of the platform. The 4-foot extension provides ample space to secure mooring lines.

*Note.* Timber piling must be treated with creosote or some other preservative Compound to protect it from fungi and marine borer attacks.

## INSTALLATION OF PILES

11-7. Pile-driving equipment and the methods of driving and pulling piles are covered in TM 3-34.41. The equipment is operated by a special crew, but the carpenter is present during the pile driving to direct the alignment of the piles.

## **USING SPECIAL TOOLS**

- 11-8. Since most of the heavy timbers used to build waterfront structures cannot be manhandled, special tools, known as logger's tools (figure 11-2), are used to move and place these timbers. They consist of—
  - *Peavy and cant hooks.* Lever-type tools, used mainly to roll timbers.
  - *Timber carriers*. Two-man tools, used mainly to pick up and carry timbers.
  - *Pike poles.* Used to hold or steady timbers while they are being placed.
  - *Cranes*. Normally, two men are assigned to a crane: the operator and the helper. The helper drives the crane carrier (truck) and hooks and unhooks loads. Using standard signals, the helper tells the operator when to lift and lower the load and where to position it. After the heavy timbers have been moved and placed, the carpenter's level is used to level them properly.

*Note.* Although the crane cannot be considered a special tool, it is mentioned here because of its use to raise and lower heavy timber.




Figure 11-2. Logger's tools

## STRAIGHTENING PILES

11-9. Piles should be straightened as soon as any misalignment is noticed. The desired accuracy of alignment varies with each job; however, if a pile is more than a few inches out of plumb, it should be set true. The greater the penetration along the wrong line, the more difficult to get the pile back into plumb. To realign piles, use one of the following:

- A block and tackle (figure 11-3), with the impact of the hammer jarring the pile back into line.
- A jet (figure 11-4, page 11-4), either alone or in conjunction with a block and tackle.
- A block and tackle and an alignment frame (figure 11-5, page 11-4) to pull the piles In a bent into proper spacing and to align them after they have been driven.

11-10. When a floating pile driver is used, a frame (template) for positioning piles may be fastened to the hull. A floating template (figure 11-6, page 11-5) is sometimes used to position the piles in each bent. The spacing of battens is such that the centerline between them is on the pile line desired. Battens are placed far enough apart so that, as the pile is driven, the larger diameter butt end will not bind on the template and carry it underwater.




Figure 11-3. Realigning with a block and tackle




Figure 11-4. Realigning with a jet




Figure 11-5. Realigning with a frame




Figure 11-6. Floating template

- 11-11. A chain or collar allows the template to rise and fall with the tide. If the ends of the battens are hinged and brought up vertically, the template may be withdrawn from between the bents and floated into position for the next bent. Several templates may be used for a bent; or a single template is moved, if the pile spacing is uniform. The position of the piles is controlled as follows:
  - **Step 1.** After each bent has been driven, a line is run back from each pile in the outer bent to the corresponding pile in each of the next several bents shoreward.
  - **Step 2.** The alignment and longitudinal spacing of the outshore bent are verified.
  - **Step 3.** Any deviation in position of previously driven piles is made up when the template is positioned for the next bent. Piles that are slightly out of position may later be pulled into place as described previously in the first paragraph.

## **CUTTING PILES**

11-12. The lengths of pile selected for a structure should be such that the butts are 2 or 3 feet higher than the desired finished elevation after driving to the desired penetration. Since the pile capping should bear evenly on every pile in the bent, trimming should be carried out accurately by nailing saw guides across all piles in the bent. Figure 11-7, page 11-6, shows cutting piles.




Figure 11-7. Cutting piles

#### **CAPPING TIMBER PILES**

- 11-13. Caps are large timbers placed on top of the timber-bearing piles to support the superstructure. The pile capping is fastened as shown in figure 11-8 and as follows:
  - **Step 1.** After the piles have been cut, the cap is put in place; a hole for a driftpin is bored through the cap into the top of each pile; and the driftpins are driven into the holes.
  - **Step 2.** At a joint between pile cap timbers, a splice scab is bolted across the joint to each side of the pile cap.
  - **Step 3.** The working platform, aligning cables, or spacing frame may then be removed, since the driftpins will hold the piles in the proper position.

#### **BRACING PILES**

- 11-14. Bents are braced as shown in figure 11-8 and as follows:
  - **Step 1.** Bolt diagonal timbers to each pile with the bracing running in one diagonal direction on one side of the bent and in the opposite diagonal direction on the other side.
  - **Step 2.** If the piles in a bent differ a lot in diameter at the point of bracing, make one of the following corrections:
  - Large piles may be flattened down with an ax (hewed or dapped).
  - Small piles may be blocked out with filler pieces.
  - The flexibility of the braces may be used to pull them tight against the piles.
- 11-15. Figure 11-9 shows transverse bracing.




Figure 11-8. Capping and bracing piles




Figure 11-9. Transverse bracing for different size piles

## WHARF SUPERSTRUCTURE

11-16. After the timber pile bents have been aligned, braced, and capped, the construction of the wharf superstructure is begun. Building the superstructure consists of installation of the stringers, the decking, and the curbs or stringpieces; and erection of the fender systems. Figure 11-10, page 11-8, shows stringers and decking in place.

#### **STRINGERS**

11-17. Stringer positions are measured from the centerline of the wharf. The stringers are toenailed to the pile caps with two 3/8- x 10-inch spikes at each bearing point. The ends of the stringers overlap to provide complete bearing on the pile caps. Spacer blocks are toenailed between stringers with two 60d nails.




Figure 11-10. Stringers and decking in place

#### **DECKING**

11-18. Standard decking consists of 4- x 8-inch planks, which are spiked to each stringer with two 5/16- x 7-inch spikes, and set with 1/4-inch spacing. Openings greater than 1/4 inch may be used between planks in areas that are subject to heavy rains.

## **STRINGPIECES**

- 11-19. The stringpiece (or curb) is placed on 2- x 10-inch blocking, 24 inches long, spaced on 48-inch centers along the edge of the deck. Stringpiece bolts are countersunk and the hole is seated with bituminous material. (Figure 11-11 shows a wharf-edge cross-section of a timber-pile wharf.)
  - When the stringpieces are *parallel* to the direction of the wharf stringers, the stringpieces are bolted through the blocking, the decking, and the stringer end pieces.
  - When the stringpieces are *perpendicular* to the direction of the stringer, they are bolted through the blocking, the decking, alternate stringers, and the pile cap.

## FENDER PILES AND CHOCKS

- 11-20. Timber is the most suitable material for wharf fenders in TO construction. Fender piles serve the following purposes:
  - They cushion a wharf from the impact of ships and protect the outer row of bearing piles from damage.
  - They protect the hulls of craft from undue abrasion.

- 11-21. The 3- or 4-foot extension of a fender pile above the deck level of a wharf supplements wharf-mooring hardware, but is not used for warping a ship into or out of the berth.
- 11-22. Since fender piles are not part of the structural support of the wharf, they are easier to replace than bearing piles.




Figure 11-11. Wharf-edge cross-section of a timber-pile wharf

#### **Protection of Fender Piles**

- 11-23. Protective devices that lengthen the life of fender piles are—
  - A heavy timber wearing ribbon, which may easily be replaced. It is sometimes installed along a line of fender piles at the elevation receiving the heaviest abrasion.
  - Floating logs or camels (floating fenders).
  - Rope wrappings, particularly on corner fenders.

## Fender Piles for Quays

11-24. Structures that are almost completely rigid, such as solid-fill quays, sometimes have fender piles backed up with heavy springs to give a combination of yield and resistance.

#### **Installation of Fender Piles**

11-25. Fender piles are driven at a slight batter (angle). Usually 1 to 12 fender piles are used along the outside edge of all rows of bearing piles, except on the extreme inshore wharf sections. Every third fender pile may extend 3 to 4 feet above the curb. The others are cut off flush with the top of the curb.

#### **Chocks and Wales**

- 11-26. Chocks are timber braces placed between fender piles at the level of the stringpiece or pile cap to hold them in position and give them lateral stability. Chock ends should be firmly seated against the piles.
  - On *timber-pile* wharves, each chock is fastened with two bolts through the stringer endpiece or pile cap.
  - On *steel-pile* wharves, each chock is bolted by 12- x 12-inch blocks driftpinned to the ends of the stringers or bolted to the ends of the wharf pile cap.
- 11-27. Wales (horizontal beams) are used at mean low water elevation when tidal currents are swift or tidal variations are great. Wales add rigidity to fender piles. A 12- x 12-inch continuous longitudinal timber wale is bolted to the back fender of each pile. Timber chocks are placed between fender piles and bolted to the line wales.

#### PILE CLUSTERS AND CORNER FENDERS

11-28. Pile clusters, whether at the faces or corners of wharves or acting as dolphins (isolated pile clusters), must combine beam strength, rigidity, and stability against horizontal stresses. Therefore, the individual piles that make up the cluster must be joined so that the cluster will act as a unit.

## **Mooring Piles**

- 11-29. Clusters of three or more piles are used to supplement or replace wharf-mooring hardware. The top of the cluster is lashed together.
- 11-30. Mooring piles are placed at intervals along the wharf face when bollards and other mooring hardware are not avail able. A maximum of three piles of each cluster extends 3 feet or more above the wharf deck.

#### **Corner Fenders**

- 11-31. Piles clustered at exposed corners of the wharf, bolted and lashed together, are provided so that a ship may use the corner to pivot when warping in and out of the berth. The wharf is strongly reinforced at the corners with layers of diagonal planking laid one across the other. This reinforcing is backed up with diagonal batter piles.
- 11-32. The standard corner-fender cluster is made up of 10 piles battered for adequate spacing at the points. Timber connectors may be used in conjunction with the bolts to tie the piles more firmly into a single rigid member. To avoid undue abrasion to ship hulls and to outside pile surfaces, heavy rope mats may be lashed to the clusters at the level of contact. To supplement mooring hardware, the corner piles extend 3 to 4 feet above deck level.

#### Deck Reinforcing on Wood-Pile Wharves

- 11-33. Before stringers are set, wooden piles battered inward are driven to support a cap, set diagonally across each corner, and bolted to the bottom face of the other caps. Another piece of cap timber is set to act as a strut between the fender cluster and the diagonal cap.
- 11-34. The space between the cluster and the diagonal cap is then floored over with two layers of plank each 6 inches thick, laid diagonally (and transversely to each other) to fill the thickness between the cap timbers. To complete the reinforcement, stringers are set close and spiked together over the outer half of each corner panel.

#### Deck Reinforcing on Steel-Pile Wharves

11-35. In steel-pile marginal wharves and piers with corner fenders, the deck in each corner panel is similarly reinforced with timber. Wood piles battered inward carry a diagonal cap timber bolted to the bottom flanges of the steel-pile caps. The diagonal cap is strutted against the fender cluster, the diagonal layers of plank are applied, and the stringers are set close and spiked together, as described above for wood-pile wharves.

## FLOATING LOG FENDERS (CAMELS)

- 11-36. Floating logs are used to absorb part of the impact shock when a ship is berthed. They protect the surface of fender piles while a ship is tied up. The simplest type of fender is a single line of floating logs, each secured by two or more lengths of 1/2-inch galvanized chain fastened to 3/4-inch eyebolts in the fender log and the wharf pile. Some arrangement, such as loose steel collars around the wharf piles, is provided to allow the logs to rise and fall with the tide.
- 11-37. Floating clusters of logs or strongly constructed rafts are called camels. In addition to absorbing impact shock and protecting fender piles from the sliding friction of a ship moving in the berth, camels may be required to breast a ship off the face of the wharf into deeper water.

## PILE-MOORING DOLPHINS

- 11-38. Dolphins (figures 11-12 and 11-13, pages 11-12 and 11-13) are isolated clusters of piles to which a ship may be moored. The center of the cluster, called a king pile, may be a single pile or a cluster driven vertically and wrapped to act as a unit. The other piles are driven in one or more concentric rings around the king pile, each battered towards the center. The king pile is normally left somewhat longer than the others for use as a mooring post.
- 11-39. When composed of a cluster, the king pile is wrapped with at least six turns of 1-inch diameter galvanized wire rope, stapled to each pile at every turn.
- 11-40. Two wrappings of the type described above are used for the pile cluster. One wrapping is located near the top of the cluster and the second about 2/3 the distance above mean low water.




Figure 11-12. Typical pile dolphin

11-41. To further ensure that the cluster will act as a unit, the piles are chocked and bolted together approximately 2 feet above mean low water.




Figure 11-13. Typical dolphin plan views

## DOCKING HARDWARE

11-42. Ships tie up to wharves with lines fastened to mooring fittings such as bollards, corner mooring posts, cleats, chocks, and pad eyes (figure 11-14, page 11-14).

- Bollards, single- or double-bitt, are steel or cast-iron posts to which large ships are tied. They prevent ships' lines from riding up off the post. Bollards may have waist diameters smaller than ton diameters and may have caps, or projecting, rounded horns. Double-bitt bollards are also known as double bitts or double steamship bitts. Bollard bodies may be hollow for filling with concrete after installation They are usually designed to take line pulls of about 35 tons.
- Corner mooring posts are usually designed to take pulls of up to 60 tons.
- *Cleats* are generally cast iron, with arms extending horizontally from a relatively low body. The base may be open or closed. Cleats are used for securing smaller ships, tugs, and workboats.
- Open or closed *chocks*, generally made of cast iron, are used for directing and snubbing lines when working a ship into or out of its berth. A closed chock must be used when there is a change in both vertical and horizontal directions of a line.
- Pad eyes are metal rings mounted vertically on a plate and intended to receive a ship's line spliced with thimble and shackle. They are used only for securing small craft.

#### HARDWARE INSTALLATION

11-43. Proper installation requires that the vertical and horizontal stress on any structural unit on which mooring hardware is attached be partially transferred to the wharf structure. This is done by increasing the number and size of stringers under the hardware installation, and by providing anchorage for mooring hardware bolts that will transfer the stress through the pile cap of one or more bents to several piles.




Figure 11-14. Mooring hardware

## **Stringer Reinforcement**

11-44. The number and size of stringers are increased at the location of major hardware items. When base widths of hardware are greater than 12 inches, but less than 24 inches, at least two 12- x 12-inch stringers are needed. For base widths greater than 24 inches, but less than 36 inches, three 12 x 12-inch stringers are needed; and so forth. Stringers are laid close together and are spiked to each other and at each bearing point. Mooring hardware bolts pass through stringers, filler blocks, and anchorage timbers.

#### **Standard Installation**

- 11-45. Standard wharf structures use the following mooring hardware:
  - Pier, 90 x 500 feet—six large double-bitt bollards on each side on 100-foot centers and five 42-inch cleats on each side centered between bollards.
  - Offshore marginal wharf, 60 x 500 feet— six large double-bitt bollards and five 42-inch cleats spaced as above on the outshore side only.
  - Lighterage quay 35 x 500 feet—eleven 42-inch cleats on 50-foot centers.

#### **Nonstandard Installation**

- 11-46. For nonstandard wharf structures, mooring hardware should be installed in numbers, types, and spacing approximately that of standard wharves.
- 11-47. When cleats and pad eyes are not available, every third fender pile must be extended 3 to 4 feet above the wharf deck. Fender-pile extensions may be used to steady a ship in the berth, but not to winch a ship into position.
- 11-48. On berths located near enough to the shore, bollards or mooring posts may be located onshore.

#### Location

11-49. Bollards and other mooring hardware are placed clear of cranes and traffic and as close to the curb as possible. Onshore mooring anchors should be located so that the lines will not have to be moved for traffic.

#### ANCHORAGES FOR HARDWARE

11-50. The following paragraphs explain the different types of hardware and their uses:

#### **Location Between Pile Bents**

11-51. To provide anchorage for heavy items of mooring hardware located between pile bents, a grillwork of  $12 \times 12$  timbers is bolted underneath the pile cap (figure 11-15). Each of the four piles directly affected by the upward pull on the grillwork is strapped to the pile cap with 3- x 3/8-inch steel strapping. The straps are spiked to piles and pile caps. Filler blocks of  $12 \times 12$  timbers are centered to receive the mooring hardware bolts.




Figure 11-15. Timber grillwork

#### **Location on Pile Bents**

- 11-52. Mooring hardware is also located directly over the outside bearing pile of a bent as shown in Figure 11-16, page 11-16. Mooring hardware with 22- to 26-inch bolt centers is anchored as follows:
  - Two 12 x 12 by approximately 20-foot-long timbers are bolted under the pile cap over which the hardware is located and to both sides of three piles of the bent.
  - 12 x 12-inch filler timbers approximately 4 feet long are bolted to the wharf pile cap under the hardware bolt location.
  - Each of the three piles directly affected by the upward pull on the grillwork is strapped to the pile cap with steel strappings as described above (see figure 11-15).
- 11-53. Items of mooring hardware with bolt centers greater than 26 inches require using timber wider than 12 inches or doubling the number of timbers, or locating the hardware between bents using the timber grillwork anchorage described previously.

## **Bracing**

11-54. The wharf structure is longitudinally braced at the location of bollard installations. Diagonal bracing is done from just below the pile caps to about low-water level at the location of each bollard. The cross bracing is bolted to each pile.




Figure 11-16. Mooring hardware over bearing pile

## **Installation of Light Items**

11-55. Light items of mooring hardware with bolt centers less than 8 inches, such as cleats, chocks, and pad eyes, are bolted through the stringpiece, blocking, decking, and stringer end piece.

# Appendix A

# **CONVERSION TABLES**

Metric to US			US to Metric		
LENGTH					
1 mm = 0.04 in (0.03937 in)		1 yd = 91	1 yd = 91.44 cm		
1 cm = 0.3937 in		1 ft = 30.4	1 ft = 30.48 cm		
1 m = 3.281 ft or 1.094 yd = 39.3707 in		1 in = 2.5	1 in = 2.54 cm		
1 km = 0.621 statute - mile		7/8 in = 2	7/8 in = 2.22 cm (22.22 mm)		
1 km = 0.5399 nautical mile (nmi)		3/4 in = 1	3/4 in = 1.90 cm (19.05 mm)		
		5/8 in = 1	5/8 in = 1.59 cm (15.88 mm)		
		1/2 in = 1	1/2 in = 1.27 cm (12.70 mm)		
		3/8 in = 0	3/8 in = 0.98 cm (9.52 mm)		
		1/4 in = 0	1/4 in = 0.64 cm (6.35 mm)		
		1/8 in = 0	1/8 in = 0.32 cm (3.18)		
		AREA			
1 sq cm = 0.155 sq in		1 sq in =	1 sq in = 6.45 sq cm		
1 sq m = 10.76 sq ft or 1.196 sq yd		1 sq ft = 0	1 sq ft = 0.0929 sq m		
1 sq km = 0.386 sq miles		1 sq yd =	1 sq yd = 0.836 sq m		
1 hectare (ha) = 2.47 acres		1 sq mi =	1 sq mi = 2.59 sq km		
		1 acre = 0	1 acre = 0.405 ha		
		1 acre = 4	1 acre = 43560 sq ft		
LINEAR MEASURE					
Metric Denomi	nation N	leter	US Equivalent		
	1 millimeter	= 0.001	= 0.0394 in		
10 millimeters	= 1 centimeter	= 0.01	= 0.3937 in		
10 centimeters	= 1 decimeter	= 0.1	= 3.937 in		
10 decimeters	= 1 meter	= 1.	= 39.3707 in = 3.28 ft		
10 meters	= 1 dekameter		= 32.809 ft		
10 dekameters	= 1 hectometer		= 328.09 ft		
10 hectometers	= 1 kilometer	= 1,000.	= 0.62138 mi		
10 kilometers	= 1 myriameter	= 10,000.	= 6.2138 mi		

This page intentionall	y left blank.	

## Appendix B

## **Carpentry Abbreviations and Symbols**

## **ABBREVIATIONS**

B-1. Carpenters use the following abbreviations in connection with lumber:

ad air-driedal all lengthav average

avw average width
avl average length

bd boardbf board footbdl bundlebev beveled

**bm** board (foot) measure

btr better
clg ceiling
CL centerline
clr clear

**CM** center-matched; that is, tongue-and-groove

joints are made along the center of the edge

of the piece.

com common
csg casing
ctg crating
cu ft cubic foot

**D&CM** dressed (one or two sides) and center-

matched

**D&M** dressed and matched; that is, dressed one or

two sides and tongue and grooved on the edges. The match may be center or standard.

**ds** drop siding

**D&SM** dressed (one or two sides) and standard-

matched

D2S&CM dressed two sides and center-matched
D2S&SM dressed two sides and standard-matched

0 diameterdim dimensione edge

**FAS** firsts and seconds, a combined grade of the

two upper grades of hardwoods fbk flat back feet board measure (board feet) fbm fcty factory (lumber) flat grain fg flg flooring free of knots fok frm framing ft foot or feet hdl handle (stock) hdwd hardwood hrt heart hrtwd heartwood in inch or inches kiln-dried kd knocked down kd lbr lumber lgr longer lgth length lin ft linear foot; that is, 12 inches lr log run log run, mill culls out lr mco thousand m thousand (feet) board measure mfbm mill culls out mco merch merchantable mill run mr mfsm thousand (feet) surface measure mixed width mw number no 1s & 2s ones and twos, a combined grade of the hardwood grades of firsts and seconds ord order p planed pattern pat pky pecky plain, as in plain sawed pln partition pn

qtd rd

rdm

round random

quartered (with reference to hardwoods)

res resawed
rfg roofing
rfrs roofers
rip ripped

rl random lengthrw random width

**S&E** surfaced one side and one edge

S2S&M surfaced two sides and standard- or center-

matched

S2S&SM surfaced two sides and standard-matched

sap sapwood

**S1E** surfaced one edge

S1S1E surfaced one side and one edge S1S2E surfaced one side and two edges

S2E surfaced two edges S4S surfaced four sides

**S&CM** surfaced one or two sides and center-matched **S&M** surfaced and matched; that is, surfaced one or

two sides and tongue and grooved on the edges. The match may be center or standard.

**S&SM** surfaced one or two sides and standard

matched

**S2S&CM** surfaced two sides and center matched

sb standard beadsd seasonedsdg sidingSel select

sesd square-edge siding

sf surface foot; that is, an area of 1 square foot

sftwd softwoodshd shipping dryshipshiplap

sm standard matchedsnd sap no defect

snd soundsq squaresq e square edge

sq e&s square edge and sound

sgrssquaresstdstandardstkstock


sw sound wormy

t&g	tongue and groove	
tb&s	top, bottom, and sides	
TO	theater of operations	
tbrs	timbers	
vg	vertical grain	
wal	wider, all length	
wdr	wider	
wt	weight	
wth	width	

## **SYMBOLS**

B-2. Symbols commonly used in carpentry are given below. For additional information on the various symbols used in construction plans and blueprints, refer to TM 5-704.

## **ARCHITECTURAL**



Outside door:	Hot-water tank
Brick wall	Grease trap
Frame wall	Hose bibb or sill cock
Inside door: frame wall	V 12
Shingles (siding)	Lavatories:
Wood, rough	Pedestal
Wood, finished	Wall hung
Cased or arched opening	Corner
Single casement window	Tank
Double-hung window	Flush valve
Double casement window	
Insulation:	Urinals: Stall type
Loose fill	Wall hung
Board or quilts	Laundry trays
Cut stone	Built-in shower
Ashlar	Shower
Plumbing	Sinks:
Bathtubs:	Single drain board
Corner	Double drain board
Free standing	
Floor drain	
Shower drain	

# 

# Appendix C

# **Manpower Estimates**

C-1. This chapter contains tables (C-1 through C-14, pages C-1 through C-8) which may be used in preparing manpower estimates for carpentry work. The tables do not include provisions for loading and hauling materials to the job site. All tables presume average working conditions terms of weather, skill, crew size, accessibility, and the availability of equipment

Table C-1. Rough framing

Work element description	U	Init	Man-hours/unit
Beams (3- 2" x 8")	1,000-bd-ft me	easure	30
Floor joists, sills	1,000-bd-ft me	easure	25
Bridging	100 pr		5
Wall frames, plates	1,000-bd-ft me	easure	45
Furring, including plugging	1,000-bd-ft me	easure	32
Blocking	1,000-bd-ft me	easure	20
Grounds for plaster	1,000 lin ft		48
Door bucks	ea		3
Ceiling joists	1,000-bd-ft me	easure	25
Rafters	1,000-bd-ft me	easure	45
Trusses (span feet)	Each	Man-hours assembly	Man-hours placement
20		1.5	1
30		2.0	8
40		12.0	8
50		20.0	6*
60		24.0	6*
80		32.0	6*
Typical crew: 1 leader and 8 workers.  * Assumes the use of an organization			ers on guylines.

Table C-2. Sheathing and siding

Work element description	Unit	Man-hours/unit
Wall sheathing	1,000 sq ft	
Building paper		8
Tongue and groove		24
Plywood		16
Fiberboard		16
Roof decking	1,000 sq ft	
Tongue and groove		32
Plywood		20
Siding	1,000 sq ft	
Plywood		16
Corrugated asbestos		32
Drop siding		32
Narrow bevel		48
Shingles		40
Typical crew: 1 leader and 8 wor	kers	

Table C-3. Insulation

Work element description	Unit	Man-hours/unit
Thermal	1,000 sq ft	
Board		
Floor*		32
Wall		8
Ceiling		24
Roof		24
Rock wool		
Loose		16
Batts		12
Foil alone		8
Rigid foam		24
Acoustic	1,000 sq ft	
Strip		24
Quilt		8
Typical crew: 1 leader and 4 work	kers	
* Install vermin shield		

Table C-4. Finish carpentry

Work element description	Unit	Man-hours/unit
Walls	1,000 sq ft	
Plywood		32.0
Plasterboard (includes tape)		48.0
Ceilings	1,000 sq ft	
Wood		48.
Plasterboard (includes tape)		64.0
Cemented tile		32.0
Panel with suspension		72.0
Baseboard (2 member)	1,000 lin ft	72.0
Molding (chair)	1,000 lin ft	48.0
Door frame, trim	ea	2.5
Sliding door with pocket	ea	8.0
Window frame, trim	ea	3.0
Installing prefab closets	ea	16.0
Setting kitchen cabinets	ea	1.5
Shelving	1,000 sq ft	64.0
Chalkboard (complete)	1,000 sq ft	64.0
Stairs		
Closed stringer, built on job	story	16.0
Closed stringer, prefab	story	8.0
Open stringer	story	24.0
Typical crew: 1 leader and 3 to 8 wor	rkers	

Typical crew: 1 leader and 3 to 8 workers

For small rooms, increase time required for wall- and ceiling board installation by 30 to 50 percent

\* Includes furring strips when necessary

**Table C-5. Door installation** 

Work element description	Unit	Man-hours/unit
WOOD DOORS AND FRAMES		
Door frames and trim		
Single exterior	ea	3
Double exterior	ea	3
Single interior	ea	3
Double interior	ea	4
Sliding door frame	ea	4
Door - fit, hang, and lock		
Single exterior	ea	5
Double exterior	ea	8
Single interior	ea	5
Double interior	ea	7
Screen doors	ea	2
METAL DOORS		
Single	ea	6
Double	ea	9
MISCELLANEOUS DOORS COMPLETE WITH TRIM AND HARDWARE		
Rolling, manual operated	ea	29
Rolling, motor-operated	ea	35
Sliding, manual-operated	ea	20
Sliding, motor-operated	ea	25
Sliding, fire	ea	19
Garage doors		
Wood 16' x 7'	ea	8
Aluminum 16' x 7'	ea	10
Scuttles	ea	10
CAULKING	1,000 lin ft	5
Includes jambs stops, casings, and weather Does not include sills and thresholds	stripping	

Does not include sills and thresholds On wood doors, if power planes hinge butt routers, and lock mortises are used, deduct 25 percent from installation time.

Table C-6 Flooring

Work element description	Unit	Man-hours/unit
Wood floors	1,000 sq ft	
Subfloor		
Tongue and groove		24
Plywood		16
Finish floor		
Softwood		24
Hardwood		32
O-ft till-	4.000 #	
Soft tile	1,000 sq ft	
Cemented		24
Nailed		32
Linoleum	1,000 sq ft	32
Typical flooring crew: 1 leader ar	nd 4 workers	

Table C-7. Window installation

Work element description	Unit	Man-hours/unit
Wood windows		
Double hung	ea	4
Casement, single	ea	4
Fixed wood sash	ea	3
Jalousie	ea	2
Skylights	ea	8
Louvers	ea	5
Screens	ea	2
Venetian Blinds	ea	2
Metal windows		
Double hung	ea	2
Casement	ea	2
Commercial projected	ea	2
Skylights	ea	9
Weather striping	ea	3

Table C-7. Window installation

Work element description	Unit	Man-hours/unit
Caulking	1,000 sq ft	16

Suggested crew size: 2 to 16 workers

Installation includes drilling fasteners, expansion sills, installing plugs, toggle blocking, hinges, locks, and other hardware

For special panic-device doors, add three hours for single doors and four hours for double doors.

Table C-8. Built-up roofing, insulation, and flashing

Work element description	Unit	Man-hours/unit
Roofing	1,000 sq ft	
2 ply		12
3 ply		20
4 ply		25
5 ply		30
Insulation	1,000 sq ft	25
Flashing	1,000 sq ft	60
Typical crew: 1 leader and 6 wo	rkers.	

Table C-9. Roll roofing

Work element description	Unit	Man-hours/unit
Paper (plain) and felt	1,000 sq ft	7
Asphaltic aluminum (including primer)	1,000 sq ft	18
Canvas (including 2 coats of paint)	1,000 sq ft	25
Typical crew: 1 leader and 6 workers		

Table C-10. Shingle roofing

Work element description	Unit	Man-hours/unit
Wood	1,000 sq ft	35
Slate	1,000 sq ft	55
Metal	1,000 sq ft	50
Asphalt	1,000 sq ft	30
Typical crew: 1 leader and 4 wo	orkers	

Table C-11. Metal, asbestos-cement, and tile roofing (pitch at least 3 inches per foot.)

Work element description	Unit	Man-hours/unit
Metal (corrugated and V-crimp)	1,000 sq ft	
Wood purlins		18
Metal purlins		36
Sheet (seamed)		60
Asbestos-cement	1,000 sq ft	
Wood purlins		35
Metal purlins		45
Tile	1,000 sq ft	
Clay		55
Metal		60
Typical crew: 1 leader and 5 workers		

Table C-12. Pile bracing and capping

Work element description	Unit	Man-hours/unit
Bracing*	ea	
Horizontal		1.0
Diagonal		0.8
	4 000 %	
Capping	1,000 sq ft	
Wood		100.0
Steel		150.0

Table C-12. Pile bracing and capping

Work element description	Unit	Man-hours/unit
Concrete		200.0
Typical crew: 1 leader and 6 works	ers	
*Table based on 4-inch x 10-inch x	4-foot bracing memb	ers

Table C-13. Pier framing

Work element description	Unit	Man-hours/unit
Stringers	1,000-bd-ft measure	40
Bridging	1,000 lin ft	40
4-inch deck	1,000 sq ft	20
2-in wearing surface	1,000 sq ft	16
Bull rail	1,000 lin ft	60
Bumper	1,000 lin ft	36
Typical crew: 1 leader and 10 workers		

Table C-14. Deck hardware

Work element description	Unit	Man-hours/unit
Bits	ea	3
Bollards	ea	4
Chocks	ea	3
Cleats	ea	2
Pad eyes	ea	1
Typical crew: 1 leader and 4 workers		

#### Appendix D

## **General Information**

#### FLOOR AND WALL TILE

- D-1. The following paragraphs include information pertaining to the various types of tile and their installation procedures.
- D-2. The number of tiles needed is calculated by performing the following procedures:
- D-3. First, calculate the square feet of the area to be tiled. If you are using 12-inch-square tiles, the total floor area (in square feet) equals the total number of tiles needed, plus an additional 10 percent waste factor. If another size of tiles is being used, multiply the area by 144 to convert to square inches. Then divide that number by the area (square inches) of the tiles to find the required amount (include a 10 percent waste factor).

Example: You are using tiles 9 x 9 inches. To tile a floor 12 feet long and 9 feet wide—

Multiply the room dimensions to find the area:  $12 \text{ feet } \times 9 \text{ feet} = 108 \text{ square feet}$ 

Multiply the area by 144:  $108 \times 144 = 15,552$  square inches

Calculate the area of the tile: 9 inches x 9 inches = 81 square inches

Divide the room area (square inches) by the tile area (square inches): 15,552 divided by 81 = 192

Add 10 percent waste factor: 192 + 19 = 211 tiles required

#### RESILIENT FLOOR TILE

- D-4. Resilient floor tile is durable, easily maintained, comfortable and attractive, and low cost. It is made of rubber, vinyl, linoleum, and asphalt. Common sizes of this tile are either 9 x 9 inches or 12 x 12 inches.
- D-5. A notched trowel (used for spreading adhesive) and a tile cutter are required for installation. To lay out and install resilient floor tile, perform the following procedures:
- D-6. Locate the center of the end walls of the room. Establish a main centerline by snapping a chalk line between these two points. Lay out another centerline at right angles to the main centerline. This line may be established using a framing square or the triangulation method. With the centerline established, make a trial layout of the tiles along the centerlines. Measure the distance between the wall and the last tile. If this measurement is less than 1/2 tile, move the centerline half the width of the tile closer to the wall. This adjustment will eliminate the need to install border tiles that are too narrow. Since the original centerline is moved exactly half the tile size, the border tile will remain uniform on opposite sides of the room. Check the layout along the other centerline in the same way.
- D-7. Spread adhesive over one quarter of the total area, starting with the quarter farthest from the door and working toward the door. Ensure that the floor surface is clean before you spread the adhesive. Spread up to the chalk lines but do not cover them. Be sure to use a notched trowel with the notch depth recommended by the manufacturer of the adhesive. Allow the adhesive to take an initial set before setting the first tile. The time required will vary, depending on the type of adhesive used.
- D-8. Start laying the tiles at the center of the room. Make sure the edges of the tiles are aligned with the chalk line. Lay rows by width, stair-stepping additional rows and ensuring that the tiles are tight against one another in a cross-grained pattern unless otherwise specified. After all of the full tiles have been laid, install the border or edge tiles around the room. To lay out a border tile, place a loose tile over the last tile in the outside row with the grains running in opposite directions (if using a cross-grained pattern). Then, take another tile and place it in position against the wall and mark a pencil line on the first tile. Cut the tile along the marked line.

D-9. After all the tiles have been installed, remove any excess adhesive using a cleaner or solvent and procedures approved by the manufacturer.

#### CERAMIC AND OTHER SPECIALTY TILES

D-10. This tile is used extensively where sanitation, stain resistance, easy cleaning, and low maintenance are desired. Types of tile include ceramic, mosaic, paver, quarry, brick-veneer, cement-bodied, marble, and other stone tiles. These can be used for both interior and exterior flooring. Tile is used on both walls and floors. Field tile is regular tile placed on all courses in the main field of an installation. Trim tile is a specially shaped tile used to border and complete the main field of tile; it is available in a wide variety of shapes, sizes, and colors to match field tile.

D-11. Tiles come with two types of finishes—glazed and unglazed. Glazed tiles are coated with a glaze before firing to give the tile color and to preserve its surface. They may be fired to a smooth or textured finish. Glazed tiles are most commonly used for walls but may also be applied to floors and countertops. They are used mainly for interiors. Unglazed tiles are fired without a glaze coating. They derive their color from the clay from which they are made. Adhesives used are Thinset or Organic Mastic. Thinset is a powdered cement-based product that is mixed with either water, a latex or acrylic additive, or epoxy. It is very versatile. Organic Mastic is premixed in a solvent or latex base. It may deteriorate if exposed to heat or water.

D-12. Grout is a powder made from sand and cement and is used to seal the cracks between the tiles. It is mixed with either water or, to increase durability, an additive. It is available in a variety of colors.

D-13. The following tools and equipment are required for installing ceramic and specialty tiles:

D-14. A *striking tool is* used to compact the grout into the joints.

- A *beating block is* a board used to even the tile surface after it has been set.
- A square-notched trowel is used to spread adhesive.
- A *pointing trowel is* used to spread adhesive in tight spots.
- A *tile cutter is* used to score the tile surface so that it can be snapped by applying pressure to the score.
- A fine file or tile stone is used to smooth rough edges after cutting tile.
- A time nipper is used to clip tile and cut irregular openings.
- A squeegee or sponge is used to remove excess grout from the tile surface.
- A sponge float or rubber-faced trowel is used to spread grout over the surface.
- An *electric tile saw is* similar to a mason saw. It is used to make clean, accurate cuts.

D-15. To lay out and install ceramic and specialty tiles, perform the following procedures:

D-16. Check the area to be tiled to determine if it is square. If the area is slightly out of square, minor changes in the layout can accommodate these conditions. If the area is seriously out of square, the process stops for any required structural repairs or surface preparation. If the framing problems are serious, it may not be possible to tile the area.

D-17. Draw the layout on paper. Layout depends greatly on the pattern desired and the type, size, and shape of the tile being used. Use as many full tiles and as few cut tiles as possible. Place cut tile away from visual focal points (doorways, thresholds, and so forth); tiles should be set symmetrically for a more attractive finish and appearance.

D-18. Place reference lines on the floor or wall. Once the layout has been established on paper, transfer it to the floor or wall. A reference line should be snapped to mark the rows of cut tiles around the perimeter. A grid of reference lines should be snapped to enclose all full tiles in sections no larger than 3 square feet.

D-19. To install tiles, first spread adhesive over a small area or section (3 x 3 feet), making sure to spread it just up to the lines so that the lines will still be visible. Align the first tile against a 90° intersection in the grid and press it gently into the adhesive. After each course of tile is applied, use a beating block to level the surface. After all the tiles are set, allow the adhesive to set the required time, according to

manufacturer's instructions. Prepare the grout and spread it over the tile surface, ensuring that the joints are filled. When the grout begins to dry, clean the tile with a damp sponge. After the grout has dried, wipe off the haze with a clean rag or towel. After the grout has completely dried and hardened (approximately 72 hours), a grout sealer may be applied.

#### SUSPENDED CEILINGS

D-20. Suspended ceilings are primarily designed for acoustical control; however, ceilings are also lowered to save on heating and air conditioning expenses; finish off exposed joints; and cover damaged plaster.

#### ACOUSTICAL TILE

D-21. Acoustical tile absorbs sound, reduces noise, reflects light, and resists flame. Its thickness ranges from 3/16 to 3/4 inch; its width from 12 to 30 inches; and its length from 12 to 60 inches. The most common size panels used are 2 x 2 feet and 2 x 4 feet.

#### **GRID-SYSTEM COMPONENTS**

- D-22. The grid-system components used in suspended ceilings include the following: the *main tee* (12-foot lengths), the *cross tee* (2- and 4-foot lengths), the *wall angle* (10-foot lengths), the *splice plate* (available in aluminum only), *suspending devices*, and *suspending wire*.
- D-23. Suspending devices include screw eyelets; suspending hooks and nails; 8d common nails or larger, driven into wood joists and bent into a U-shape; and an approved Hilti fastener for concrete or steel.
- D-24. Suspending wire includes 16-gauge anneal wire placed at 4-foot intervals and attached to suspending devices at the ceiling and to the main tees in the grid system.

#### INSTALLATION

- D-25. First, lay out the grid pattern. This is based on the ceiling's length and width at the new ceiling height. If the ceiling's length or width is not divisible by 2 feet, increase to the next higher dimension divisible by 2 feet. For example, if a ceiling measures 12 feet 7 inches x 10 feet 4 inches, the dimensions should be increased to 14 feet x 12 feet for layout purposes. Draw the layout on paper. Make sure that the main tees run perpendicular to the joists. Position the main tees so that the border panels at the room's edges are equal and as large as possible. Draw in cross tees so that the border panels at the room's ends are equal and as large as possible. Determine the number of pieces of wall angle by dividing the perimeter by 10 and adding 1 additional piece for any fraction. Determine the number of main tees and cross tees by counting them on the grid pattern layout.
- D-26. Next, establish the ceiling height. Mark a line around the entire room at the desired height to serve as a reference line. There must be a minimum of 2 inches between the new ceiling and the existing ceiling. Ensure that this line is level and marked continuously so that it meets at intersecting corners. Next, install the wall angle. Secure the wall angle along the reference line, ensuring that it is level.
- D-27. Install the suspension wire. Suspension wires are required every 4 feet along the main tees and on each side of all splices. Attach the wires to the suspending devices. The wires should be cut at least 2 feet longer than the distance between the old and new ceiling. Now, install the main tees. Main tees need to be laid out from the center to ensure that the slots line up with the cross-tee locations. Cut them where appropriate. Tees 12 feet long or less are installed by resting the ends on opposite wall angles and inserting the suspension wire. Tees over 12 feet long must be cut to ensure that the cross tees will not intersect the main tee at a splice joint. Rest the cut end on the wall angle and attach suspension wires along the tee. Make necessary splices and continue attaching suspension wires along the tee until the tee rests on the opposite wall angle. Ensure that the main tees are level and secured before continuing.
- D-28. Install the cross tees. Cut and install border tees on one side of the room. Install the remaining cross tees according to the grid-pattern layout. At opposite wall angles, install the remaining border tiles. Finally, install the acoustical panels. Install the full-size panels first. Handle panels with care and ensure that the

surfaces are kept clean from hand prints and smudges. If you are working on a large project, work from several cartons to avoid a noticeable change of uniformity. Cut and install the border panels.

#### PAINTING CEILINGS AND WALLS

D-29. The following tools and equipment are required for painting:

- Paint brushes, wall, 2 to 4 inches wide.
- Paint roller with cover.
- Paint pan.
- Stepladder.
- Paddle (stir stick).
- Rags.
- Paint, latex, flat.
- Bucket of water.

D-30. Prepare the paint for application. Remove the cover from the paint container. Remove any film layer from the top of the paint. Using the paddle (stir stick), mix the paint thoroughly, in a figure-8 motion. Scrape off and break up any unsettled matter on the bottom or lower sides of the container. Pour the paint into the paint pan until it is 2/3 full.

#### **CEILING**

D-31. Brush a narrow strip of paint around the perimeter of the ceiling along the inside edges where the wall and the ceiling meet. Using a roller, paint the remaining portion of the ceiling. Cross roll to ensure complete paint coverage without voids.

#### **WALLS**

D-32. Brush a narrow strip of paint along the inside corners of the wall and corner post. Cut in around all trim and baseboards with a trim brush. Using a roller, paint the remaining portion of the wall and corner post. The corner post may be painted with a brush. When the first coat has completely dried, apply a second coat in the same way. Ensure that the entire surface is covered and without voids.

#### **CLEANUP**

D-33. Clean paint spots from painted surfaces. Use the appropriate solvent and a clean rag. Repaint spots if necessary. Pour excess paint back into the container. Thoroughly clean brushes and rollers.

# Glossary

**AFM** Air Force Manual

irons of special form used to connect timbers or masonry Anchor

bolts which fasten columns, girders, or other members to concrete or masonry anchor bolts apron

a plain or molded finish piece below the stool of a window; covers the rough edges

of plaster

attention attn

the bevel on the top edge of a hip rafter that allows the roofing board to fit the top backing

of the rafter without leaving a triangular space between it and the lower side of the

roof covering

balloon frame the lightest and most economical form of construction. The studding and corner

posts are set up in continuous lengths from the first-floor line or sill to the roof

plate.

a small pillar or column used to support a rail Baluster

a series of balusters connected by a rail; generally used for porches, balconies, and balustrade

such

a low, flat molding band

the bottom of a column; the finish of a room at the junction of the walls and floor base

base molding the molding on the top of a baseboard

a narrow strip of board fastening several pieces together batten (cleat)

a door made of sheathing and reinforced with strips of board nailed crosswise batten door board a temporary framework for locating the corners when laying a foundation batter

a pile driven at an angle to brace a structure against lateral thrust batter pile

bd ft board feet

an inclusive term for joists, girders, rafters, and purlins beam

a filling of mortar, putty, or other substance in order to secure a firm bearing bedding molding a molding used to cover the joint between the plancier and frieze bed

(horizontal decorative band around the wall of a room); also used as a base

molding on heavy work and sometimes as a member of a cornice

a horizontal board across or around a building; usually made of a flat member and belt course

a molding

a single, vertical framework consisting of horizontal and vertical members bent

supporting the deck of a bridge or pier

bevel board (pitch

board)

a board used to lay out bevels in framing a roof or stairway

a cutout near the bottom of a rafter; fits over the rafter plate bird's mouth

driving nails so that the holes are concealed blind-nailing

lumber less than 2 inches thick board

board foot the equivalent of a board 1 foot square and 1 inch thick

the process of nailing boards on the outside studding of a house boarding in

a steel or cast-iron post to which large ships are tied bollard

bill of materials **BOM** 

pieces fitted and firmly fastened to two others at any angle; used to strengthen the braces

angle thus treated

**bracket** a projecting support for shelves or other structures

break joints to arrange joints so that they do not come directly under or over the joints of

adjoining pieces, such as in shingling and siding

**bridging** pieces fitted in pairs from the bottom of one floor joist to the top of adjacent joints

and crossed to distribute the floor load; it can also be pieces of width equal to the

joists and fitted neatly between them

building paper cheap, thick paper used to insulate a building before the siding or roofing is put on;

sometimes placed between double floors

**built-up member** a single structural component made from several pieces fastened together

**built-up timber** a timber made of several pieces fastened together, forming one piece of larger

dimension

**butt joint** a joint made by fastening two end pieces together without overlapping

**camber** the angle cut in a piece of wood (such as a joist) to match an adjacent member

(such as a rafter)

**carriages** the supports, or the steps and risers, of a flight of stairs

**casement** a window in which the sash opens on hinges

**casing** the trimming around a door or window opening, outside or inside; the finished

lumber around a post or beam

**CB** circuit breaker

ceiling narrow, matched boards; sheathing of the surfaces that enclose the upper side of a

oom

**center-hung** sash a sash hung on its centers so that it swings on a horizontal axis

**chamfer** a beveled surface cut on the corner of a piece of wood **checks** splits or cracks in a board, ordinarily caused by seasoning

**chock** heavy timber fitted between fender piles along the wheel guard of a pier or wharf

chord the principal member of a truss on either the top or bottom
 clamp a mechanical device used to hold two or more pieces together
 clapboards a special form of outside covering of a house; a type of siding

**cleats** metal arms extending horizontally from a relatively low base, used for securing

small ships, tugs, and work boats

cm centimeter(s)

collar tie usually a 1 x 4 or a 1 x 6 fastened in a horizontal position to secure the upper ends

of rafters together; placed on every other rafter system

column a square, rectangular, or cylindrical support for roofs, ceilings, and so forth combination frame a combination of the principal features of the full and balloon frames

**common rafter** a rafter which runs square with the plate and extends to the ridge

**cone** concrete

**concrete** an artificial building material made by mixing cement and sand with gravel,

broken stone, or other aggregate, plus sufficient water to cause the cement to set

and bind the entire mass

**conductors** pipes for conducting water from a roof to the ground or to a receptacle or drain;

downspout

**const** construction

**cornice** the molded project that finishes the top of the wall of a building

**counterflashings** strips of metal used to prevent water from entering the top edge of the vertical side

of a roof flashing; allows expansion and contraction without danger of breaking the

flashing

**cripple** rafter rafters that cut between valley and hip rafters

**cross** brace bracing with two intersecting diagonals; also refers to the top surface of a

piece of wood that has been cut at an angle to match an adjacent member

d penny

**DA** Department of the Army

**Dado** a rectangular, square-based groove cut across the full width of a board and

commonly used to form joints; a rectangular groove cut. Dados are used in sliding

doors and window frames.

dado joint a joint formed by two intersecting boards, meeting at right angles, and with the end

of one notched into the other for half the second board's thickness

**deadening** construction intended to prevent the passage of sound

dead load a permanent load on a building or other structure, which includes the weight of its

structural members and the fixed loads they carry

**decking** the heavy plank floor of a pier or bridge

df double flow
dn down
diam diameter

diagonal inclined member of a truss or bracing system used for stiffening and for wind-

bracing

double-hung window a window with an upper and a lower sash, each with sash cords and weights

**dovetail joint** a joint made by cutting pins the shape of dovetails, which fit between dovetails

onto another piece

**drawboard joint** a mortise-and-tenon joint with holes bored so that when a pin is driven through, the

joint becomes tighter

**drip** the projection of a window sill or water table to allow the water to drain clear of

the side of the house below it

ea each elevation

end-lap joint a joint formed at the corner where two boards lap. Each board is cut away to half

its thickness and they are halved to a distance equal to their width so that they are

flush when fitted together

F Fahrenheit

**Fascia** a flat member of a cornice or other finish; generally, the board of the cornice to

which the gutter is fastened

**fender pile** the outside row of piles that protects a pier or wharf from damage by ships

**fishplates** metal plates, fastened to each side of a butt splice for support fished joint an end butt splice strengthened by pieces nailed on the sides

filler a piece used to fill the space between two surfaces

fin finished

**flashing** the material used and the process of making watertight the roof intersections and

other exposed places on the outside of the house

**flr** floor

flue the opening in a chimney through which smoke passes

#### Glossary

flush even, adjacent structural surfaces, or those in the same plane flush joint a mortar joint formed by cutting extra mortar away from the wall

FM field manual

footing an enlargement at the lower end of a wall, pier, or column that distributes the load footing form a wooden or steel structure placed around the footing to hold the concrete to the

desired shape and size

**foundation** that part of a building or wall that supports the superstructure

frame the timber skeleton of a building and the surrounding or enclosing woodwork of

windows, doors, and so forth

**frame** box a window frame with boxes to contain the sash weights

framing the rough timber structure of a building, including interior and exterior walls, floor,

ceiling, and roof

ft foot, feet

furring narrow strips of board nailed upon the walls and ceiling to form a straight surface

upon which to lay the laths or other finish

gable the vertical, triangular end of a building from the eaves to the apex of the roof

**gal** gallon

gauge a tool used by carpenters to strike a line parallel to the edge of a board gambrel a symmetrical roof with two different pitches or slopes on each side

girder a timber used to support wall beams or joists

girt (ribboned) the horizontal member of the walls of a full or combination frame house that

supports the floor joists or is flush with the top of the joists

GL ground level

**glued joint** a joint held together with glue

**grade** the horizontal ground level of a building or structure

**groove** a long, hollow channel cut by a tool into which a piece fits or in which it works.

Two special types of grooves are the dado and the housing.

**Ground** a strip of wood assisting the plasterer in making a straight wall; also, a place to

which the finish of the room may be nailed

ha hectare

half-lap joint two pieces joined by cutting away half the thickness of each so that they fit flush

into each other

halved joint a joint made by cutting half the wood away from each piece to bring the side

flush

hanger a vertical-tension member supporting a load

**header** a short joist into which the common joists are framed around or over an opening

head jamb (yoke) the top horizontal member of a door or window frame the clear space between floor and ceiling, as in a stairway

**heel of a rafter** the end or foot that rests on the wall plate

hip rafter rafters extending from the outside angle of the plates toward the apex of the roof hip roof a roof that slopes up toward the center from all sides, necessitating a hip rafter at

each corner

**housed joint** a joint in which one piece is grooved to receive the other

housing a groove cut at any angle with the grain and part way across the piece; housings are

used for framing stair risers and treads in stringers

**hypotenuse** the length of a rafter

in inch(es)

jack rafter a short rafter framing between the wall plates; a hip rafter

jamb the side piece or post of an opening; sometimes applied to the door frame

ioists timbers supporting the floorboards

**kerf** the cut made by a saw

km kilometer(s)

**knee brace** a corner brace, fastened at an angle from the wall stud to the rafter, stiffening a

wood or steel frame to prevent angular movement

**kraftpaper** strong, brown paper used for a variety of building needs

lap joint a joint of two pieces lapping over each other

laths narrow strips which support plastering

lattice crossed wood, iron plate, or bars

**lb** pound(s)

**ledgers** the support for the second-floor joists of a balloon-frame house or for similar uses;

ribband

**level** a term describing the position of a line or plane when parallel to the surface of still

water; a tool used for testing horizontal and vertical surfaces and for determining

differences of elevation

lgth length linear feet

lintel (cap) a horizontal structural member spanning an opening and supporting a wall load lip molding a molding with a lip which overlaps the piece against which the backing of the

molding rests

live load the weight a building must bear due to the combination of furniture, other movable

objects, and the people who occupy the building

**lookout** the end of a rafter, or the construction that extends beyond the sides of a house to

support the eaves; also the projecting timbers at the gables, supporting the verge

boards

**louver** a type of window (usually in peaks of gables and the tops of towers) provided with

horizontal slats, which exclude rain and snow and allow ventilation

**lumber** sawed parts of a log such as boards, planks, scantling, and timber

m meter(s)

matching (tongue-and-

groove)

the method used in cutting the edges of a board to make a tongue on one edge and

a groove on the other

max maximum

meeting rail or check

rail

the bottom rail of the upper sash of a double-hung window

**member** a single piece complete in itself, within a structure

mi mile(s)
min minimum

miter the joint formed by two abutting pieces meeting at an angle

**mm** millimeter(s)

#### Glossary

no.

the hold, generally rectangular, for a tenon or any such hole cut into or through a mortise

piece by a chisel

a joint made by cutting a hole or mortise in one piece—and a tenon, or piece to fit mortised joint

the hole, upon the other

the construction between the openings of a window frame to accommodate two or mullion

more windows

the vertical member between two pieces of the same panel work; the vertical sash muntin

bars separating the different panels of glass

North N

noncommissioned officer in charge **NCOIC** 

the principal post at the foot of a staircase; also the central support of a winding newel

flight of stairs

nautical miles nmi number

the part of a stair tread that projects over the riser or any similar projection; a term nosing

applied to the rounded edge of a board

on center O.C. pile

metal rings vertically mounted on a plate; used for tying small vessels pad eyes

the strip or bead that separates the upper and lower sashes of a window (also called parting bead

a parting strip)

a permanent interior wall that divides a building into rooms partition

a dividing wall that separates areas of a structure but does not provide support for partition, nonbearing

the room, overhead partitions, or floor joists

a molding shaped to form a support for picture hooks, often placed on the wall at picture molding

some distance from the ceiling to form the lower edge of the frieze

concrete, or masonry supports for girders, posts, or arches; intermediate supports pier timber

for adjacent ends of two bridge spans; or a structure extending outward from the

shore into the water, used as a dock for ships

masonry supports set independent of the main foundation piers

a portion of a square column, usually set within or against a wall pilaster

long posts driven into swampy soil or wherever it is difficult to secure a firm piles

foundation upon which to lay the footing course of masonry or other timbers

large timbers or poles driven into the ground or the bed of a stream to make a firm piling

foundation

inclination or slope, as for roofs or stairs; the rise divided by the span pitch

a board sawed to the exact shape formed by the stair tread, riser, and slope of the pitch board

stairs and used to lay out the carriage and stringers

a horizontal, geometrical drawing of a building showing the walls, doors, plan

windows, stairs, chimneys, columns, and other structural components

a wide piece of sawed timber, usually 1 1/2 to 4 1/2 inches thick and 6 inches or plank

more wide

a mixture of lime, hair, and sand (or of lime, cement, and sand) used to cover plaster

outside and inside wall surfaces

horizontal piece of the walls of a frame building upon which the roof rests plate the top

plate (or seat) cut the cut at the bottom end of a rafter that rests upon the top of the plate

plot plan (site plan) a drawing showing all necessary property lines, contours, building lines, building

locations, existing or new buildings, and utility easements

**plow** to cut a groove running in the same direction as the grain of the wood

plumb cut any cut made in a vertical plane; the vertical cut at the top end of a rafter ply a term used to denote a layer or thickness of building or roofing paper (such as

two-ply or three-ply)

**porch** an exterior, ornamental entranceway

post a timber set on end to support a wall, girder, or other members of the structure pr

pair

**prefab** prefabricated

**pulley stile** the member of a window frame that contains the pulleys and between which the

edges of the sash slide

**purlin** a timber supporting several rafters at one or more points, or the roof sheeting

directly

PX post exchange qty quantity riser

rabbeta corner cut out of an edge of a piece of woodrabbet jointtwo pieces of timber, rabbeted and fit together

rafters beams that slope from the ridge of a roof to the eaves making the main body of the

roof's framework

rail the horizontal members of a balustrade or panel work

rake the trim of a building extending in an oblique line, as rake, dado, or molding

rake molding the cornice on the gable edge of a pitched roof, the members of which are made to

fit those of the molding of the horizontal eaves

return the continuation of a molding or finish of any kind in a different direction

ridge the top edge or corner formed by two intersecting roof surfaces

rise the vertical distance through which anything rises, as the rise of a roof or stair

riser the vertical board between two treads of a flight of stairs

RL random length

rm room

**roof decking** the layer of wood or plywood applied directly to the rafters, under the shingles

**roofing** the material put on a roof to make it weatherproof

rub joint a glued joint made by carefully fitting the edges together, spreading glue between

them, and rubbing the pieces back and forth until they adhere

rubble roughly broken quarry stone

rubble masonry uncut stone, used for such things as rough work, foundations, and backing run the

horizontal length of a piece, such as a rafter, when it is in position

S switch

saddle board the finish of the ridge of a pitched roof house; sometimes called comb board

sash the framework that holds the glass in a window

sash lift a metal hook, bar, or plate attached to a sash to enable lifting and lowering of the

window

sawing plain lumber sawed regardless of the grain, the log simply squared and sawed to

the desired thickness

scab a short piece of lumber used to splice or prevent movement of two other pieces

scaffolding or staging a temporary structure or platform enabling workmen to reach high places

scale a short measurement used as a proportionate part of a larger dimension; the scale

of a drawing is frequently expressed as 1/4 inch = 1 foot

scantling lumber with a cross section ranging from 2 by 4 inches to 4 by 4 inches.

scarfed joint a timber spliced by cutting various shapes of shoulders or jogs which fit each other

scarfing a joint between two pieces of wood allowing them to be spliced lengthwise scotia a hollow molding used as part of a cornice and often under the nosing of a stair

tread

scribing marking a piece of wood to provide for fitting one of its surfaces to the irregular

surface of another

section a drawing showing the type, arrangement, and proportions of the various parts of a

structure. It is assumed that the structure is cut by a plane, and the section is the

view gained by looking in one direction.

**Shakes** imperfections in timber caused by high winds or imperfect growth conditions

**sheathing** wallboards or roofing boards; generally applied to narrow boards laid with a space

between them, according to the length of a shingle exposed to the weather

sheathing paper (building paper)

the paper used under siding or shingles to insulate the house

shingles thin, oblong pieces of wood or other material, thinner at one end, used for covering

roofs or walls

siding the outside finish between the casings

sills the horizontal timbers of a house which either rest upon the masonry foundation or,

in the absence of such, form the foundation

sizing working material to the desired size; a coating of glue, shellac, or other substance

applied to a surface to prepare it for painting or other finishing

sleeper a timber laid on the ground to support a floor joist sole the horizontal member on which the studs bear

spac spacing

**span** the distance between the bearings of a timber or arch

**specifications** written or printed directions regarding the details of a building or other

construction

spirit level an instrument for measuring the exactness of the horizontal or vertical position of a

building or structure member

splice joining of two similar members in a straight line

sq cmsquare centimeter(s)sq ftsquare foot, feetsq insquare inch(es)sq kmsquare kilometer(s)sq msquare meter(s)sq misquare mile(s)sq ydsquare yard(s)

square a tool used by carpenters to obtain accuracy; a term applied to a surface area of 100

square feet

stairs box those built between walls, usually having no support except the walls

standing finish term applied to the finish of the openings and the base and all other interior finish

work

**stringer** a long, horizontal timber in a structure supporting a floor

**stucco** a fine plaster used for interior decoration and fine work; also used for rough

outside wall coverings

stud an upright beam in a building framework

**studding** the framework of a partition or the wall of a house; usually referred to as 2 x 4s

**subfloor** a wood floor laid over the floor joists on which the finished floor is laid

threshold the beveled piece over which the door swings; sometimes called a carpet strip tie beam (collar beam) a beam so situated that it ties the principal rafters of a roof together and prevents

them from thrusting the plate out of line

timber lumber with a cross section more than 4 by 6 inches, such as posts, sills, and

girders

tin shingle a small piece of tin used for flashing and repairing a shingle roof

TM technical manual theater of operations

toenailing driving a nail, spike, or brad at an angle into the end of one piece of wood to fasten

it to a second piece; avoids having the nails show above the surface

top plate a piece of lumber supporting the ends of rafters to the weather a term applied to the

projection of shingles or siding beyond the course above

**TRADOC** United States Army Training and Doctrine Command

**Tread** the horizontal part of a step

trim a term sometimes applied to exterior or interior finished woodwork and the finish

around openings

**trimmer** the beam or floor joist to which a header is framed

**trimming** putting the inside and outside finish hardware on a building

truss structural framework of triangular units, used in place of rafters, for supporting

loads over long spans

US United States

USAES United States Army Engineer School

valley rafter rafters extending from an inside angle of the plates toward the ridge or centerline

of the house

valleys the internal angle formed by the two slopes of a roof

**verge** boards the boards that serve as the eaves' finish on the gable end of a building

**vestibule** an entrance to a house; usually enclosed

W watts
WH wall hung

wainscoting matched boarding or panel work covering the lower portion of a wall

wale a horizontal beam

wash the slant on a sill, capping, and so forth, to allow water to run off easily

water table the finish at the bottom of a house that carries water away from the foundation wharf a structure that provides berthing space for vessels, to facilitate loading and

Glossary

discharge of cargo

wind

a term used to describe the surface of a board when twisted (winding) or when resting upon two diagonally opposite corners, if laid upon a perfectly flat surface a piece of seasoned wood, made the size of a brick, and laid where necessary to

wooden brick

provide a nailing hold in masonry walls

# References

### **SOURCES USED**

These are the sources quoted or paraphrased in this publication.

FM 5-742. Concrete and Masonry. 14 March 1985. (superseded by TM 3-34.44)

FM 5-480. Port Construction and Repair. 12 December 1990. (superseded by TM 3-34.73)

TM 5-302-2. Army Facilities Components System: Design. 28 September 1973.

TM 5-704. Construction Print Reading in the Field (AFM 85-27). 2 January 1969.

#### **DOCUMENTS NEEDED**

These documents must be available to the intended users of this publication.

DA Form 2028. Recommended Changes to Publications and Blank Forms.

DA Form 2702. Bill of Materials.

#### READING RECOMMENDED

These readings contain relevant supplemental information.

FM 5-412. Project Management. 13 June 1994.

TM 5-303. Army Facilities Components System: Logistic Data and Bills of Materiels. 1 June 1986.

This page intentionally	y left blank.	

# Index

1		
Α	bracing, 10-3, 10-4	beams, 5-9
abutment,	construction, 10-6-10-10	cardboard, 5-1
construction of, 10-7	intermediate supports, 10-2-	column, 5-9
footing type, 10-2	10-4	design, 5-1
pile type, 10-2	multispan, 10-1	footing, 5-2
architectural symbols, 1-1,	nonstandard, 10-1	foundation, 5-2
B-3-B-4	single-span, 10-1	girder, 5-9
asbestos-cement roof. See	tread, 10-13	removal, 5-10
roof, asbestos-cement.	trestle-bent, 10-4, 10-8	sheathing, 5-4
asphalt. See roof, asphalt.	building,	shoe plates, 5-6
auger bit, 2-9	foundation, 4-7–4-9	spreaders, 5-6
В	layout, 4-1–4-7	stairs, 5-10
batter boards,	lines. See lines, building.	studs, 5-5
construction of, 4-1, 4-2, 4-4	load area, 6-9, 6-11- 6-13	tie wires, 5-2, 5-7
locating, 4-3	materials, 2-3-2-6	wales, 5-6
staking, 4-1, 4-2, 4-3	paper, 2-4, 6-27, 6-40-6-43,	wall, 5-4
bent,	6-45, 7-19	wood, 5-1
pile, 10-3, 11-14	squaring foundation lines.	connections, 6-4-6-8
pile-bent pier, 10-3	See lines, squaring.	conversion tables, A-1
trestle, 10-3, 10-4, 10-8	staking out, 4-3	corbel, 10-3
beveled siding, 6-43	tools, 4- 1	corner fenders. See fender,
bill of materials (BOM), 3-1–	wood frame, 1-12–1-18	corner.
3-4	built-up material, 6-9, 6-13,	cord, 4-3
board-feet computation, 2-6	7-21, 7-26–7-28	corrugated fasteners, 2-6,
bollard, 11-10, 11-13	butt joint. See joint, butt.	2-15, 6-4, 8-14, 8-15
bolt.	С	corrugated metal, 6-43, 7-10
carriage, 2-12	camel (floating logs), 11-9	coursed rubble, 4-7
expansion, 2-14	canopy, 8-16	crane, 2-3, 11-2
machine, 2-13	cant hook, 11-2	crawl space, 6-11, 6-48, 6-50
stove, 2-14	carpenter's level, 4-1, 4-4, 4-5	crib pier, 10-4
BOM. See bill of materials	ceiling, 6-46, 9-6, 9-10–9-12,	curb, 10-10, 10-13, 11-7
(BOM).	D-3-D-4	cut of roof, 7-3
bracing,	centerline measurement, 7-13,	
common types, 6-38	10-4, 10-7	D
cut-in, 6-39	chocks, 11-8, 11-19	dado, 8-6
diagonal sheathing, 6-39	chord,	deck, 6-19, 7-16, 7-22, 10-8,
diaphragm, 10-4	bottom, 1-16, 7-9	10-10, 10-11, 11-1, 11-7, 11-8
knee. See knee braces.	member, 7-9	details, 1-1, 1-5, 1-9, 1-12,
let-in, 6-39	top, 7-9	1-15, 1-17
longitudinal, 10-4, 10-10,	cleats, 5-9, 6-19, 11-12	door,
11-14	coal-tar pitch, 7-26, 7-28	batten, 8-1
transverse, 10-3, 10-4,	collar beam. See rafter, collar	butt, 8-8
10-10	beam.	casing, 8-2, 8-3, 8-5, 8-6,
walls. See wall, bracing.	collar tie, 7-9, 7-11	8-11
bridge,	column foundation, 4-7, 6-17	construction 8-2 8-5

abutments, 10-1

concrete forms,

exterior, 8-1–8-3, 8-6, 8-8	footing, 5-2—5-3, 10-1	half-lap splice, 6-6
frame, 8-2, 8-3-8-8	form,	miter butt, 6-6
hasty construction, 8-2	beam. See concrete forms,	oblique butt, 6-6
hinges, 8-5, 8-8	beams.	plain lap joint, 6-6
interior, 8-1–8-3, 8-6, 8-8	column. See concrete forms,	joists,
jamb, 8-3–8-5–8-6, 8-8	columns.	ceiling, 6-46
job-built, 8-1–8-2	footing. See concrete forms,	reinforced, 6- 19
layout calculations, 8-4	footing.	
ledgers, 8-2	girder. See concrete forms,	K
lock installation, 8-12	girder.	knee braces, 6-1, 7-10, 7-12
mill-built, 8-2	removal, 5-10	8-16, 10-14
screen. See screen, door.	stairs. See concrete forms,	kraft paper, 7-21
sill, 8-1, 8-3, 8-5, 8-13	stairs.	
stop, 8-4, 8-5, 8-10	wall. See concrete forms, wall.	L
strike plate, 8-12		laminated deck, 10-12
	foundation, 4-4, 4-5	lap joint, 6-6
swing, 8-8	frame,	layout instruments, 4-1
trim, 8-11	construction, 2-3	layout techniques, 4-1
t-strap hinges, 8-2	expedient, 6-4	ledger board, 6-11
drawings,	heavy, 6-3	ledger plate, 6-16
wood framing, 1-12–1-18	light, 6-1	line conventions, 1-2
working, 1-5–1-9	salvaged, 6-4	lines,
driftpins, 2-5, 2-15, 10-10,	stairway, 6-50	building, 1-3, 4-1
11-6	wood substitute, 6-4	extending, 4-5-4-7
drop siding, 2-4, 6-43	frame construction methods,	squaring, 4-6
E	built-in-place method, 2-1	logger's tool, 11-2
elevation, 1-6	cutting party, 2-1	lumber,
end dam, 10-2, 10-7, 10-10	marking pattern, 2-2	computation, 2-6
excavation, 4-1, 4-3, 6-4	panel method 2-1, 2-2	grade, 2-4
extending lines. See lines,	template, 2-2	size, 2-4
extending.	furring strips, 9-4, 9-11	types, 2-2
exterior walls. See wall,	G	
exterior.	girder, 5-9, 6-10–6-19	M
	girt, 6-34	manpower estimates, C-1-
F	giit, 0-0 <del>-</del>	C-11
felt, 6-40, 7-17, 7-18, 7-19,	н	material,
7-21, 7-25, 8-2	half-lap splice joint. See joint,	bill, 3-1–3-4
fender,	half-lap splice	conventions, 1-2
corner, 11-10	handrail, 10-14	estimate list, 3-2–3-4
floating log. See camel	horizontal wood siding, 6-36	takeoff list, 3-1
(floating logs).	Ç.	mission tile, 7-29
pile, 11-1, 11-7	I	molding,
fiberboard, 9-1	interior wall, 9-1	base, 9-8
fishplate, 6-8, 6-9	iron stirrup, 6-20	ceiling, 9-11
flashing, 6-47, 7-18		mortise, 8-8, 8-9, 8-12
floor,	J	
concrete, 6-28	jack rafters,	N
finish, 6-14, 6-27–6-28	cripple jack, 7-3	nails, 2-6
joists, 6-1, 6-8, 6-11, 6-19,	hip jack, 7-3	<b>D</b>
6-20	valley jack, 7-3	<b>P</b>
openings, 6-25, 6-26	joint,	pad eye, 11-12
subfloor, 6-1, 6-14, 6-26	butt, 2-15, 6-5, 6-17, 8-12	partition, 6-28, 11-2
wood, 6-27	cross lap, 6-6	pile,
flooring, 6-19, 10-12		

abutment. See abutment,	rolled roofing, 7-16	shoe plates, 5-4
pile type.	roof,	sidewalk, 10-14
bearing, 11-1	aggregate, 7-21	siding 2-4, 6-4, 6-33, 6-43-45
bent. See bent, pile.	asbestos-cement, 7-16	sill,
bracing, 11-6	asphalt, 7-16, 7-25	box, 6-1
capping, 11-5	asphalt shingle, 7-22	built-up, 6-0
clusters, 11-10	binder, 7-21	bracing frame, 6-9
cutting, 11-5	built-up material, 7- 21	joining to joists, 6-16
dolphins, 11-11	coal-tar, 7-26	t-sill, 6-9
fender, 11-1, 11-8	covering, 7-16	types, 6-9
mooring, 11-2, 11-0	deck, 7-16	sisal kraft paper, 7-21
steel, 11-10	flashing, 7-8	site plans. See plans, site.
straightening, 11-3	hip, 7-18	sole, 2-3
king, 11-9, 11-11	metal, 7-30	spanish tile, 7-30
pitch, 7-8	opening, 7-15	splice,
plain lap joint. See joint, plain	rafter, 7-2	bend resistant, 6-8
lap.	replacement, 7-22	butt, 6-8
plans,	slate, 7-29	compression-resistant, 6-8
floor, 1-1, 1-7–1-9	tile, 7-29	tension-resistant, 6-8
plot, 1-5		
site, 1-5	truss, 7-9	squaring lines,
plumbing posts, 6-35	valley, 7-18	diagonal method, 4-7
plywood sheathing, 6-39	wood-shingle, 7-30	6-8-10 method, 4-6
purlin, 7-10	rosin paper, 7-21	split ring, 2- 16
pa,	S	spreaders, 5-2, 5-6
R	saddle flashing, 7-18	stairway,
rabbet, 8-4	sash, 8-14	design, 1-12
rafter,	scab, 6-8,	details, 1-12
collar beam, 7-4		forms, 5-10
common, 7-2	screen,	framing, 6-51
hip, 7-2	door, 8-15	riser, 6-53
jack, 7-4	joints, 8-15	stringers, 6-45
layout, 7-4	window, 8-12, 8-15	tread, 6-53
plate, 1-16	screws,	stovepipes, 6-47
trussed, 1-16, 1-17, 1-18,	lag, 2-11	straightening walls, 6-35
7-9	sheet-metal, 2-12	stringer, 10-1, 11-7
types, 7-2	sizes, 2-10	stringpiece, 11-8
valley, 7-3	wood, 2-10	studs, 5-5
reroofing,	sheathing, 2-4, 5-2, 5-4, 5-6,	substructure, 10-1
applying shingles, 7-22	5-7	superstructure, 10-10
asbestos-cement, 7-30	sheetrock, finishing, 9-7	
asphalt shingle, 7-22	<b>.</b>	T
built-up roofs, 7-26	patching, 9-8	tile, 7-29
metal, 7-30	placing, 9-6	toothed rings, 2-17
preparation of deck, 7-22	tools, 9-5	top plate, 6-23, 6-34
roll roofing, 7-25	shingle,	t-post, 6-31
slate, 7-29	applying, 7-22	tread, 6-53, 10-10
tar pitch, 7-28	asbestos-cement, 7-16	truss,
tile, 7-29	asphalt, 7-16	assembly, 7-11
wood-shingle, 7-30	hip and valley, 7-18	installation, 7-14
_	laying, 7-17	placement, 7-14
retaining wall, 10-8	standard weight, 7-22	support, 7-10
revetment, 10-8	thick butt, 7-22	t-sills, 6-9
riser, 1-9, 5-10, 6-53	wood, 7-30	

exterior, 6-40 double-hung, 8-12 valley jack, 7-3 frame, 6-28 frame, 8-9, 8-13 ventilators, 6-48 partitions, 6-29 glass, 8-13 sheathing, 6-39 hasty construction, 8-13 W siding, 6-43 in-swinging, 8-12 wales, 11-9 straightening, 6-37 out-swinging, 8-12 wall, windows, sash, 8-14 bracing, 6-38 casement, 8-12 screen. See screen, window.

Index-4

By order of the Secretary of the Army:

RAYMOND T. ODIERNO General, United States Army Chief of Staff

Official:

**ĠERALD B. O'KEEFE**Administrative Assistant to the Secretary of the Army 1326112

### **DISTRIBUTION:**

Active Army, Army National Guard, and United States Army Reserve: Not to be distributed; electronic media only.

PIN: 100521-000